

GB-250

Great Basin™ High Efficiency Grease Interceptor Technical Data
 Submittal | Special Precautions | Specifications | Installation | Application Specific Details

STANDARD: 4' plain end inlet/outlet | Capacities - Liquid: 275 gal. (1041 L); Grease: 1076 lbs. (488.1 kg) (47.4 gal/558 L); Solids: 105 gal. (397.5 L); Highway traffic load rated, bolted, gas/water tight composite covers, (6,000 lbs.)

OPTIONS:

<input type="checkbox"/> 4' Male Thread Inlet/Outlet	<input type="checkbox"/> High Water Anchor Kit
<input type="checkbox"/> 6' Plain End Inlet/Outlet	<input type="checkbox"/> Teleside Risers
<input type="checkbox"/> 6' Male Thread Inlet/Outlet (stainless steel)	<input type="checkbox"/> LR24 (x2) 5' - 23"
<input type="checkbox"/> Pedestrian Rated Covers - 2,000 lbs.	<input type="checkbox"/> LR24 (x2) >23" - 38"
<input type="checkbox"/> H2O Load Rated Pickable Cast Iron Covers	<input type="checkbox"/> LR24 (x4) >38" - 43"
<input type="checkbox"/> Integral Membrane Clamping Collar Kit	<input type="checkbox"/> LR24 (x2) + LR24 (x2) >43" - 58"
<input type="checkbox"/> Pumpout Port (Large)	<input type="checkbox"/> LR24 (x4) >58" - 72"

APPROVAL:

Signature: _____
 Date: _____
 Company: _____
 Specifying Engineer: _____
 Engineering Firm: _____

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 1 of 7

SPECIAL PRECAUTIONS

For All Schier Grease Interceptor Installations

Installation Instructions
 Installation instructions and additional components are located inside the Interceptor. Read all instructions prior to installation. This interceptor is intended to be installed by a licensed plumber in conformance with all local codes.

High Temperature Kitchen Drain
 If water is entering the interceptor at excessive temperature (over 140° F), a drain water tempering valve (DWT) must be installed. Most state and local plumbing codes prohibit water above 140° F being discharged into the sanitary sewer. Water above 140° F will weaken or deform PVC Schedule 40 pipe, poly drainage fixtures like interceptors and erode the coating of cast iron (leading to eventual failure). Failure to follow this guidance voids your warranty.

When Installing Interceptor Inside
 If your dishwashing sink(s) discharges into a floor drain/sink (drain), you must regulate the flow into the drain to avoid an overflow of water onto the kitchen floor. This can be done by installing a valve or flow restriction cap on the sink piping that discharges into the drain. See drawing below for guidance. For detailed guidance on indirect connections, go to http://webtools.schierproducts.com/Technical_Data/Indirect_Connections.pdf

Hydrostatic Slabs (or Pressure Slabs)
 When installed under a hydrostatic slab (slab designed to withstand upward lift, usually caused by hydrostatic pressure) interceptor must be enclosed in a watertight concrete vault. Failure to follow this guidance voids your warranty.

ANCHOR KIT INSTALLATION
 Stainless steel anchor kit is recommended for installation in high water table conditions to prevent float out. Necessity to be determined by specifying engineer. Hold down force achieved by ballast weight acting on Anchor Plate.

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 2 of 7

SPECIFICATIONS

NOTES:

- 4' plain end inlet/outlet.
- Unit weight - w/composite covers: 290 lbs.; w/cast iron covers: 340 lbs. (For wet weight add 2290 lbs.)
- Maximum operating temperature 140° F continuous
- Capacity - Liquid: 275 gal.; Grease: 1076 lbs. (47.4 gal.); Solids: 105 gal.
- Built-in flow control.
- For gravity drainage applications only.
- Do not use for pressure applications.
- Cover placement allows full access to tank for proper maintenance.
- Vent not required unless per local code.
- Engineered inlet and outlet diffusers are removable to inspect/clean piping.
- Integral air relief / Anti-siphon / Sampling access.

DIFFUSION FLOW TECHNOLOGY
 The inlet diffuser splits influent into three paths, creating laminar flow and utilizing the entire liquid volume of the tank for efficient grease separation. The calibrated openings greatly reduce effluent turbulence. The effluent enters the main chamber without disturbing the existing grease or sediment layers.

INLET AIR RELIEF / ANTI-SIPHON
 The integral air relief / anti-siphon in the top of the outlet diffuser allows pressure stabilization in the unit during operation. The bottom of the outlet diffuser allows only effluent which is free of grease to exit the tank. It can easily be attached to any of the three outlets provided to ease job site piping layouts.

ENGINEER SPECIFICATION GUIDE
 Schier Great Basin™ grease interceptor model # GB-250 shall be lifetime guaranteed and made in USA of seamless, rotationally-molded polyethylene. Interceptor shall be furnished for above or below grade installation. Interceptor shall be certified to ASME A12.14.3 (Type C) and CSA B481.1 with field adjustable riser system, built-in flow control, built-in test caps and three outlet options. Interceptor flow rate shall be 100 GPM. Interceptor grease capacity shall be 1076 lbs. Cover shall provide water/gas-tight seal and have minimum 18,000 lbs. load capacity.

CERTIFIED PERFORMANCE
 Great Basin hydrochemical grease interceptors are third party performance tested and listed by IAPMO to ASME A12.14.3 and CSA B481.1 grease interceptor standards and greatly exceed requirements for grease separation and storage. They are compliant to the Uniform Plumbing Code and the International Plumbing Code.

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 3 of 7

INSTALLATION (1 of 3)

WARNING! DO NOT AIR TEST UNIT OR TELEPHONE CORDER SYSTEM Doing so may result in property damage, personal injury or death.

LEAK/SEAL TESTING
 Cap/plug all base unit plumbing connections and remove covers. Fill base unit testing fill with water to just above the highest connection. For riser system testing (if required) fill with water to finished grade level. CAUTION: There must be supported below the filling with water to prevent tipping. Inspect unit, connections and all gaskets and clamps (if applicable) for leaks. Check water level at specific time intervals per local code.

GENERAL INSTALLATION INSTRUCTIONS
 Schier grease interceptors are manufactured with an internal flow control system. They do not require an external flow control system or air intake vent. Schier grease interceptors are not to be installed in any other manner except as shown. Consult local codes for separate trapping requirements, clearance locations and additional installation instructions.

- The flow control plate is not installed on this unit. When the unit is installed 15 feet or more below the fixture that flows into the unit, or a high flow/increased head pressure condition exists (causing a flow rate above 100 GPM), install the inlet diffuser flow control plate to maintain proper flow rate.
- Set unit on level solid surface as close as possible to fixture.
- Connect outlet diffuser to the desired outlet (A, B, C). Unit is shipped with the outlet diffuser in location B and sealing caps on locations A and C.
- Connect inlet and outlet drainage lines to unit. Mechanically couple pipes to unit. Do not seal with sealant.
- For units with cast iron covers, remove retainer clips prior to burial. NOTE: Do not install below a hydrostatic slab.

BELLOW GRADE INSTALLATION INSTRUCTIONS
EXCAVATION

- Surrounding soil must be undisturbed soil or well compacted engineering fill.
- Width and length of excavation shall be a minimum of 12" greater than the tank on all sides and depth shall be 6" deeper than tank bottom.
- Set the tank level on a 6" deep layer of well-packed crushed aggregate material and connect waste piping per General Installation Instructions.

BACKFILL

- Preparation of sub grade per geotech recommendations.
- Stabilize and compact sub grade to 90% proctor.
- Fill unit with water before backfilling to stabilize unit and prevent float-out during backfilling. Secure covers and risers (if necessary) to the unit.
- Backfill around tank using crushed aggregate approximately 24" size rock or as req. with no fines, or flowable fill. The rest compact backfill around units.

FINISHED CONCRETE SLAB
 Slab must extend 18" minimum outside the unit footprint.
 Pedestrian traffic or greasepass access: 4" Thick reinforced concrete slab required.
 Vehicle traffic: Minimum 8" Thick concrete slab with rebar required. Finish thickness of concrete around cover to be determined by specifying engineer. If traffic loading is required the concrete slab dimensions shown are for guidance purposes only. Concrete to be 28 day compressive strength to 4,000 PSI. Use NO. 4 rebar (1/2" grade 60 steel per ASTM A616) connected with tie wire. Rebar to be 2'-0" from edge of concrete and spaced in a 12" grid with 4" spacing around access openings.

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 4 of 7

INSTALLATION (2 of 3)

TELESIDE RISER (24 SERIES)
INSTALLATION SUBINSTRUCTIONS
 Teleside risers are 7/8" NPT riser (included), marker (included), tape measure and drill with 1/2" chuck. U-jack, circular saw or reciprocating saw will be needed if risers need to be cut.

NOTE: To remove a component or adjust its position, the Upper Band Clamp needs to be loosened or removed using nut driver bit. Loosened clamps should be re-tightened to 5 - 8 ft lbs. of torque (same as a rubber no-hub coupling). The Lower Band Clamp is factory set and should not be adjusted or removed.

Riser Assembly Instructions/Steps

- Set unit so the pipe connections line up with job site piping and measure riser height needed from top of cover to finished grade. See Table 1 to select risers needed to meet or to finished grade.
- Remove covers from adapters. Remove adapters from main unit. On a level surface, pre-assemble the risers and adapters, adjusting the components upwards or downwards to achieve the riser height needed. Make sure to maintain minimum and maximum insertion depths as shown in Figure 2. If components are too long, make a circular line around the sidewall with marker and cut with a power saw. The lowest cut line on the riser assembly will be 6" beyond the riser height needed to allow for ideal insertion depth (See Figure 1). An alignment mark should be drawn 2" beyond the riser height needed which will align with the top of the base unit gasket. DO NOT cut the alignment mark. The Adapters and risers should sit level with each other. Tighten upper clamps to keep riser/adaptor assembly from shifting. Make alignment marks on the sidewalls at the top of all riser gaskets to aid final assembly.
- IMPORTANT!** Before the next step, make sure both diffusers are installed inside the main unit at the appropriate locations. Check if there needs to be any flow control adjustment at the inlet diffuser (see general installation instructions).
- Take apart riser assembly and clean all sidewalls and inside of gaskets to remove dust/debris. Install components into the main unit starting from the lowest riser and work your way up to finished grade. Ensure that riser will not interfere with diffuser allowing 1" clearance. Maintain minimum and maximum insertion depths for all components (see Figure 2). Tighten Upper Clamps to specified torque after correct positioning components. Riser assembly may need to be supported during backfill.
- If fitting of the adapter is required to be flush with grade, do so AFTER all clamps have been adjusted with riser (a factor in a vertical and level position. Tiling is done using gasket flexibility. Tiling before tightening clamps may ruin perfect gasket seal. Schier recommends filling only the adapter versus the entire riser assembly to make sure your riser height and proper tank access is maintained.
- If riser height conditions change after completing above steps, there may be room for adjustment. As long as minimum and maximum insertion depths are maintained (See Figure 2) the adapters/risers can be adjusted/out as many times as necessary. When riser system installation is complete, see Leak/Seal Testing procedure if required (p. 5 of 7).

ANCHOR KIT INSTALLATION
 Stainless steel anchor kit is recommended for installation in high water table conditions to prevent float out. Necessity to be determined by specifying engineer. Hold down force achieved by ballast weight acting on Anchor Plate.

Slide Anchor Hook over tie down point on end wall and bolt to Anchor Strap. Bolt Anchor Strap to Anchor Plate using provided stainless steel hardware. If required, Anchor Plate may be bolted to concrete slab using provided holes.

Riser Height Needed	Risers Required
0 - 3'-2"	None (use adapter)
5' - 23"	SR24 (x2)
>23" - 38"	LR24 (x2)
>38" - 43"	SR24 (x4)
>43" - 58"	SR24 (x2) + LR24 (x2)
>58" - 72"	LR24 (x4)

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 5 of 7

INSTALLATION (3 of 3)

EXPANDING GREASE CAPACITY
 Multiple grease interceptor configurations must be piped as shown to ensure the system works properly as designed. For below grade installations, all units must be level in the excavation pit. Hybrid systems combining parallel and series installations are available per written approval from Schier.

All inlet manifolds, outlet manifolds, piping between units and two-way cleanout tees by others.

Series Installation of Multiple Grease Interceptors
 For lower flow rates and higher grease storage requirements.

For below grade installations it is recommended to install a two-way cleanout tee extended to finished grade before the inlet of the first unit, after the outlet of the last unit and in between units (if there is a long run of pipe between units) for line cleaning purposes.

NOTE: When the flow control plate is required, it should only be installed on the first unit in the series.

Parallel Installation of Multiple Grease Interceptors
 For flow rates above 100 GPM and higher grease storage requirements.

Units must be equally spaced to ensure equal effluent flow distribution.

For below grade installations it is recommended to install a two-way cleanout tee extended to finished grade before and after each unit for line cleaning purposes.

Flow Splitter™ (FS-DU, FS-TRIO, FS-QUAD) sold separately.

MODEL NUMBER: GB-250
DESCRIPTION: Polyethylene Grease Interceptor 100 GPM - 275 gallon capacity
PART #: 4055-001-XX **DRAWN BY:** B. Karner **DATE:** 10/08/2016 **REV:** 3 10/13/2017 **SDC:**

1800 Woodland Road | Schwanerville, CO 80111 | Tel: 919-491-8900 | Fax: 919-491-8999 | www.schierproducts.com | Copyright 2017 Schier, All Rights Reserved

057-0870-02 page 6 of 7

GROUP

CKE GROUP

INCORPORATED
 engineering • architecture • planning

15500 NEW BARN ROAD
 SUITE 106
 MIAMI LAKES, FLORIDA 33014

PHONE: (305) 588-4124
 FAX: (305) 826-0619
 EB#000432

SEAL
 EDUARDO L. CARCACHÉ
 CIVIL ENGINEER-PE 31914
 ANA A. GONZALEZ VALDEZ
 ARCHITECT-AR 97769

NO.	DATE	DESCRIPTION
Δ	03-02-18	
Δ	07-24-18	(NEW SHEET)
Δ		
Δ		
Δ		
Δ		
Δ		
Δ		

CONTRACT DATE: _____
 BUILDING TYPE: CUSTOM
 PLAN VERSION: 1
 SITE NUMBER: 309797
 STORE NUMBER: 420630

TACO BELL

5070 W. Atlantic, Blvd.
 Delray Bch., FL

TACO BELL

OPEN KITCHEN

DELRAY BEACH SOL

GREASE TRAP
 DETAILS

GT-1

Plot Date: 07-26-2018