



**ADDENDUM No. 2
(Revision D – Client Comments)
to
PERMIT DOCUMENTS
for
Taco Bell – Delray Beach
5075 Atlantic Ave
Delray Beach, FL 33484**

August 17, 2018

-
- A. The original permit documents for the above referenced project are hereby amended as noted in Addendum No. 2.
 - B. This Addendum supersedes and takes precedence over information provided prior to the date of this Addendum.
 - C. This Addendum includes two (2) 22" x 34" drawings.

Revisions to Drawings:

Sheet A3.0

- 1. Per client request, the hood exhaust was moved farther south away from the solar water heater collectors.

Sheet A4.0

- 1. All building signage located on the West facade was removed from the scope of work.
- 2. A 3'-0" high painted water table was added to the base of all walls finished with Hardie fiber cement panels. Finish #8 was added to the Exterior Finish Schedule to denote this.
- 3. The Signage Schedule was updated to reflect the current building signage.
- 4. Sheet Note #7 was revised to indicate that the tower installation is entirely by the G.C.
- 5. The reveals in the Trespa entry portal were shifted to align with the portal opening.
- 6. The service door is to be painted SW7026, Griffin.

Sheet A4.1

- 1. All building signage located on the East facade was removed from the scope of work.
- 2. A 3'-0" high painted water table was added to the base of all walls finished with Hardie fiber cement panels. Finish #8 was added to the Exterior Finish Schedule to denote this.
- 3. A new surface-mounted cabinet sign was added to the tower on the North façade.

Sheet A5.0

- 1. The wall-mounted ladder and access panels in the CMU for the integral signage were removed from the scope of work.

Sheet A5.2

- 1. The notes in Section B/A5.2 were revised to indicate that the tower installation is entirely by the G.C.

Sheet A5.3

1. The notes in Section A/A5.2 were revised to indicate that the tower installation is entirely by the G.C.
2. The Bottom of the Entrance Soffit denoted in Section C/A5.3 was revised to 18'-4" AFF.

Sheet M2.0 & M2.1

1. The hood exhaust was shifted to the south away from the solar water heater collectors on the roof.

END OF ADDENDUM No. 2

