

EXHIBIT “D”

SUPPLEMENTAL PROJECT INFORMATION

The following information is clarification to the plans and specifications and takes priority over them. Any questions regarding the plans and specifications should be directed to the designated Owners Project Manager.

1. Owner's sign installer shall install all building signage and site signage and building canopies. GC will coordinate his work with sign installer. GC's electrician shall provide power to all sign locations on building.
2. GC to remove and dispose of existing clearance bar in drive thru lane.
3. GC to provide new foundation for new clearance bar and OCU canopy's.
4. Owners Sign installer to install new clearance bar and OCU canopy's.
5. GC to extend electrical feeds from existing OCU pedestal to new OCU
6. GC to remove and dispose of existing red parapet light band. Owners sign installer will install new LED light band and transformers. GC's electrician responsible for final connections to light band.
7. GC to supply power, conduit, and appropriate wall backing for owner supplied TV's.
8. Dining Room and restroom finishes will be installed as per décor plans. GC is responsible for supplying and installing all wall finishes; wall tile, chair rail, windowsills, wainscot, and owner supplied wall graphics.
9. GC is responsible for grouting the top of filled core holes.
10. GC will supply & install all restroom fixtures: grab bars, mirrors and recessed waste container in restrooms. (Soap dispensers supplied by owner and installed by GC) Hand dryers supplied by GC and installed by GC.
11. Landscaping by owner. Rough grading in all areas of any applicable excavation work by GC. GC to remove all excavation spoils from site prior to landscape work.
12. Nichiha Fiber Cement Panels: Contact Chris Tate – National Account Manager for Nichiha USA for Panel for specification, installation, pricing information. Phone: 404.538.1261 email: ctate@nichiha.com
13. GC to ensure all parking lot lights are working on day 1 of construction. If any repairs are needed, GC to report and provide a change order to rectify.
14. GC to ensure all floor drains are protected from construction debris. GC to flush or camera all drain lines to insure there are no underground issues. If any are discovered, GC to report and provide change order.