

# North Brandywine Contractors

**PMB # 268 – 1554 Paoli Pike, West Chester, Pa 19380**

**Ph: (610) 496-3379 F: (610) 429-9033 Em: Alex2Alex@aol.com HIC Contractor # Pa-134114**

January 31, 2022

Todd Markevicz, P.E., Owner / Member  
APD ENGINEERING & ARCHITECTURE, PLLC  
615 Fishers Run  
Victor, New York 14564

T: 585.742.0222  
M: 585.414.3586  
E: tmarkevicz@apd.com

Subject: Asbestos Sampling – NBC Proposal 211231-AI-01  
Burger King # 4651 - 1239 N Charlotte Street - Pottstown, Pa

As per your request, NBC/North Brandywine Contractors, (NBC) provided you with an EPA/ certified Asbestos/Environmental Inspection team (EI) on Friday, January 14, 2022 and to perform a thorough visual inspection and bulk sampling to determine the presence of suspected asbestos containing materials prior to renovations of the above-identified property. The area inspection included all interior and exterior spaces impacted by the upcoming renovations in accordance with the contract documents provided. 1239 N Charlotte Street is a 1 story masonry/steel and wood building encompassing approximately 3,500 sf with a small loft area where roof access is gained.

## Asbestos

All areas were inspected using non-mechanical, yet destructive sampling methods once authorized by the client. Some hand demolition was performed to open hidden chases, false floors, or tunnels within the building envelope (no sub-surface investigation). Roofing samples were gathered from the roofs and appropriate repairs made at the sample locations. All suspect materials were identified by the inspector, quantified and sampled for the appropriate number of samples required by EPA protocol. Tested materials included drywall/joint compound, ceiling tiles, fireproofing, mastic, roofing and roof tar sealer, window caulk and exterior stucco.

EMSL Laboratories, Inc. (EMSL) of Plymouth Meeting, Pennsylvania analyzed all bulk samples from by Polarized Light Microscopy (PLM) using U.S. EPA Method 600/R-93/166. EMSL is an AIHA/NVLAP accredited laboratory for asbestos analysis. The laboratory accreditation number is included in the attached analytical reports. All samples were collected as per current regulatory regulations and guidelines. A minimum of three negative samples (based on square footage) were collected as required of each suspect material to identify them as non-asbestos containing if laboratory results were less than 1% asbestos by weight. A stop order was placed on first positive sample results for all materials sampled based on the onsite inspectors' visual inspection of the materials' consistency regarding color, texture, weight and appearance. **42** PLM analyses were performed by EMSL. Analysis Sheets can be found in Attachment A.

PLM analysis or assumption of known/suspected materials determined the following materials to be confirmed or presumed greater than 1% asbestos by weight by building location:



**Todd Markevich, P.E - APD ENGINEERING**  
**Environmental Inspection – NBC Project - 211231-EI-01**  
**BK # 4651 - 1239 N Charlotte Street - Pottstown, Pa**  
**Page Two**

- **Asbestos was detected greater than 1% in silver coat and main field roof (approx. 3,250 SF)**
- **Asbestos was detected greater than 1% in silver coat and roof flashing. (incl. in above quantities)**

NBC/North Brandywine Contractors has made reasonable efforts to identify and quantify suspect ACM based upon the standard care in the environmental industry existing at the time of the survey. Estimated cost for abatement of non-friable asbestos roofing materials is approximately \$ 13,500.00 - \$ 16,500.00. Typically, Cat 1 – Non-Friable roofing is not regulated in Pennsylvania and minor penetrations/repairs are made by certified roofers. If all materials are to be removed, certified asbestos contractors are usually retained to limit liability to Ownership.

### **Lead**

The subject structure was evaluated for LBP on Thursday, January, 2022 by Darren Slack, a Pa-licensed Lead Paint Inspector/Risk Assessor (certification #004947). Field XRF data summaries comprise can be found in Attachment B

The purpose of this LBP evaluation was to determine the likely presence, location, and condition of LBP on building surfaces with the understanding that the subject space is scheduled to be renovated. As part of this evaluation, the Lead Paint Inspector/Risk Assessor sampled 60 painted surfaces for total lead content using a Viken Pb200i X-Ray Fluorescence (XRF) Analyzer (serial # 2609).

XRF analytical results, provided in Attachment B of this report, detected lead concentrations exceeding the federal regulatory standard of 1.0 milligrams per square centimeter (mg/cm<sup>2</sup>) of paint in the following locations:

### **No Results in excess of 1.0 milligrams per square centimeter (mg/cm<sup>2</sup>)**

**NOTE:** Other painted surfaces may exist in presently inaccessible areas or beneath fixed equipment, shelving, or other appurtenances. Should future renovations or demolition disturb presently inaccessible areas or spaces outside the scope of this inspection, additional evaluation for the presence of LBP may be warranted.

Only areas identified within this report were part of the environmental survey. Although no piping or process equipment appeared to run underground or in sealed cavities, NBC cannot warrant that hidden asbestos-containing materials will not be discovered. The information contained in this report is only for the specific use of the Owner and NBC/North Brandywine Contractors, unless written authorization is obtained from NBC. NBC accepts no responsibility for the use, interpretation, or reliance by other parties on the information contained herein, nor does this report represent an instrument of regulatory compliance or an asbestos/environmental abatement specification.



**Todd Markevich, P.E - APD ENGINEERING**  
**Environmental Inspection – NBC Project - 211231-EI-01**  
**BK # 4651 - 1239 N Charlotte Street - Pottstown, Pa**  
**Page Three**

All applicable regulations must be followed during the renovation of the site. Should undiscovered suspect materials be uncovered during the renovation/demolition process, work should cease that would impact the suspect material and testing for asbestos content should be performed. Suspected materials should be treated as asbestos until testing confirms the materials to be non-asbestos. The inspection report and material inventory will be modified if additional materials are discovered.

My staff and I appreciated the opportunity to work with you. If you have any questions regarding the report, please do not hesitate to call me at 610-496-3379. I look forward to working with you in the future.

Sincerely,

*Jeremy Hassett*

Jeremy Hassett  
Pa Asbestos Inspector # 033992

*Allen Feinberg*

Allen Feinberg  
Industrial Hygienist/Principal

# **Attachment A**

**Polarized Microscopy Analysis Sheets  
EMSL Analytical, Inc.**

**Burger King # 4651  
1239 N Charlotte Street - Pottstown, Pa**

**January 20 , 2022**



# EMSL Analytical, Inc.

5221 Militia Hill Road Plymouth Meeting, PA 19462  
Tel/Fax: (610) 828-3102 / (610) 828-3122  
<http://www.EMSL.com> / [plymouthmeetinglab@emsl.com](mailto:plymouthmeetinglab@emsl.com)

**EMSL Order:** 182200206  
**Customer ID:** NBCO50  
**Customer PO:**  
**Project ID:**

**Attention:** Allen Feinberg  
North Brandywine Contractors  
1554 Paoli Pike #268  
West Chester, PA 19380

**Phone:** (610) 496-3379  
**Fax:** (610) 429-9033  
**Received Date:** 01/19/2022 9:00 AM  
**Analysis Date:** 01/20/2022  
**Collected Date:** 01/14/2022

**Project:** BK 4651- 1239 N CHARLETTE ST, POTTSTOWN, PA

## Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
BKP -01 <small>182200206-0001</small>	REAR - 2X2 DRYWALL CEILING TILES	Gray Fibrous Homogeneous	8% Cellulose 4% Glass	88% Non-fibrous (Other)	None Detected
			HA: 1		
BKP -02 <small>182200206-0002</small>	REAR - 2X2 DRYWALL CEILING TILES	Gray Fibrous Homogeneous	7% Cellulose 3% Glass	90% Non-fibrous (Other)	None Detected
			HA: 1		
BKP -03 <small>182200206-0003</small>	REAR - 2X2 DRYWALL CEILING TILES	Gray Fibrous Homogeneous	7% Cellulose 4% Glass	89% Non-fibrous (Other)	None Detected
			HA: 1		
BKP -04-Drywall <small>182200206-0004</small>	REAR - DRY WALL SYSTEM	Gray Fibrous Homogeneous	8% Cellulose 4% Glass	88% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -04-Joint Compound <small>182200206-0004A</small>	REAR - DRY WALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -05-Drywall <small>182200206-0005</small>	REAR - DRY WALL SYSTEM	Gray Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -05-Joint Compound <small>182200206-0005A</small>	REAR - DRY WALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -06-Drywall <small>182200206-0006</small>	BATH ROOM - DRY WALL SYSTEM	Gray Fibrous Homogeneous	6% Cellulose 4% Glass	90% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -06-Joint Compound <small>182200206-0006A</small>	BATH ROOM - DRY WALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -07-Drywall <small>182200206-0007</small>	DINING - DRY WALL SYSTEM	Gray Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -07-Joint Compound <small>182200206-0007A</small>	DINING - DRY WALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		

Initial report from: 01/21/2022 10:53:51



# EMSL Analytical, Inc.

5221 Militia Hill Road Plymouth Meeting, PA 19462

Tel/Fax: (610) 828-3102 / (610) 828-3122

<http://www.EMSL.com> / [plymouthmeetinglab@emsl.com](mailto:plymouthmeetinglab@emsl.com)

**EMSL Order:** 182200206  
**Customer ID:** NBCO50  
**Customer PO:**  
**Project ID:**

## Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
BKP -08-Drywall <small>182200206-0008</small>	DINING - DRY WALL SYSTEM	Gray Fibrous Homogeneous	7% Cellulose 4% Glass	89% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -08-Joint Compound <small>182200206-0008A</small>	DINING - DRY WALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 2		
BKP -09 <small>182200206-0009</small>	DINING - 2X2 ROUGH CEILING TILE	White Fibrous Homogeneous	15% Cellulose 75% Min. Wool	10% Non-fibrous (Other)	None Detected
			HA: 3		
BKP -10 <small>182200206-0010</small>	DINING - 2X2 ROUGH CEILING TILE	White Fibrous Homogeneous	10% Cellulose 80% Min. Wool	10% Non-fibrous (Other)	None Detected
			HA: 3		
BKP -11 <small>182200206-0011</small>	DINING - 2X2 ROUGH CEILING TILE	White Fibrous Homogeneous	10% Cellulose 80% Min. Wool	10% Non-fibrous (Other)	None Detected
			HA: 3		
BKP -12 <small>182200206-0012</small>	KITCHEN R - FIRE PROOFING	Gray Fibrous Homogeneous	20% Cellulose 25% Glass	55% Non-fibrous (Other)	None Detected
			HA: 4		
BKP -13 <small>182200206-0013</small>	KITCHEN DRU THRU - FIRE PROOFING	Gray Fibrous Homogeneous	30% Cellulose 25% Glass	45% Non-fibrous (Other)	None Detected
			HA: 4		
BKP -14 <small>182200206-0014</small>	KITCHEN BY FREEZER - FIRE PROOFING	Gray Fibrous Homogeneous	25% Cellulose 20% Glass	55% Non-fibrous (Other)	None Detected
			HA: 4		
BKP -15 <small>182200206-0015</small>	HALL BY BATHS - FIRE PROOFING	Gray Fibrous Homogeneous	15% Cellulose 15% Glass	70% Non-fibrous (Other)	None Detected
			HA: 4		
BKP -16 <small>182200206-0016</small>	DINING ENTRANCE - FIRE PROOFING	Gray Fibrous Homogeneous	20% Cellulose 15% Glass	65% Non-fibrous (Other)	None Detected
			HA: 4		
BKP -17 <small>182200206-0017</small>	FRONT - WINDOW CAULK	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 5		
BKP -18 <small>182200206-0018</small>	ENTRANCE - WINDOW CAULK	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 5		
BKP -19 <small>182200206-0019</small>	DRIVE THUR SIDE - WINDOW CAULK	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 5		
BKP -20-Drywall <small>182200206-0020</small>	LOFT TO ROOF - DRYWALL SYSTEM	Gray Fibrous Homogeneous	7% Cellulose	93% Non-fibrous (Other)	None Detected
			HA: 6		

Initial report from: 01/21/2022 10:53:51



# EMSL Analytical, Inc.

5221 Militia Hill Road Plymouth Meeting, PA 19462  
Tel/Fax: (610) 828-3102 / (610) 828-3122  
<http://www.EMSL.com> / [plymouthmeetinglab@emsl.com](mailto:plymouthmeetinglab@emsl.com)

**EMSL Order:** 182200206  
**Customer ID:** NBCO50  
**Customer PO:**  
**Project ID:**

## Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
BKP -20-Joint Compound  182200206-0020A	LOFT TO ROOF - DRYWALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 6		
BKP -21-Drywall  182200206-0021	LOFT TO ROOF - DRYWALL SYSTEM	Gray Non-Fibrous Homogeneous	5% Cellulose	95% Non-fibrous (Other)	None Detected
			HA: 6		
BKP -21-Joint Compound  182200206-0021A	LOFT TO ROOF - DRYWALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 6		
BKP -22-Drywall  182200206-0022	LOFT TO ROOF - DRYWALL SYSTEM	Gray Fibrous Homogeneous	6% Cellulose 3% Glass	91% Non-fibrous (Other)	None Detected
			HA: 6		
BKP -22-Joint Compound  182200206-0022A	LOFT TO ROOF - DRYWALL SYSTEM	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 6		
BKP -23-Silver Paint  182200206-0023	ROOF- MAIN FIELD -N	Silver Non-Fibrous Homogeneous		98% Non-fibrous (Other)	2% Chrysotile
			HA: 7		
BKP -23-Roofing  182200206-0023A <i>Composite of roofing shingles</i>	ROOF- MAIN FIELD -N	Brown/Black Fibrous Heterogeneous	60% Cellulose	25% Non-fibrous (Other)	15% Chrysotile
			HA: 7		
BKP -24-Silver Paint  182200206-0024	ROOF- MAIN FIELD -C				Positive Stop (Not Analyzed)
			HA: 7		
BKP -24-Roofing  182200206-0024A	ROOF- MAIN FIELD -C				Positive Stop (Not Analyzed)
			HA: 7		
BKP -25-Silver Paint  182200206-0025	ROOF- MAIN FIELD -S				Positive Stop (Not Analyzed)
			HA: 7		
BKP -25-Roofing  182200206-0025A	ROOF- MAIN FIELD -S				Positive Stop (Not Analyzed)
			HA: 7		
BKP -26-Silver Paint  182200206-0026	ROOF- FLASHING- N	Silver Non-Fibrous Homogeneous		98% Non-fibrous (Other)	2% Chrysotile
			HA: 8		
BKP -26-Roofing  182200206-0026A <i>Composite of shingles</i>	ROOF- FLASHING- N	Brown/Black Fibrous Heterogeneous	50% Cellulose 4% Glass	31% Non-fibrous (Other)	15% Chrysotile
			HA: 8		

Initial report from: 01/21/2022 10:53:51



# EMSL Analytical, Inc.

5221 Militia Hill Road Plymouth Meeting, PA 19462  
Tel/Fax: (610) 828-3102 / (610) 828-3122  
<http://www.EMSL.com> / [plymouthmeetinglab@emsl.com](mailto:plymouthmeetinglab@emsl.com)

**EMSL Order:** 182200206  
**Customer ID:** NBCO50  
**Customer PO:**  
**Project ID:**

## Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
BKP -27-Silver Paint  182200206-0027	ROOF- FLASHING- C				Positive Stop (Not Analyzed)
			HA: 8		
BKP -27-Roofing  182200206-0027A	ROOF- FLASHING- C				Positive Stop (Not Analyzed)
			HA: 8		
BKP -28-Silver Paint  182200206-0028	ROOF- FLASHING- S				Positive Stop (Not Analyzed)
			HA: 8		
BKP -28-Roofing  182200206-0028A	ROOF- FLASHING- S				Positive Stop (Not Analyzed)
			HA: 8		
BKP -29  182200206-0029	ROOF- TAR SEALER -N	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 9		
BKP -30  182200206-0030	ROOF- TAR SEALER -C	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 9		
BKP -31  182200206-0031	ROOF- TAR SEALER -C	Black Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 9		
BKP -32  182200206-0032	EXTERIOR STUCCO- N	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 10		
BKP -33  182200206-0033	EXTERIOR STUCCO- CENTER	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 10		
BKP -34  182200206-0034	EXTERIOR STUCCO- S	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
			HA: 10		

Analyst(s)  
Colin Walker (40)

Kevin Ream, Laboratory Manager  
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. Plymouth Meeting, PA NVLAP Lab Code 200699-0, Philadelphia ALL-292, VA 3333000315, AIHA-LAP, LLC IHLAP #178659

Initial report from: 01/21/2022 10:53:51





### Asbestos Chain of Custody (Air, Bulk, Soil)

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077

182200206

PHONE: (800) 220-3675  
EMAIL: [CinnAslab@EMSL.com](mailto:CinnAslab@EMSL.com)

EMSL ANALYTICAL, INC.  
TESTING LABS • PRODUCTS • TRAINING

If Bill-To is the same as Report-To leave this section blank. Third-party billing requires written authorization

<b>Customer Information</b> Customer ID: <u>NBC05D</u> Company Name: <u>NBC/Work Breakup Contractors</u> Contact Name: <u>Allen Feinberg</u> Street Address: <u>1554 Park Plk #260</u> City, State, Zip: <u>West Chester Pa 19380</u> Country: _____ Phone: <u>610-496-3379</u> Email(s) for Report: <u>Alex2Alex@aol.com</u>	<b>Billing Information</b> Billing ID: <u>SAME</u> Company Name: _____ Billing Contact: _____ Street Address: _____ City, State, Zip: _____ Country: _____ Phone: _____ Email(s) for Invoice: _____
--	--

<b>Project Information</b>	
Project Name/No: <u>DK4651-1239 N Charlotte St. Pittston Pa</u>	Purchase Order: _____
EMSL LIMS Project ID: _____ <small>(If applicable, EMSL will provide)</small>	US State where samples collected: _____ State of Connecticut (CT) must select project location. <input type="checkbox"/> Commercial (Taxable) <input type="checkbox"/> Residential (Non-Taxable)
Sampled By Name: <u>A. Feinberg / E. Kegan</u>	Sampled By Signature: <u>[Signature]</u> No. of Samples in Shipment: _____
Turn-Around-Time (TAT) <input type="checkbox"/> 3 Hour <input type="checkbox"/> 4-6 Hour <input type="checkbox"/> 8 Hour <input type="checkbox"/> 24 Hour <input type="checkbox"/> 32 Hour <input checked="" type="checkbox"/> 48 Hour <input type="checkbox"/> 72 Hour <input type="checkbox"/> 96 Hour <input type="checkbox"/> 1 Week <input type="checkbox"/> 2 Week <small>TEM Air 3-8 Hour, please call ahead to schedule. 32 Hour TAT available for select tests only; samples must be submitted by 11:30 am.</small>	

<b>PCM Air</b> <input type="checkbox"/> NIOSH 7400 <input type="checkbox"/> NIOSH 7400 w/ 8hr. TWA <input checked="" type="checkbox"/> <b>PLM - Bulk (reporting limit)</b> <input checked="" type="checkbox"/> PLM EPA 600/R-93/116 (<1%) <input type="checkbox"/> PLM EPA NOB (<1%) <input type="checkbox"/> POINT COUNT <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1,000 (<0.1%) <input type="checkbox"/> POINT COUNT w/ GRAVIMETRIC <input type="checkbox"/> 400 (<0.25%) <input type="checkbox"/> 1,000 (<0.1%) <input type="checkbox"/> NIOSH 9002 (<1%) <input type="checkbox"/> NYS-198 1 (Friable - NY) <input type="checkbox"/> NYS 198 6 NOB (Non-Friable - NY) <input type="checkbox"/> NYS 198.8 (Vermiculite SM-V)	<b>TEM - Air</b> <input type="checkbox"/> AHERA 40 CFR, Part 763 <input type="checkbox"/> NIOSH 7402 <input type="checkbox"/> EPA Level II <input type="checkbox"/> ISO 10312* <b>TEM - Bulk</b> <input type="checkbox"/> TEM EPA NOB <input type="checkbox"/> NYS NOB 198.4 (Non-Friable-NY) <input type="checkbox"/> TEM EPA 600/R-93/116 w Milling Prep (0 1%)	<b>TEM - Settled Dust</b> <input type="checkbox"/> Microvac - ASTM D5755 <input type="checkbox"/> Wipe - ASTM D5480 <input type="checkbox"/> Qualitative via Filtration Prep <input type="checkbox"/> Qualitative via Drop Mount Prep <b>Soil - Rock - Vermiculite (reporting limit)*</b> <input type="checkbox"/> PLM EPA 600/R-93/116 with milling prep (<0.25%) <input type="checkbox"/> PLM EPA 600/R-93/116 with milling prep (<0.1%) <input type="checkbox"/> TEM EPA 600/R-93/116 with milling prep (<0.1%) <input type="checkbox"/> TEM Qualitative v/a Filtration Prep <input type="checkbox"/> TEM Qualitative via Drop Mount Prep
<b>Other Test (please specify)</b> _____ _____ _____		

Positive Stop - Clearly Identified Homogeneous Areas (HA) Filter Pore Size (Air Samples)  0.8um  0.45um

Sample Number	Sample Location / Description	Volume, Area or Homogeneous Area	Date / Time Sampled (Air Monitoring Only)
BKP-01	2x2 Drywall Ceiling tiles - Rev	1	1-14-22 1530
02	"		
03	"		
BKP-04	Drywall System - Rev	2	
05	" - Rev	"	
06	" - Bath Area	"	
07	" - Dry	"	
08	" - Dry	"	

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)  
 Drywall & Joint Compound Separate

Method of Shipment: <u>Hand</u>	Sample Condition Upon Receipt: _____		
Relinquished by: <u>[Signature]</u>	Date/Time: <u>1/14/22 12:00</u>	Received by: <u>Nicholson</u>	Date/Time: <u>1-19-22 9am</u>
Relinquished by: _____	Date/Time: _____	Received by: _____	Date/Time: _____

Controlled Document - CQC-05 Asbestos R15 4/23/2013  AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



**Asbestos Chain of Custody (Air, Bulk, Soil)**

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077

182200206

PHONE: (800) 220-3675

EMAIL: CinnAsblab@EMSL.com

**EMSL ANALYTICAL, INC.**  
TESTING LABS • PRODUCTS • TRAINING

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

- BK Potts Inc - Cont -

Sample Number	Sample Location / Description	Volume, Area or Homogeneous Area	Date / Time Sampled (Air Monitoring Only)
BKP-09	2x2 Rough Cng foto - Dmij	3	1/14/14 1530
10	"	"	<div style="border-left: 1px solid black; border-right: 1px solid black; height: 100%;"></div>
11	"	"	
BKP-12	Fire Proofing - Kit R	4	
13	" - Kit Down thr	"	
14	" - Kit by frame	"	
15	" - hall - by Batho	"	
16	" - Dry - Exterior	"	
BKP-17	Window Caulk - fast	5	
18	" - Exterior	"	
19	" - Down the side	"	
BKP-20	Drywall System - left to roof	6	
21	"	"	
22	"	"	
BKP-23	Roof - Main Parcel - N	7	
24	" - C	"	
25	" - S	"	
BKP-26	Roof - Plashy - N	8	
27	" - C	"	
28	" - S	"	
BKP-29	Roof - far scale - N	9	
30	" - C	"	
31	" - C	"	
BKA-32	Exter stucco - N	10	
33	" - Cont	"	
34	" - S	"	

Method of Shipment:		Sample Condition Upon Receipt:	
Relinquished by:	Date/Time:	Received by:	Date/Time:
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - COC-05 Asbestos R15 4/23/2021  **AGREE TO ELECTRONIC SIGNATURE** (By checking, I consent to signing this Chain of Custody document by electronic signature.)  
 EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

# **Attachment B**

## **Lead Inspection Report and XRF Readings Sheets**

**Mandell Environmental  
Consulting**

**Burger King # 4651  
1239 N Charlotte Street -  
Pottstown, Pa**

**January 20, 2022**



---

## MANDELL ENVIRONMENTAL CONSULTING

---

409 MINNISINK ROAD • SUITE 102 • TOTOWA, NJ 07512 • (973) 785-7574 • FAX (973) 785-0561

### LEAD PAINT INSPECTION REPORT

INSPECTION FOR: North Brandywine Contractors  
1554 Paoli Pike  
West Chester, PA 19380

PERFORMED AT: 1239 N. Charlotte Street  
Pottstown, PA

INSPECTION DATE: 01/20/22

INSTRUMENT TYPE: Viken Pb200i  
XRF Lead-Based Paint Analyzer  
Serial Numbers: 2609

ACTION LEVEL: 1.0 mg/cm<sup>2</sup>

OPERATOR LICENSE: PA Lead Inspector ID# 004947

#### THIS REPORT IS NON TRANSFERABLE

The measurements contained within are accurate to the best of our knowledge. Mandell Lead Inspectors Inc. does not under any circumstances make any representation guarantee or warranty as to the reported or future condition of the property.

SIGNED:         *Darren Slack*         Date:         1-31-2022          
Darren Slack  
Mandell Lead Inspectors, Inc.  
409 Minnisink Road, Suite 102  
Totowa, NJ 07512  
973-785-7574

## Summary

On January 20, 2022, Mandell Lead Inspectors, Inc. conducted a limited inspection for the possible presence of Lead-based Paint 1239 N. Charlotte Street, Pottstown, PA. Sampling of selected areas was performed using a Viken Pb200i Lead-Based Paint Analyzer. The inspection was conducted by Darren Slack PA/EPA Lead Paint Inspector Certification # 004947. The inspection was limited to the random testing of painted components that may be disturbed during renovation or demolition activities. The inspection was not intended to be a full survey in accordance with HUD Guidelines.

The enclosed information will primarily assist you in identifying the location(s) of lead-based paint on the exterior and interior painted surfaces tested during the inspection. It should not be used to assess whether an individual has been exposed to harmful levels of lead and/or the future for potential for future exposure. However, this information can provide the basis for a more detailed inspection or risk assessment, which includes an in depth, hazard evaluation as well as soil, and dust wipe sampling.

The XRF results section of this report provides a listing of all the readings collected during the inspection, organized by room and structure type. The positive readings are highlighted and include those readings that were at or above the action level 1.0 mg/cm<sup>2</sup>. **None of the readings tested positive for lead-based paint.** However, some painted surfaces may contain levels of lead below 1.0 mg/cm<sup>2</sup> (e.g. inconclusive), which could create dust or lead-contaminated soil hazards if the paint is turned into dust by abrasion, scraping, or sanding. When reviewing the reports please consider that XRF readings were only collected on representative painted surfaces which were visible to the inspector at the time of the inspection, and accessible from ground level. Readings were not collected in areas where the presence or absence of paint could not be determined, or accessed. The overall condition of the painted surfaces at these locations is also provided.

# XRF RESULTS

## EXPLANATION OF TERMS AND ABBREVIATIONS

The following information has been provided to assist you with the attached Lead-Based Paint Inspection Report.

**Action Level** – The level at or above which any paint, shellac, varnish, or other coating is considered to be lead-based and, consequently, appropriate abatement and/or interim control measures should be considered. Currently, the action level as outlined in State and Federal guidelines is 1.0 milligrams/square centimeter (1.0 mg/cm<sup>2</sup>) as measured by X-Ray Fluorescence (XRF) testing, or 0.5% by weight as measured by laboratory analysis.

**Reading No.** – Corresponds to a specific XRF measurement as taken in a numerical sequence during the inspection.

**Surface** – The general location of a measurement relative to a wall on the exterior of the house or within a particular room. Wall A corresponds to the front entry wall, while walls B through D are identified proceeding in a clockwise direction.

**Structure** – A major component such as a window, wall, or staircase located inside or outside of the house, upon which a measurement or set of measurements were collected.

**Location** – The specific area on a structure where a measurement was collected.

**Member** – A portion of a structure such as a window jam, door header, or stair riser where a measurement was collected.

**Friction Surface** – Any interior or exterior surface such as a window, stair tread, or floor subject to friction or abrasion.

**Impact Surface** – An interior or exterior surface such as surfaces on doors subject to damage by repeated impact or contact.

**Paint Condition** – A subjective classification of the condition of a painted surface upon which a measurement was collected. Paint is classified into one of two categories that include “sound” or “unsound”. A “sound” surface is considered to be completely intact and free from any visible signs of damage or deterioration. All other surfaces are considered “unsound”. Regardless of the paint condition at the time of inspection, all friction and impact surfaces are considered “unsound” due to the ongoing generation of dust that is inherent to these surfaces during use. If test results indicate the presence of lead-based paint, particularly on an “unsound” surface, steps should be taken to establish and maintain a lead-safe condition.

**I = Intact:** Paint surface is smooth, continuous and free of surface defect that would result in the release of paint dust or chips.

**F=Fair:** Large surfaces – a surface where less than or equal to two square feet of surface are not intact. Areas without large surfaces - surface where less than or equal to 10 percent of the surface is not intact.

**P=Poor:** Large surfaces – a surface where more than two square feet of surface are not intact. Areas without large surfaces – surface where more than 10 percent of the surface is not intact.

# Lead Inspection Report

Inspection Date: 1/20/2022 - 1/20/2022  
 Action Level: 1.0 (mg/cm<sup>2</sup>)  
 Total Readings: 63  
 Unit Started: 01/20/2022 11:12:43  
 Unit Ended: 01/20/2022 11:45:30

Inspection Site: 1239 N. Charlotte Street  
 Pottstown, PA

Read #	Result	Room	Wall	Component	Substrate	Paint Condition	Lead (mg/cm <sup>2</sup> )
200 (CAL)							1.2 mg/cm <sup>2</sup>
201 (CAL)							1.1 mg/cm <sup>2</sup>
202 (CAL)							1.1 mg/cm <sup>2</sup>
203 (CAL)							0.0 mg/cm <sup>2</sup>
204 (CAL)							0.0 mg/cm <sup>2</sup>
205 (CAL)							0.0 mg/cm <sup>2</sup>
206	Negative	Lobby	A	Wall	Plaster	Intact	0.1 mg/cm <sup>2</sup>
207	Negative	Lobby	D	Wall	Plaster	Intact	0.0 mg/cm <sup>2</sup>
208	Negative	Lobby	D	Window Molding	Wood	Intact	0.0 mg/cm <sup>2</sup>
209	Negative	Lobby	B	Window Molding	Wood	Intact	0.0 mg/cm <sup>2</sup>
210	Negative	Lobby	B	Wall	Plaster	Intact	0.1 mg/cm <sup>2</sup>
211	Negative	Kitchen/Fo	D	Door Molding	Metal	Deteriorated	0.1 mg/cm <sup>2</sup>
212	Negative	Kitchen/Food		Door	Wood	Deteriorated	0.0 mg/cm <sup>2</sup>
213	Negative	Kitchen/Fo	C	Door	Metal	Deteriorated	0.0 mg/cm <sup>2</sup>
214	Negative	Kitchen/Food		Door Molding	Metal	Deteriorated	0.1 mg/cm <sup>2</sup>
215	Negative	Kitchen/Fo	C	Wall	Paneling	Intact	0.0 mg/cm <sup>2</sup>
216	Negative	Kitchen/Food		Wall	Plaster	Intact	0.0 mg/cm <sup>2</sup>
217	Negative	Kitchen/Fo	C	Wall	Plaster	Intact	0.1 mg/cm <sup>2</sup>
218	Negative	Men's	B	Door	Wood	Intact	0.1 mg/cm <sup>2</sup>
219	Negative	Men's	B	Door Molding	Wood	Intact	0.1 mg/cm <sup>2</sup>
220	Negative	Men's	Center	Ceiling	Plaster	Intact	0.0 mg/cm <sup>2</sup>



# Lead Inspection Report

Inspection Date: 1/20/2022 - 1/20/2022  
 Action Level: 1.0 (mg/cm<sup>2</sup>)  
 Total Readings: 63  
 Unit Started: 01/20/2022 11:12:43  
 Unit Ended: 01/20/2022 11:45:30

Inspection Site: 1239 N. Charlotte Street  
 Pottstown, PA

Read #	Result	Room	Wall	Component	Substrate	Paint Condition	Lead (mg/cm <sup>2</sup> )
221	Negative	Woman's Bathroom	Center	Ceiling	Plaster	Intact	0.0 mg/cm <sup>2</sup>
222	Negative	Woman's Bathroom	Center	Ceiling	Plaster	Intact	0.0 mg/cm <sup>2</sup>
223	Negative	Woman's Bathroom	Center	Door Molding	Metal	Intact	0.1 mg/cm <sup>2</sup>
224	Negative	Woman's Bathroom	B	Door Molding	Metal	Intact	0.1 mg/cm <sup>2</sup>
225	Negative	Woman's Bathroom	B	Door	Wood	Intact	0.1 mg/cm <sup>2</sup>
226	Negative	Lobby	D	Ceiling Molding	Wood	Intact	0.0 mg/cm <sup>2</sup>
227	Negative	Lobby	D	Ceiling Molding	Wood	Intact	0.0 mg/cm <sup>2</sup>
228	Negative	Woman's Bathroom	B	Wall	Tile	Intact	0.5 mg/cm <sup>2</sup>
229	Negative	Woman's Bathroom	B	Wall	Tile	Intact	0.5 mg/cm <sup>2</sup>
230	Negative	Woman's Bathroom	C	Wall	Tile	Intact	0.2 mg/cm <sup>2</sup>
231	Negative	Woman's Bathroom	D	Wall	Tile	Intact	0.5 mg/cm <sup>2</sup>
232	Negative	Woman's Bathroom	D	Wall	Tile	Intact	0.4 mg/cm <sup>2</sup>
233	Negative	Woman's Bathroom	A	Wall	Tile	Intact	0.4 mg/cm <sup>2</sup>
234	Negative	Woman's Bathroom	A	Wall	Tile	Intact	0.0 mg/cm <sup>2</sup>
235	Negative	Kitchen/Prep Area	B	Wall	Tile	Intact	0.3 mg/cm <sup>2</sup>
236	Negative	Kitchen/Prep Area	Food	Wall	Tile	Intact	0.3 mg/cm <sup>2</sup>
237	Negative	Kitchen/Prep Area	D	Wall	Tile	Intact	0.5 mg/cm <sup>2</sup>
238	Negative	Exterior	A	Wall	Masonry	Intact	0.0 mg/cm <sup>2</sup>
239	Negative	Exterior	A	Window Molding	Wood	Intact	0.0 mg/cm <sup>2</sup>
240	Negative	Exterior	A	Ceiling	Metal	Intact	0.0 mg/cm <sup>2</sup>

# Lead Inspection Report

Inspection Date: 1/20/2022 - 1/20/2022      Inspection Site: 1239 N. Charlotte Street  
 Action Level: 1.0 (mg/cm<sup>2</sup>)      Pottstown, PA  
 Total Readings: 63  
 Unit Started: 01/20/2022 11:12:43  
 Unit Ended: 01/20/2022 11:45:30

Read #	Result	Room	Wall	Component	Substrate	Paint Condition	Lead (mg/cm <sup>2</sup> )
241	Negative	Exterior	B	Wall	Masonry	Intact	0.2 mg/cm <sup>2</sup>
242	Negative	Exterior	B	Column	Wood	Intact	0.1 mg/cm <sup>2</sup>
243	Negative	Exterior	B	Column	Wood	Intact	0.0 mg/cm <sup>2</sup>
244	Negative	Exterior	B	Soffit	Wood	Deteriorated	0.0 mg/cm <sup>2</sup>
245	Negative	Exterior	B	Fascia	Wood	Deteriorated	0.0 mg/cm <sup>2</sup>
246	Negative	Exterior	C	Utility Box	Metal	Deteriorated	0.3 mg/cm <sup>2</sup>
247	Negative	Exterior	C	Door	Metal	Deteriorated	0.1 mg/cm <sup>2</sup>
248	Negative	Exterior	C	Door Molding	Metal	Deteriorated	0.1 mg/cm <sup>2</sup>
249	Negative	Exterior	C	Wall	Concrete	Deteriorated	0.0 mg/cm <sup>2</sup>
250	Negative	Exterior	C	Wall	Concrete	Deteriorated	0.1 mg/cm <sup>2</sup>
251	Negative	Exterior	C	Ceiling	Wood	Intact	0.0 mg/cm <sup>2</sup>
252	Negative	Exterior	C	Gate	Wood	Intact	0.0 mg/cm <sup>2</sup>
253	Negative	Exterior	D	Parking Stripe	Concrete	Intact	0.1 mg/cm <sup>2</sup>
254	Negative	Exterior	D	Parking Stripe	Concrete	Intact	0.0 mg/cm <sup>2</sup>
255	Negative	Exterior	D	Bollard	Metal	Intact	0.2 mg/cm <sup>2</sup>
256	Negative	Exterior	D	Bollard	Metal	Intact	0.3 mg/cm <sup>2</sup>
257 (CAL)							1.1 mg/cm <sup>2</sup>
258 (CAL)							1.0 mg/cm <sup>2</sup>
259 (CAL)							1.1 mg/cm <sup>2</sup>
260 (CAL)							0.0 mg/cm <sup>2</sup>
261 (CAL)							0.0 mg/cm <sup>2</sup>
262 (CAL)							0.0 mg/cm <sup>2</sup>

----- END OF READINGS -----