


# IMPROVEMENT PLANS

# TACO BELL

WEST PLANE STREET  
BETHEL, OH

**NOT FOR  
CONSTRUCTION**



INDEX OF DRAWINGS	
TITLE SHEET	TS-001
ALTA	...
GENERAL NOTES	C-001
SWPP NOTES	C-010
SWPP DETAILS	C-011
SWPP PLAN	C-012
DEMOLITION PLAN	C-101
SITE PLAN	C-111
GRADING PLAN	C-121
UTILITY PLAN	C-131
DETAILS	C-501
DETAILS	C-502
DETAILS	C-503
DETAILS	C-504
DETAILS	C-505
LANDSCAPE NOTES	L-001
LANDSCAPE PLAN	L-101
LANDSCAPE DETAILS	L-501

DATE	REMARKS

CONTRACT DATE:  
BUILDING TYPE: END 20  
PLAN VERSION: JUNE 2021  
BRAND DESIGNER:  
SITE NUMBER:  
STORE NUMBER:  
PA/PM: AB  
DRAWN BY.: KK  
JOB NO.: 2021188.12

**TACO BELL**  
West Plane Street  
Bethel, OH 45013



END 20  
  
TITLE SHEET

TS-001

PLOT DATE:

**PROJECT DESCRIPTION**  
THE EXISTING PROJECT SITE IS CURRENTLY A RESIDENTIAL HOME THAT WILL BE DEMOLISHED TO MAKE WAY FOR THE PROPOSED DEVELOPMENT, A TACO BELL RESTAURANT. THE SITE CURRENTLY DRAINS INTO AN EXISTING CREEK LOCATED ON THE NORTH END OF THE SITE. THESE DRAINAGE PATTERNS WERE FOLLOWED IN THE POST-DEVELOPED CONDITIONS.

**ODOT AND CLERMONT COUNTY SPECIFICATION**  
THE OHIO DEPARTMENT OF TRANSPORTATION "CONSTRUCTION AND MATERIAL SPECIFICATIONS", CURRENT EDITION, AND THE CURRENT RULES AND REGULATIONS OF CLERMONT COUNTY SHALL GOVERN ALL CONSTRUCTION ITEMS ON THIS PLAN, UNLESS NOTED OTHERWISE.

**STANDARD DRAWINGS:**  
THE FOLLOWING ODOT AND LOCAL STANDARD DRAWINGS SHALL BE CONSIDERED A PART OF THIS PLAN.

- CB 1.1 (07-19-19) CATCH BASINS NOS 2-2A & B, 3A (ODOT)

**OWNER AND DEVELOPER**  
AMPLER DEVELOPMENT, LLC.  
2601 NORTHWEST EXPRESSWAY, SUITE 100W  
OKLAHOMA CITY, OK 73112  
DAN PEYTON  
(513)-468-7088

**PLAN REPRODUCTION WARNING**  
THE PLANS HAVE BEEN PREPARED FOR PRINTING ON ANSI X (22"x34") SHEETS. PRINTING ON OTHER SIZE SHEETS MAY DISTORT SCALES. REFER TO GRAPHIC SCALES.

BENCHMARKS:

- 1. X-CUT ON HYDRANT BONNET BOLT
N 355397
E 1516029
ELEV. = 878.94
BENCHMARK 2
2. X-CUT ON HYDRANT BONNET BOLT
N 355629
E 1515405
ELEV. = 877.49

LEGEND:

- EXISTING GIN SPIKE FOUND AS NOTED
EXISTING IRON PIN FOUND AS NOTED
5/8" x 30" REBAR WITH CAP "GPD" SET
EXISTING POWER & TELEPHONE POLE
EXISTING CATCH BASIN
EXISTING CURB INLET
EXISTING STORM MANHOLE
EXISTING SANITARY MANHOLE
EXISTING FIRE HYDRANT
EXISTING WATER VALVE
EXISTING SIGNAL POLE
EXISTING GUY WIRE
EXISTING SIGN
EXISTING SOIL BORING
EXISTING PROPERTY LINE
EXISTING RIGHT OF WAY LINE
EXISTING CENTER LINE
EXISTING OVERHEAD UTILITY LINES
EXISTING UNDERGROUND GAS LINES
EXISTING UNDERGROUND STORM LINES
EXISTING UNDERGROUND WATER LINES
EXISTING DECIDUOUS TREE

INVERTS:

- STMH 67 T/C = 877.27
18" RCP (E&W) = 869.67
12" RCP (S) = 869.67
CB 66 T/C = 876.60
12" RCP (N) = 870.30
STMH 83 T/C = 876.60
18" VCP (NW) = 866.50
18" VCP (E) = 866.80
CB 300 T/C = 873.96
18" VCP (NE&SE) = 865.16
STMH 302 T/C = 875.38
18" RCP (N&S) = 863.98
SSMH 60 T/C = 876.93
8" VCP (E) = 868.73
8" VCP (S) = 868.78
8" VCP (N) = 868.83
6" CMP (SW) = 872.28
SSMH 100001 T/C = 877.43
8" VCP (W) = 868.53
8" VCP (E) = 868.48
6" VCP (NW) = 868.83
6" VCP (SW) = 868.93

Underground Utilities
Ohio Utilities Protection Service
Call 811 before you dig

1-800-362-2764 or 811

UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OURS REQUEST #8129202186 AND #8129202188.
SUBSURFACE UTILITY INFORMATION PROVIDED IN THIS BASEMAP IS FROM A COMBINATION OF ONE CALL COORDINATION AND A PRIVATE UTILITY LOCATE (PUL) PERFORMED BY GPD GROUP, UNLESS OTHERWISE LABELED SUBSURFACE UTILITY LINES SHOWN HEREON ARE ASCE SUE QUALITY LEVEL (QL) D. SUBSURFACE UTILITY LINES LABELED AS QL-D CAN BE FROM ONE CALL 811 COORDINATION AS DESCRIBED IN THE PROJECT STATE'S CODIFIED LAWS AND THOSE SUBSURFACE UTILITY LINES SHOWN HEREON WERE MARKED ON THE GROUND OR DEPICTED IN RECORDS/MAPPING PROVIDED BY THIRD PARTIES OR OTHERS, THAT MAY OR MAY NOT PROVIDE ACCURATE HORIZONTAL LOCATION INFORMATION OF SUBSURFACE FACILITIES. THESE THIRD PARTIES AND OTHERS ARE NOT CONTRACTUALLY OBLIGATED OR LIABLE TO GPD GROUP OR CLIENT. GPD GROUP ASSUMES NO LIABILITY OR RESPONSIBILITY FOR QL-D LINES ARISING OUT OF ANY AND ALL SHOWN OR UNSHOWN SUBSURFACE UTILITIES RELATING TO THE DEVELOPED BASEMAP, THEREFORE NO WARRANTY OR GUARANTEE IS EXPRESSED OR IMPLIED OF ANY AND ALL OF THESE SUBSURFACE UTILITIES.

SUBSURFACE UTILITY LINES AND ANOMALIES LABELED AS QL-B, QL-C, "OPR ANOMALY QL-D", OR "PASSIVE EM QL-D" ARE FACILITIES INDICATED PRESENT BY OUR EQUIPMENT AND AT THE APPROXIMATE HORIZONTAL POSITION SHOWN HEREON BASED ON GPD GROUP'S PUL EFFORTS. OUR PUL MARKINGS ARE SUBJECT TO OUR SPECIFICATIONS OF PERFORMANCE AND ALL QUALITY LEVELS ARE FURTHER DESCRIBED IN ASCE MANUAL 38-02 "GUIDELINE FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA".

SCHEDULE B - SECTION II:

Fidelity National Title Insurance Company
File Number: 2153610411
Commitment Date: 02/04/2022 at 6:59 a.m.

15. INTENTIONALLY DELETED

16. Annexation, filed for record March 20, 1997, in OR Volume 882, Page 432 of the Clermont County, Ohio Records. (INCLUDES SURVEYED PROPERTY)

17. Taxes for the second half of 2021 and subsequent installments thereafter, which are not yet due and payable. The County Treasurer's General Tax Records for the tax year 2021 are as follows: PPN 36-03-27.031.

Taxes for the first half are a lien, now due and payable. Taxes for the second half are a lien, not yet due and payable. Per half amount \$965.72.

NOTE: Taxes are based on underlying acreage. Future parcel number of the premises insured herein will be 360327.121. (As to Parcel 1), (NOT A SURVEY MATTER)

18. Reservations, restrictions, covenants, limitations, easements and/or other conditions as shown on Lot Split Survey filed in TL95-0392, of the Clermont County Engineers Record of Surveys. (PLOTTED AND SHOWN)

19. Matters shown on the ALTA/NSPS Land Title Survey prepared by Steven L. Mullaney, Registered Surveyor No. 7900 for GPD Group, dated November 10, 2021, last revised having Job No. 2021188.12.

A. Possible driveway encroachment as shown; and
B. Wood shed is over the property line. Ownership not noted. (PLOTTED AND SHOWN)

ALTA/NSPS LAND TITLE SURVEY

BRECKENRIDGE'S MILITARY SURVEY No. 2373
VILLAGE OF BETHEL
COUNTY OF CLERMONT
STATE OF OHIO

GENERAL NOTES:

- 1. THE DESCRIBED REAL ESTATE IS IN A ZONE X, AS INDICATED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY'S NATIONAL FLOOD INSURANCE PROGRAM PANEL NO. 39025C0330G, EFFECTIVE DATE OF MARCH 16, 2006.
2. THIS SURVEY IS NOT FOR THE PURPOSE OF LOCATING OR IDENTIFYING ANY POLLUTANTS OR HAZARDOUS MATERIALS ON OR UNDER THE PROPERTY SHOWN HEREON.
3. GPD GROUP AND/OR THE SURVEYORS COMMENTS REGARDING BOUNDARIES, LOCATION AND/OR LIMITS OF THE RIGHTS OF WAY, EASEMENTS AND/OR SERVITUDES AS SHOWN HEREON ARE SOLELY RELATED TO THE LOCATION OF SAID ITEMS AND IS BASED ON THE INFORMATION GATHERED DURING THE FIELD SURVEY AND A REVIEW OF THE INFORMATION PROVIDED IN THE TITLE COMMITMENT REFERENCED HEREON. COMMENTS REGARDING TITLE ITEMS DO NOT REPRESENT A LEGAL OPINION ON THE EXISTENCE, TERMINATION, AFFECTS OR BENEFITS OF SAID ITEMS, AS THAT IS A QUESTION OF LAW AND OUTSIDE THE RESPONSIBILITIES OF THE SURVEYOR.

REFERENCES:

- 1. COUNTY TAX MAP.
2. DEEDS AS REFERENCED ON SURVEY.
3. TITLE REPORT

BASIS OF BEARING:

STATE PLANE GRID NORTH, NAD 83 (2011), GEOID 18, OHIO SOUTH ZONE.
ELEVATIONS ARE NAVD 88.
TIED BY GPS TO THE O.D.O.T. VRS.



LOCATION MAP

NOT FOR CONSTRUCTION

TITLE DESCRIPTION:

Situated in the State of Ohio, County of Clermont, Tate Township, Brecklenridge's Military Survey No. 2373, Village of Bethel and being part of a tract conveyed to Alfwaress Properties LLC, and on the west line of a tract conveyed to Richard A. and Linda J. Bauer by Instrument Number 9900020872; thence on the west line of said Bauer tract South 11 degrees 53 minutes 50 seconds West a distance of 57.41 feet to a 5/8 inch rebar (found) with cap stamped "Jasontek 7582" being the POINT OF BEGINNING of the parcel herein described;

COMMENCING at a 1 inch iron pipe (found) at the southwest corner of Lot 16 of the Tate Run Subdivision as recorded in Plat Cabinet 5, Page 46, on the east line of a tract conveyed to Paul W. Mayes and Victoria L. Patterson by Instrument Number 201700000518, and on the west line of a tract conveyed to Richard A. and Linda J. Bauer by Instrument Number 9900020872; thence on the west line of said Bauer tract South 11 degrees 53 minutes 50 seconds West a distance of 57.41 feet to a 5/8 inch rebar (found) with cap stamped "Jasontek 7582" being the POINT OF BEGINNING of the parcel herein described;

- 1) Thence on the south line of said Bauer line, South 75 degrees 45 minutes 13 seconds East, a distance of 228.05 feet to a 5/8 inch rebar (set) with cap stamped "GPD";
2) South 21 degrees 40 minutes 36 seconds West, a distance of 377.37 feet to a 5/8 inch rebar (set), with cap stamped "GPD"
3) North 68 degrees 01 minutes 29 seconds West, a distance of 10.00 feet, to a 5/8 inch rebar (set), with cap stamped "GPD";
4) South 21 degrees 58 minutes 31 seconds West, a distance of 130.00 feet, to a point on the centerline of West Plane Street (State Route 125) and passing over a 5/8 inch rebar (set), with cap stamped "GPD" at 75.29 feet on the north right of way line of said West Plane Street;
5) Thence on the centerline of said West Plane Street, North 68 degrees 01 minutes 29 seconds West, a distance of 133.38 feet, to a point;
6) Thence leaving said centerline, North 11 degrees 54 minutes 47 seconds East, passing over a point on the north right of way line of said West Plane Street at 56.12 feet, being witnessed by a Gin Spike (found) bearing North 11 degrees 54 minutes 47 seconds East, a distance of 0.67 feet, to a total distance of 484.14 feet, to the Point of Beginning, containing 2,074.5 acres, of which the present road occupies 0.1745 acres, and being part of Clermont County Auditor's Parcel Number 360327.031.

The bearings for this description are based on Grid North, of the Ohio State Plane Coordinate System, South Zone, NAD83(2011), as measured with GPS.
This description was prepared and reviewed under the supervision of Steven L. Mullaney, professional Surveyor No. 7900, in May 2021.
PPN: 360327.031.

CERTIFICATION:

TO AMPLER DEVELOPMENT LLC, UNION BANK & TRUST COMPANY, AB BELLS LLC, ALFWARESS PROPERTIES LLC, AND FIDELITY NATIONAL TITLE INSURANCE COMPANY:

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2021 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 5, 6(b), 7(c), 7(b), 8, 9, 11(b), 13, 18, 19 AND 20 (APPENDIX A - ADDITIONAL TACO BELL SURVEY REQUIREMENTS) OF TABLE A THEREOF. FIELD WORK WAS COMPLETED ON NOVEMBER 10, 2021.

STEVEN L. MULLANEY, OHIO PROFESSIONAL SURVEYOR NO. 7900 DATE

WEST PLANE ST. (S.R. 125, VARIABLE WIDTH)





Table with columns: REV., DATE, DESCRIPTION. Row 1: 1, 2/10/2022, UPDATED TITLE

TACO BELL
W PLANE ST (S.R. 125)
BETHEL, OHIO 45106

Table with columns: ISSUED FOR, PERMIT, BID, CONSTRUCTION, RECORD. Values: SLM, JEK

JOB NO. 2021188.12

1 of 1

GPD GROUP logo and contact information: 520 South Main Street, Suite 2531 Akron, OH 44311

Drawing Name: C:\2021\2021188.12 - Bethel, OH (Amplifier Development)\12\_Field Services\03\_Land Survey\Basemap\2021188.12\_BASE.dwg February 10, 2022 - Hesch

## DEMOLITION NOTES

- CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS PRIOR TO ANY DEMOLITION PROCESS. CERTAIN ACTIVITIES ASSOCIATED WITH CONSTRUCTION WILL REQUIRE AIR PERMITS INCLUDING BUT NOT LIMITED TO: MOBILE CONCRETE BATCH PLANTS, MOBILE ASPHALT PLANTS, CONCRETE CRUSHERS, LARGE GENERATORS, ETC. THESE ACTIVITIES WILL REQUIRE SPECIFIC CURRENT STATE'S EPA OR LOCAL GOVERNING AUTHORITIES AIR PERMITS FOR INSTALLATION AND OPERATION. CONTRACTORS MUST SEEK AUTHORIZATION FROM THE CORRESPONDING GOVERNING BODIES. FOR DEMOLITION OF ALL COMMERCIAL SITES, A NOTIFICATION FOR RESTORATION AND DEMOLITION MUST BE SUBMITTED TO THE CURRENT STATE'S EPA AND LOCAL GOVERNING AUTHORITIES TO DETERMINE ANY CORRECTIVE ACTIONS THAT MAY BE REQUIRED.
- DEMOLITION INCLUDES THE FOLLOWING:
  - TRANSFER BENCHMARK CONTROL TO NEW LOCATIONS OUTSIDE THE DISTURBED AREA PRIOR TO COMMENCING DEMOLITION OPERATIONS (WHEN APPLICABLE).
  - DEMOLITION AND REMOVAL OF SITE IMPROVEMENTS NECESSARY FOR THE PROPOSED CONSTRUCTION OF NEW IMPROVEMENTS.
  - REROUTING, RELOCATING, DISCONNECTING, CAPPING OR SEALING, AND ABANDONING/REMOVING SITE UTILITIES IN PLACE (WHICHEVER IS APPLICABLE).
- REMOVE AND LEGALLY DISPOSE OF ITEMS CALLED OUT TO BE REMOVED. REMOVE AND TRANSPORT DEBRIS IN A MANNER THAT WILL PREVENT SPILLAGE ON ADJACENT SURFACES AND AREAS. THOSE ITEMS INDICATED TO BE REINSTALLED, SALVAGED, OR TO REMAIN SHALL BE CLEANED, SERVICED, AND OTHERWISE PREPARED FOR REUSE. CONTRACTOR TO STORE AND PROTECT AGAINST DAMAGE. REINSTALL ITEMS IN LOCATIONS INDICATED.
- PROTECT ITEMS INDICATED TO REMAIN AGAINST DAMAGE AND SOILING THROUGHOUT CONSTRUCTION. WHEN PERMITTED BY THE CONSTRUCTION MANAGER OR OWNER, ITEMS MAY BE REMOVED TO A SUITABLE, PROTECTED STORAGE LOCATION THROUGHOUT CONSTRUCTION AND THEN CLEANED AND REINSTALLED IN THEIR ORIGINAL LOCATIONS. PROMPTLY REPAIR DAMAGES TO ADJACENT FACILITIES CAUSED BY DEMOLITION OPERATIONS AT THE CONTRACTORS COST.
- CONTRACTOR SHALL SCHEDULE DEMOLITION ACTIVITIES WITH THE CONSTRUCTION/PROJECT MANAGER INCLUDING THE FOLLOWING:
  - DETAILED SEQUENCE OF DEMOLITION AND REMOVAL WORK, WITH STARTING AND ENDING DATES FOR EACH ACTIVITY.
  - DATES FOR SHUTOFF, CAPPING, AND CONTINUATION OF UTILITY SERVICES.
  - IDENTIFY AND ACCURATELY LOCATE UTILITIES AND OTHER SUBSURFACE STRUCTURAL, ELECTRICAL, OR MECHANICAL CONDITIONS.
- REGULATORY REQUIREMENTS: COMPLY WITH GOVERNING EPA NOTIFICATION REGULATIONS BEFORE STARTING DEMOLITION. COMPLY WITH HAULING AND DISPOSAL REGULATIONS OF AUTHORITIES HAVING JURISDICTION
- MAINTAIN EXISTING UTILITIES INDICATED TO REMAIN IN SERVICE AND PROTECT THEM AGAINST DAMAGE THROUGHOUT CONSTRUCTION OPERATIONS.
  - DO NOT INTERRUPT EXISTING UTILITIES SERVING OCCUPIED OR OPERATING FACILITIES. EXCEPT WHEN AUTHORIZED IN WRITING BY OWNER'S REPRESENTATIVE AND AUTHORITIES HAVING JURISDICTION. PROVIDE TEMPORARY SERVICES DURING INTERRUPTIONS TO EXISTING UTILITIES, AS ACCEPTABLE TO OWNER AND TO GOVERNING AUTHORITIES.
- LOCATE, IDENTIFY, DISCONNECT, AND SEAL OR CAP OFF INDICATED UTILITY SERVICES SERVING THE SITE. ARRANGE TO SHUT OFF AND CAP UTILITIES WITH UTILITY COMPANIES AND FOLLOW THEIR RESPECTIVE UTILITY KILL AND CAP POLICIES. DO NOT START DEMOLITION WORK UNTIL UTILITY DISCONNECTING AND SEALING HAVE BEEN COMPLETED AND VERIFIED IN WRITING BY THE UTILITY COMPANY.
- CONDUCT DEMOLITION OPERATIONS TO PREVENT INJURY TO PEOPLE AND DAMAGE TO ADJACENT BUILDINGS AND FACILITIES TO REMAIN. ENSURE SAFE PASSAGE OF PEOPLE AROUND DEMOLITION AREA. SAFE PASSAGE INCLUDES THE ERECTION OF TEMPORARY PROTECTION AND/OR BARRICADES AS PER LOCAL GOVERNING AUTHORITIES AND IN ACCORDANCE WITH THE CURRENT ADA REGULATIONS. USE OF EXPLOSIVES WILL NOT BE PERMITTED.
- CLEAN ADJACENT BUILDINGS AND IMPROVEMENT OF DUST, DIRT, AND DEBRIS CAUSED BY DEMOLITION OPERATIONS. RETURN ADJACENT AREAS TO CONDITION EXISTING BEFORE START OF DEMOLITION.
- PROMPTLY DISPOSE OF DEMOLISHED MATERIALS. DO NOT ALLOW DEMOLISHED MATERIALS TO ACCUMULATE ON-SITE. STORAGE OR SALE OF REMOVED ITEMS OR MATERIALS ON-SITE WILL NOT BE PERMITTED. NO BURNING OF ANY MATERIALS ON SITE SHALL BE PERMITTED.
- IT IS NOT EXPECTED THAT ASBESTOS WILL BE ENCOUNTERED IN THE COURSE OF THIS CONTRACT. IF ANY MATERIALS SUSPECTED OF CONTAINING ASBESTOS ARE ENCOUNTERED, DO NOT DISTURB THE MATERIALS. IMMEDIATELY NOTIFY THE CONSTRUCTION MANAGER AND THE OWNER.
- SURVEY THE CONDITION OF THE STRUCTURE TO DETERMINE WHETHER REMOVING ANY ELEMENT MIGHT RESULT IN A STRUCTURAL DEFICIENCY OR UNPLANNED COLLAPSE OF ANY PORTION OF THE STRUCTURE OR ADJACENT STRUCTURES THROUGHOUT CONSTRUCTION.
- DEMOLISH BUILDING AND STRUCTURAL PADS COMPLETELY AND REMOVE FROM THE SITE. USE METHODS REQUIRED TO COMPLETE WORK WITHIN LIMITATIONS OF GOVERNING REGULATIONS AND AS FOLLOWS:
  - DISPOSE OF DEMOLISHED ITEMS AND MATERIALS PROMPTLY.
  - DEMOLISH CONCRETE AND MASONRY IN SMALL SECTIONS.
  - BREAK UP AND REMOVE CONCRETE SLABS ON GRADE.
- BELOW-GRADE DEMOLITION: DEMOLISH FOUNDATION WALLS, PAVEMENTS, AND OTHER BELOW-GRADE DEMOLITION, AS FOLLOWS:
  - COMPLETELY REMOVE BELOW-GRADE DEMOLITION, INCLUDING FOUNDATION WALLS FOOTINGS, KNOWN AND UNKNOWN PAVEMENT SECTIONS INCLUDING UNDERLYING CONCRETE SLABS, AND OTHER BELOW GRADE CONCRETE SLABS FOUND DURING DEMOLITION (INCLUDING ITEMS WHICH MAY NOT BE IDENTIFIED HEREIN).
- FILLING BELOW-GRADE AREAS: COMPLETELY FILL BELOW-GRADE AREAS AND VOIDS RESULTING FROM DEMOLITION OF BUILDINGS, PAVEMENTS, AND OTHER REMOVED ITEMS WITH SOIL MATERIALS ACCORDING TO REQUIREMENTS PER SOILS REPORT AND ON-SITE GEOTECHNICAL ENGINEER'S REPRESENTATIVE. CONTRACTOR SHALL CONTACT GEOTECHNICAL ENGINEER PRIOR TO FILLING ANY AREAS TO OBSERVE FILL PROCEDURES.
- CONDUCT DEMOLITION OPERATIONS AND REMOVE DEBRIS TO ENSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, WALKS, AND OTHER ADJACENT OCCUPIED AND USED FACILITIES. DO NOT CLOSE OR OBSTRUCT STREETS, WALKS, OR OTHER ADJACENT OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM OWNER AND AUTHORITIES HAVING JURISDICTION. PROVIDE ALTERNATE ROUTES AROUND CLOSED OR OBSTRUCTED TRAFFIC WAYS IF REQUIRED BY GOVERNING REGULATIONS.
- CONTRACTOR TO WET SAWCUT EXISTING PAVEMENT TO REMAIN AT NEXT NEAREST JOINT PRIOR TO REMOVALS OF CURB, GUTTER, PAVEMENT, ETC.
- THE CONTRACTOR SHALL REMOVE EXISTING PAVEMENT MARKINGS WITH SMALL HANDHELD GRINDERS OR SCARIFIERS OR OTHER METHODS, WITH THE APPROVAL OF THE CONSTRUCTION MANAGER. TAKE CARE DURING MARKING REMOVAL NOT TO SCAR, DISCOLOR, OR OTHERWISE DAMAGE THE PAVEMENT SURFACE. DO NOT OVERPAINT OR USE OTHER METHODS OF COVERING MARKINGS INSTEAD OF REMOVAL.
- WHEN NOTED AND ALLOWED BY THE OWNER, THE CONTRACTOR MAY RE-USE EXISTING WHEELSTOPS FOR THE PROPOSED SITE. CONTRACTOR AND CONSTRUCTION MANAGER SHALL COORDINATE WHICH EXISTING WHEELSTOPS MAY BE RE-USED PRIOR TO DEMOLITION. CONTRACTOR SHALL ENSURE THAT ALL RE-USED WHEELSTOPS ARE PROTECTED DURING CONSTRUCTION.
- IF UNDERGROUND TANKAGE IS CALLED FOR DEMOLITION, THE CONTRACTOR SHALL COORDINATE REMOVAL AND REPLACEMENT WITH THE STATE BUREAU OF UNDERGROUND STORAGE TANK REGULATIONS (BUSTR). UNDERGROUND TANK REMOVAL SHALL ALSO INCLUDE THE REMOVAL OF ANY MONITORING WELLS, OIL/GAS WELLS, AND MINE SHAFTS, IN ACCORDANCE WITH GOVERNING AUTHORITIES HAVING JURISDICTION.
- CONTRACTOR SHALL FULLY SECURE WORK AREA WITH THE APPROPRIATE SIGNAGE, FENCING, AND BARRICADES WHICH ACCOMMODATE VISUALLY IMPAIRED PERSONS AS AGREED UPON WITH SITE CONSTRUCTION/PROJECT MANAGER AND OWNER TO WARN AND KEEP PEOPLE OUT OF THE SITE WORK AREA FOR THE DURATION OF THE PROJECT.

## GENERAL PLAN AND SURVEY NOTES

- PRIOR TO STARTING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING SURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED; NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AUTHORITIES.
- THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE SECTION OF THESE NOTES ENTITLED "GRADING PLAN NOTES" FOR DEFINITIONS AS MAY BE NECESSARY FOR "GEOTECHNICAL ENGINEER" AND "SOILS REPORT".
- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS, SPECIFICATIONS AND THE REQUIREMENTS AND STANDARDS OF THE LOCAL GOVERNING AUTHORITY. THE SOILS REPORT AND RECOMMENDATIONS SET FORTH THEREIN ARE A PART OF THE REQUIRED CONSTRUCTION DOCUMENTS AND TAKE PRECEDENCE UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION/PROJECT MANAGER OF ANY DISCREPANCY BETWEEN SOILS REPORT AND PLANS, ETC.
- THE CONTRACTOR SHALL, UPON BECOMING AWARE OF SUBSURFACE OR LATENT PHYSICAL CONDITIONS DIFFERING FROM THOSE DISCLOSED BY THE ORIGINAL SOIL EXPLORATION WORK, PROMPTLY NOTIFY THE OWNER VERBALLY TO PERMIT VERIFICATION OF THE CONDITIONS AND IN WRITING AS TO THE NATURE OF THE DIFFERING CONDITIONS. NO CLAIM BY THE CONTRACTOR FOR ANY CONDITIONS DIFFERING FROM THOSE ANTICIPATED IN THE PLAN AND SPECIFICATIONS AND DISCLOSED BY THE SOIL STUDIES WILL BE ALLOWED UNLESS THE CONTRACTOR HAS SO NOTIFIED THE OWNER, VERBALLY AND IN WRITING AS REQUIRED ABOVE, OF SUCH DIFFERING CONDITIONS.
- ALL WORK WITHIN THE RIGHTS OF WAY SHALL BE IN ACCORDANCE WITH THE GOVERNING JURISDICTION AND SPECIFICATIONS.
- CONTRACTOR SHALL COORDINATE ANY MAINTENANCE OF TRAFFIC WITH THE OWNER'S REPRESENTATIVE AND THE LOCAL JURISDICTION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL AT ALL TIMES ENSURE THAT SWPP MEASURES PROTECTING EXISTING DRAINAGE FACILITIES BE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY PHASE OF THE SITE CONSTRUCTION OR LAND ALTERATION. (SEE SWPP PLANS).
- ALL WORK SHALL BE COMPLETED IN A NEAT AND ORDERLY MANNER REMOVING ALL EXCESS MATERIAL AND WASTE FROM THE SITE INCLUDING TIMELY REMOVAL OF ANY CONCRETE SPLATTER. UPON COMPLETION OF PROJECT, CONTRACTOR SHALL CLEAN THE PAVED AREAS PRIOR TO REMOVAL OF TEMPORARY SEDIMENT CONTROLS, AS DIRECTED BY THE CITY AND/OR CONSTRUCTION/PROJECT MANAGER. IF POWER WASHING IS USED, NO SEDIMENT LADEN WATER SHALL BE WASHED INTO THE STORM SYSTEM. ALL SEDIMENT LADEN MATERIAL ON PAVEMENT OR WITHIN THE STORM SYSTEM SHALL BE COLLECTED AND REMOVED FROM THE SITE AT CONTRACTOR'S EXPENSE (SEE SWPP PLANS).
- THESE PROJECT CONSTRUCTION DOCUMENTS SHALL NOT CONSTITUTE A CONTRACTUAL RELATIONSHIP BETWEEN GPD GROUP AND THE CONTRACTOR / SUBCONTRACTOR / OR OTHER AFFILIATED PARTIES.
- THE ENGINEER WILL NOT BE RESPONSIBLE FOR CONSTRUCTION OR SAFETY, MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES UTILIZED IN CONSTRUCTION BY THE CONTRACTOR OR SUBCONTRACTORS. ANY SEQUENCING OR SUGGESTED NOTATIONS WHICH MAY APPEAR IN THE PLANS IS INTENDED TO ASSIST IN THE UNDERSTANDING OF PROJECT INTENT.
- DETAILS, NOTES, AND OTHER REFERENCES CONTAIN HEREIN MAY HAVE BEEN ATTAINED FROM OUTSIDE REFERENCE SOURCE LOCATIONS SUCH AS, BUT NOT LIMITED TO, LOCAL AUTHORITY AGENCIES, DESIGN REFERENCE MANUALS, MANUFACTURER'S RECOMMENDED DOCUMENTATION, OR OTHER INDUSTRY SOURCES. GPD DOES NOT WARRANT INFORMATION OR REPRESENTATION OF SAID CONTENT CONTAINED HEREIN. IT IS SHOWN SOLELY FOR REFERENCE ONLY OF DESIGN INTENT AT THE TIME OF PLAN PREPARATION. THE CONSTRUCTION TEAM MEMBERS (CONTRACTOR AND CONSTRUCTION MANAGER, WHERE APPLICABLE) SHALL OBTAIN THE MOST CURRENT DETAILED INFORMATION FROM THE RESPECTIVE SOURCE TO CONSTRUCT THE IMPROVEMENTS UNDER THE AUTHORITY OF THE RESPECTIVE GOVERNING AGENCIES. IF ANY DISCREPANCIES ARE DISCOVERED BETWEEN THE ORIGINAL DESIGN INTENT AND THE CONSTRUCTION TEAM OBTAINED REFERENCE MATERIAL, THE CONSTRUCTION MANAGER OR THE PROJECT'S CONTACT PERSON SHALL BE NOTIFIED PRIOR TO COMMENCING OF ASSOCIATED WORK.
- CONDUCT CONSTRUCTION OPERATIONS TO ENSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, WALKS, AND OTHER ADJACENT OCCUPIED AND USED FACILITIES. DO NOT CLOSE OR OBSTRUCT STREETS, WALKS, OR OTHER ADJACENT OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM OWNER AND AUTHORITIES HAVING JURISDICTION. PROVIDE ALTERNATE ROUTES AROUND CLOSED OR OBSTRUCTED TRAFFIC WAYS.
- THE A.L.T.A. SURVEY BY GPD GROUP, DATED JANUARY 4, 2022 SHALL BE CONSIDERED A PART OF THESE PLANS. THE G.C. IS RESPONSIBLE FOR LOCATING IMPROVEMENTS PER THESE PLANS.
- THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THE PLANS ARE BASED ON GENERAL FIELD SURVEYS. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO BECOME FAMILIAR WITH THE SITE'S POSSIBLE BELOW GRADE FEATURES, INCLUDING BUT NOT LIMITED TO, ROOMS, VAULTS, UTILITIES, ETC. AND SHALL CONDUCT A WALK THROUGH WITH THE OWNER'S REPRESENTATIVE. CONTRACTOR SHALL CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR REPAIR TO DAMAGE CAUSED BY THEIR WORK FORCE TO FACILITIES WHICH ARE NOT INTENDED TO BE DISTURBED.
- ALL DIMENSIONS, GRADES, AND UTILITY LOCATIONS SHOWN ON THESE PLANS WERE BASED ON THE SURVEY. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY CONSTRUCTION/PROJECT MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY CHANGES, NO EXTRA COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO INFORMATION SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.
- IN SOME CASES, THE DEVELOPER OR OWNER MAY HAVE PROVIDED THEIR OVERALL DEVELOPMENT PLANS FOR THE PROJECT DESIGN RATHER THAN A FIELD SURVEY. (SEE SITE PLAN FOR NOTES WHEN THIS IS THE CASE). ALL DIMENSIONS, GRADES, AND UTILITY LOCATIONS SHOWN ON THESE PLANS WERE BASED ON SAID DEVELOPMENT PLANS. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY CONSTRUCTION MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY CHANGES. NO EXTRA COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO INFORMATION SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.
- THE CONTRACTOR SHALL RUN AN INDEPENDENT VERTICAL CONTROL TRAVERSE TO CHECK BENCHMARKS AND A HORIZONTAL CONTROL TRAVERSE THROUGH THE REFERENCED PROJECT CONTROL DATUM TO CONFIRM GEOMETRIC DATA. IT IS THE CONTRACTORS RESPONSIBILITY TO NOTIFY THE CONSTRUCTION MANAGER OF ANY DISCREPANCIES PRIOR TO THE START OF CONSTRUCTION.

## CONCRETE NOTES AND SPECIFICATIONS

- ALL EXTERIOR SITE SPECIFIC PORTLAND CEMENT CONCRETE (PCC) (I.E. SIDEWALK, PAVEMENT OR CURBING) SHALL MEET THE MINIMUM REQUIREMENTS OF THE LATEST EDITIONS OF THE STATE DEPARTMENT OF TRANSPORTATION (DOT) AND THE AMERICAN CONCRETE INSTITUTE (ACI) SPECIFICATIONS USING THE RESPECTIVE ASTM STANDARDS FOR MATERIALS USED, MIXING, TRANSPORTATION, FORMING, PLACEMENT, CURING, AND SEALING. THE MINIMUM STRENGTH FOR NORMAL WEIGHT CONCRETE IS 4000 PSI AT 28 DAY STRENGTH. CONTRACTOR SHALL REFER TO DETAILS, NOTES, AND SPECIFICATIONS WITHIN THE CONSTRUCTION DOCUMENTS FOR VARIATIONS TO THIS SPECIFICATION. MIX DESIGN SHOP DRAWINGS SHALL BE TAILORED TO THE ACTUAL FIELD PLACEMENT CONDITIONS AND BE SUBMITTED TO THE CONSTRUCTION/PROJECT MANAGER IN ACCORDANCE WITH THE PROJECT REQUIREMENTS.
 

SLAB THICKNESS - "T"	MAXIMUM JOINT SPACING
LESS THAN 4 INCHES	8 FEET
4 - < 5 INCHES	10 FEET
5 - < 6 INCHES	12.5 FEET
6 INCHES - < 8 INCHES	15 FEET
8 INCHES - 10 INCHES	15 FEET
- ALL EXTERIOR CONCRETE CURBS SHALL HAVE JOINTS PER ACI 330. CURB JOINTS ARE TO ALIGN WITH CONCRETE PAVEMENT JOINTS WHERE APPLICABLE, TYPICALLY BEING 10 FT TO 12 FT. ALL EXTERIOR VEHICULAR CONCRETE PAVEMENT AND FLATWORK SHALL HAVE CONTROL JOINTS PER TABLE BELOW AND EXPANSION JOINTS PER ACI 330 TYPICAL RECOMMENDATIONS.
 

SLAB THICKNESS - "T"	MAXIMUM JOINT SPACING
LESS THAN 4 INCHES	8 FEET
4 - < 5 INCHES	10 FEET
5 - < 6 INCHES	12.5 FEET
6 INCHES - < 8 INCHES	15 FEET
8 INCHES - 10 INCHES	15 FEET
- ALL JOINTS, INCLUDING SAWED JOINTS, SHALL BE SEALED. JOINTS SHALL BE CLEANED AND DRIED PRIOR TO SEALING. JOINT SEALING MATERIALS SHALL COMPLY WITH ASTM D 3406 FOR HOT APPLIED ELASTOMERIC, TT-S-001543A FOR SILICONE RUBBER, AND TT-S-00230S FOR SINGLE COMPONENT ELASTOMERIC SEALER WIDTH, DEPTH, AND PREPARED APPLICATION SURFACES SHALL BE PER MANUFACTURERS RECOMMENDATIONS. JOINT FILLER MATERIAL SHALL CONFORM TO ASTM D1751 OR ASTM D8139 AND EXTEND THE FULL DEPTH OF CONTACTING SURFACE.
- ALL CONCRETE PANELS SHALL BE SQUARE WITH A LENGTH TO WIDTH RATIO NO GREATER THAN 1.25 TO 1 AND HAVE A MEDIUM BROOM FINISH (TRANSVERSE, SLIP RESISTANT FOR PEDESTRIAN PATHWAYS) WHICH SHALL BE TO MINIMUM STRENGTH PRIOR TO OPENING FOR VEHICULAR TRAFFIC AREAS. STAGGERED/OFFSET JOINT, INTERIOR CORNERS, ANGLES LESS THAN 60 DEGREES, SLABS LESS THAN 18-INCHES WIDE, AND ODD SHAPES SHALL NOT BE PERMITTED. BLOCKOUTS AROUND ALL PAVEMENT CASTINGS SHALL BE PROVIDED IN ACCORDANCE WITH ACI RECOMMENDATIONS.
- ALL JOINTING (IF) SHOWN HEREIN IS ONLY A GENERAL GUIDELINE OF DESIGN INTENT. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FINAL LAYOUT OF THE JOINTING WHICH COINCIDES WITH THEIR MEANS AND METHODS TO ENSURE NO UNDESIRED CRACKS FORM THROUGH ANY PLACED CONCRETE. JOINTS SHALL BE APPROPRIATELY PLACED AS SOON AS POSSIBLE TO KEEP UNNECESSARY CRACKS FROM DEVELOPING. CONTRACTOR SHALL SUBMIT SHOP DRAWING OF THEIR PAVEMENT JOINT LAYOUT TO OWNER / CONSTRUCTION MANAGER PRIOR TO PLACEMENT FOR RECORD. THE CONTRACTOR SHALL REPLACE ANY CRACKED CONCRETE, WHICH HAS NOT BEEN PLACED/FINISHED IN ACCORDANCE WITH ACI STANDARDS, TO THE NEXT JOINT PAST THE EFFECTED AREA AT NO ADDITIONAL COST TO THE PROJECT WITHIN ONE YEAR OF PROJECT COMPLETION.
- DESIGN INTENT CONCRETE AND SHALL CONFORM TO THE FOLLOWING MINIMUM AND MAXIMUM VALUES:
 

a. STRENGTH	PER MIX DESIGN, MINIMUM 4000 PSI
b. PORTLAND CEMENT CONTENT	550 LB / CY (ASTM C150 TYPE III)
c. POZZOLAN MATERIALS (SEE NOTES BELOW)	SILICA FUME MAY REPLACE MAX. 7% CEMENT FLY ASH OR SLAG CEMENT MAY REPLACE MAX. 2% CEMENT
d. MAX W/C RATIO	PER MIX DESIGN, MAXIMUM 0.45
e. ENTRAINED AIR	6.5% AVG ± 1.5% (7.0% TARGET) ASTM C260
f. SLUMP	4" MAX WITHOUT WATER REDUCER
g. SLUMP WITH HRWR OR MID RANGE WR	6" TO 8"
h. WATER REDUCER	NORMAL TYPE A (ASTM C494)
i. RETARDER	NORMAL TYPE B OR D AS NEEDED (REQUIRED IF CONCRETE TEMPERATURE EXCEEDS 85F)
j. CONCRETE TEMPERATURE AT PLACEMENT	50F-90F
k. ACCELERATOR	NON-CHLORIDE TYPE ONLY - CALCIUM CHLORIDE IS PROHIBITED
l. FIBERS TO BE USED	POLYPROPYLENE OR POLYETHYLENE
FOR SHRINKAGE CRACK CONTROL - (CURBS, WALKS, STEPS, RAMPS)	MICRO SYNTHETIC FIBERS @ 1.5 LBS / CY (FIBERMESH 300 OR APPROVED EQUAL)
- FOR USE AS W.W.F. REPLACEMENT (VEHICULAR TRAFFIC PAVEMENT)	MACRO SYNTHETIC FIBERS @ 4.0 LBS / CY (TUF-STRAND SF OR APPROVED EQUAL)
- ALL SYNTHETIC FIBERS SHALL BE TYPE III PER ASTM C1116 AND ASTM D7508. MACRO FIBERS SHALL BE 1.5 TO 2.25 INCHES IN LENGTH.
- ALL REINFORCING STEEL SHALL CONFORM TO ASTM A615, ASTM A1064, ASTM A307, AND ASTM A775. WHEN USED, ALL W.W.F. SLAB REINFORCEMENT SHALL BE SUPPORTED ON CHAIRS AND BE FLAT SHEETS ONLY. ZINC REPAIR MATERIAL SHALL CONFORM TO ASTM A780.
- CONCRETE SHALL ARRIVE AT JOB SITE WITH APPROPRIATE W/C RATIO. NO WATER SHALL BE ADDED TO CONCRETE ON SITE WHICH EXCEEDS THE MAXIMUM ALLOWED W/C RATIO AS INDICATED BY THE WRITTEN BATCH PLANT TICKET FROM THE SUPPLIER. SUPERPLASTICIZER AND/OR OTHER ADMIXTURES MAY BE UTILIZED TO ACHIEVE DESIRED WORKABILITY AND TO ACCOUNT FOR ADVERSE PLACEMENT CONDITIONS. ADMIXTURES SHALL BE UTILIZED ONLY IN ACCORDANCE WITH THE MANUFACTURERS WRITTEN INSTRUCTIONS AND MEET THE REQUIREMENTS OF ASTM C494 AND/OR ASTM C1017.
- CONTRACTOR SHALL HAVE A MIN. 5 YEARS EXPERIENCE WITH SUCCESSFUL PLACEMENT OF CONCRETE UTILIZING POZZOLAN MATERIALS. MIX DESIGNS WHICH UTILIZED POZZOLAN MATERIALS SHALL BE IN ACCORDANCE WITH LOCAL DOT SPECIFICATIONS AND ACI STANDARDS. FLY ASH SHALL MEET THE REQUIREMENTS OF ASTM C618 CLASS C OR CLASS F EXCEPT THE LOSS ON IGNITION MUST NOT EXCEED 5%. SLAG CEMENT ACCORDING TO ASTM C899, GRADE 100 MINIMUM. SILICA FUME SHALL BE DRY DENSIFIED MEETING THE REQUIREMENTS OF ASTM C1240. USE OF MATERIALS SHALL BE IN ACCORDANCE WITH ACI 211.1.
- AGGREGATES SHALL BE LOW-SHRINKAGE / WELL GRADED PER ASTM C33 AND THE LOCAL DOT SPECIFICATIONS WHICH ARE RESISTANT TO FREEZE / THAW, SULFATE ATTACK, AND ARE NOT ALKALI-CARBONATE AGGREGATES OR SUSCEPTIBLE TO ALKALI-AGGREGATE REACTIVITY. SLAG AGGREGATES SHALL NOT BE PERMITTED IN ANY CONCRETE MIX.
- LIQUID MEMBRANE FORMING CURING COMPOUNDS SHALL BE PER ASTM C1315 TYPE II CLASS A IN ACCORDANCE WITH ACI 308. LIQUID MEMBRANE FORMING CURING COMPOUNDS SHALL BE WHITE PIGMENTED AND TWO COATS APPLIED IN TWO PERPENDICULAR UNIFORM APPLICATIONS PER MANUFACTURERS RECOMMENDATIONS WITHIN THE ALLOWABLE TIME PERIODS. APPLICATIONS SHALL BE PHOTOGRAPH DOCUMENTED FOR EVEN AND CONSISTENT COVERAGE SIMILAR TO THE APPEARANCE OF A BLANK WHITE SHEET OF COPY PAPER. NO POOLING OF MATERIAL SHALL BE ACCEPTED.
- CONCRETE SEALER SHALL BE APPLIED IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS. A WRITTEN STATEMENT FROM THE MANUFACTURE FOR THE SEALER AND CURING COMPOUND SHALL BE PROVIDED GUARANTEEING COMPATIBILITY.
- REFER TO ACI INDUSTRY STANDARDS FOR CONCRETE PLACEMENT AND INSTALLATION. CONTRACTOR SHALL INCLUDE PROVISIONS IN ACCORDANCE WITH ACI 305R AND 306R FOR HOT AND COLD WEATHER PLACEMENT WHEN PROJECT SCHEDULE TIMING FALLS WITHIN THE REQUIRED TEMPERATURE RANGES PER ACI AND THE LOCAL DOT.

## GRADING PLAN NOTES

- A SOILS REPORT HAS BEEN PREPARED BY TERRACON CONSULTANTS, INC., DATED FEBRUARY 22, 2022 AND SHALL BE CONSIDERED TO BE A PART OF THIS PLAN SET.
- BEFORE STARTING GRADING OPERATIONS, SEE STORMWATER POLLUTION PREVENTION PLAN, NOTES AND DETAILS (SWPP), LANDSCAPE PLAN AND SOILS REPORT FOR TREATMENT OF EXISTING GRADE.
- PRIOR TO SITE CONSTRUCTION ACTIVITY, THE CONTRACTOR SHALL INSTALL ALL SWPP MEASURES TO PROTECT EXISTING DRAINAGE FACILITIES. CONTRACTOR SHALL PREVENT SILTATION FROM LEAVING THE SITE AT ALL TIMES.
- STRIP BUILDING AND PAVEMENT AREAS OF ALL ORGANIC TOPSOILS. STOCKPILE SUITABLE TOPSOILS FOR RESPREADING ONTO LANDSCAPE AREAS. ALL EXCESS EXCAVATED MATERIALS SHALL BE REMOVED FROM THE SITE AT THE CONTRACTOR'S EXPENSE. SEE GEOTECHNICAL REPORT FOR STRIPPING AND TOPSOIL REQUIREMENTS.
- OBTAIN APPROVED BORROW SOIL MATERIALS OFF-SITE WHEN SUFFICIENT SATISFACTORY SOIL MATERIALS ARE NOT AVAILABLE ON-SITE.
- SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SOFT, YIELDING OR UNSUITABLE MATERIALS AND REPLACING WITH SUITABLE MATERIALS AS SPECIFIED IN THE SOILS REPORT. UNLESS OTHERWISE SPECIFIED IN THE PLANS, SPECIFICATIONS, OR SOILS REPORT THE SITE GRADING, EXCAVATION, AND EMBANKMENT SHALL BE IN ACCORDANCE WITH THE STATE DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS.
- AT A MINIMUM ALL EXCAVATED OR FILLED AREAS SHALL BE COMPACTED TO 96% OF STANDARD PROCTOR MAXIMUM DRY DENSITY PER A.S.T.M. TEST D-698. MOISTURE CONTENT AT TIME OF PLACEMENT SHALL NOT EXCEED 2% ABOVE NOR 2% BELOW OPTIMUM. THE CONTRACTOR SHALL FOLLOW THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT AND RETAIN A QUALIFIED SOILS ENGINEER REGISTERED WITHIN THE STATE TO ENSURE COMPLIANCE WITH THE GEOTECHNICAL REPORT. MAKE GEOTECHNICAL RECOMMENDATIONS BASED ON FIELD CONDITIONS, AND ENSURE THAT ALL SHORING AND DEWATERING MEANS AND METHODS WILL NOT COMPROMISE THE STABILITY OF EXISTING OR PROPOSED FOOTINGS/FOUNDATIONS. THE OWNER SHALL RECEIVE ALL COMPACTION REPORTS PREPARED BY THE CONTRACTOR'S GEOTECHNICAL ENGINEER, VERIFYING THAT ALL FILLED AREAS AND SUBGRADE AREAS WITHIN THE BUILDING PAD AREA AND AREAS TO BE PAVED HAVE BEEN COMPACTED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT. NOTIFY PROJECT CONSTRUCTION MANAGER IF ANY UNSUITABLE SOILS ARE FOUND.
- FOLLOWING GRADING OF SUBSOIL TO SUBGRADE ELEVATIONS THE CONTRACTOR SHALL PLACE TOPSOIL TO A 6" DEPTH (UNLESS OTHERWISE SPECIFIED IN LANDSCAPING DETAILS) IN ALL DISTURBED AREAS WHICH ARE NOT TO BE PAVED. SMOOTHLY FINISH GRADE TO MEET SURROUNDING LAWN AREAS AND ENSURE POSITIVE DRAINAGE. STOCKPILED TOPSOIL SHALL BE SCREENED PRIOR TO RESPREADING. TOPSOIL SHALL BE FREE OF SUBSOIL, DEBRIS, BRUSH AND STONES LARGER THAN 1" IN ANY DIMENSION. ROCK HOUNDING IN PLACE WILL NOT BE PERMITTED. ALL EXCESS TOPSOIL SHALL BE LEGALLY DISPOSED OF OFF SITE.
- ELEVATIONS GIVEN ARE AT BOTTOM FACE OF CURB AND/OR FINISHED PAVEMENT GRADE UNLESS OTHERWISE SPECIFIED ON GRADING PLAN. ALL PAVEMENT SHALL BE LAID ON A STRAIGHT, EVEN, AND UNIFORM GRADE WITH A MINIMUM OF 1% SLOPE TOWARD THE COLLECTION POINTS UNLESS OTHERWISE SPECIFIED ON THE GRADING PLAN. DO NOT ALLOW NEGATIVE GRADES OR PONDING OF WATER.
- SLOPE BUILDING SIDEWALK AWAY FROM THE BUILDING AT A MAXIMUM OF 1.5% (UNLESS OTHERWISE INDICATED ON THE GRADING PLAN).
- WHEN CONSTRUCTING ASPHALTIC CONCRETE PAVEMENTS, CONTRACTOR SHALL PROVIDE BUTT END JOINT TO MEET EXISTING PAVEMENT IN ELEVATION AT DRIVE RETURNS AND ENSURE POSITIVE DRAINAGE.

## GENERAL UTILITY NOTES

- CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES IMMEDIATELY AFTER BID IS AWARDED AND ENSURE THE UTILITY COMPANIES HAVE THE ESSENTIALS REQUIRED FOR COMPLETE SERVICE INSTALLATION. CONTRACTOR SHALL NOTIFY CONSTRUCTION MANAGER OF ANY TIME FRAMES ESTABLISHED BY UTILITY COMPANIES WHICH WILL NOT MEET OPENING DATE.
- CONTRACTOR SHALL VERIFY THE SIZE, LOCATION, INVERT ELEVATION, AND CONDITION OF EXISTING UTILITIES WHICH ARE INTENDED TO BE UTILIZED AS A CONNECTION POINT FOR ALL PROPOSED UTILITIES PRIOR TO ANY CONSTRUCTION. CONTRACTOR TO ENSURE EXISTING UTILITIES ARE IN GOOD CONDITION AND FREE FLOWING (IF APPLICABLE). IF ELEVATIONS, SIZE, OR LOCATION DIFFER FROM WHAT IS SHOWN ON PLANS, CONTRACTOR SHALL NOTIFY CONSTRUCTION MANAGER IMMEDIATELY.
- WHERE PLANS PROVIDE FOR PROPOSED WORK TO BE CONNECTED TO, OR CROSS OVER AN EXISTING SEWER OR UNDERGROUND UTILITY, THE CONTRACTOR SHALL LOCATE THE EXISTING PIPES OR UTILITIES BOTH AS TO LINE AND GRADE BEFORE STARTING THE PROPOSED WORK. IF IT IS DETERMINED THAT THE ELEVATION OF THE EXISTING CONDUIT, OR EXISTING APPURTENANCE RESULTS IN A CHANGE IN THE PLAN, THE CONSTRUCTION MANAGER SHALL BE NOTIFIED BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED WORK WHICH WOULD BE AFFECTED BY THE INTERFERENCE WITH AN EXISTING FACILITY. PAYMENT FOR ALL THE OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT ITEM.
- UTILITY SERVICE PROVIDERS RULES AND REQUIREMENTS TAKE PRECEDENCE OVER INFORMATION HEREIN. IF DISCREPANCY ARISES, CONTRACTOR SHALL FULLY COORDINATE WITH UTILITY SERVICE PROVIDER PRIOR TO START OF CONSTRUCTION.

## SANITARY SEWER NOTES

- SANITARY SEWER LATERAL INVERT AT BUILDING SHALL BE A MINIMUM OF 3' BELOW FINISH FLOOR.
- CLEAN-OUTS TO BE INSTALLED AT ALL PIPE BENDS AND ANGLES, UNLESS A MANHOLE IS INDICATED.
- THE CONTRACTOR SHALL HIRE A LOCAL PLUMBER LICENSED WITH THE LOCAL SANITARY JURISDICTION TO MAKE ALL CONNECTIONS FROM THE BUILDING TO THE EXISTING SEWER. CONTRACTOR SHALL SECURE A SANITARY SEWER CONNECTION PERMIT PRIOR TO ANY CONSTRUCTION. THE CONTRACTORS PRICE FOR SANITARY SEWER INSTALLATION SHALL INCLUDE ALL FEES AND APPURTENANCES REQUIRED BY THE LOCAL SANITARY JURISDICTION TO PROVIDE A COMPLETE WORKING SERVICE. COORDINATE ALL WORK WITH CLEMONT COUNTY ENGINEER'S OFFICE, DOUG ROYER @ 513-732-8857. CONTRACTOR SHALL OBTAIN A UTILITY PERMIT FOR WORK IN THE RIGHT OF WAY.
- ALL SANITARY PIPE MATERIAL SHALL BE 6" PVC, SDR 35 CONFORMING TO ASTM D 3034, WITH JOINTS PER ASTM 3212 UNLESS OTHERWISE REQUIRED BY THE LOCAL JURISDICTION.

## WATER NOTES

- WATER SERVICE MATERIALS SHALL BE COPPER TYPE "K" UNLESS OTHERWISE NOTED ON PLANS. DIAMETER SHALL BE AS NOTED ON THESE PLANS AND SHALL BE INSTALLED WITH A MINIMUM COVER OF 48" OR BELOW FROST LINE, WHICHEVER IS GREATER.
- CONSTRUCTION AND MATERIALS PROVIDED BY THE WATER COMPANY:
  - TAP MAIN.
  - FURNISH AND INSTALL WATER METER.
  - FURNISH AND INSTALL SHORT WATER STUB OUT OF METER FOR 305R AND 306R.
  - COORDINATE ALL WORK WITH THE VILLAGE OF BETHEL, TRAVIS DOTSON @ 513-734-2243 EXT. 10.
- CONSTRUCTION AND MATERIALS PROVIDED BY THE CONTRACTOR:
  - FURNISH AND INSTALL COPPER SERVICE LINE FROM STUBBED LOCATION TO BUILDING.
  - ALL TRENCHING AND BACKFILLING.

## STORM SEWER NOTES

- ALL STORM SEWER PIPE 12" OR GREATER IN DIAMETER SHALL BE CORRUGATED HIGH DENSITY POLYETHYLENE (HDPE) SMOOTH INTERIOR PIPE UNLESS OTHERWISE NOTED ON PLAN OR RCP. CL IV. HDPE PIPE SHALL CONFORM TO ASTM D 3350 AND JOINTS PER ASTM F477. RCP PIPE SHALL CONFORM TO ASTM C76, AND JOINTS PER ASTM S-443. STORM SEWER LESS THAN 12" IN DIAMETER SHALL BE PVC, SDR 35. PER ASTM D 3034 AND JOINTS PER ASTM J 3212 (OR APPROVED EQUAL).
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRENCHING, BACKFILLING AND PIPE INSTALLATION, PIPE MATERIAL AND TAP CONNECTION. COORDINATE ALL WORK WITH THE CLEMONT COUNTY ENGINEER'S OFFICE DOUG ROYER @ 513-732-8857.
- ALL DRAINAGE STRUCTURES AT PAVEMENT SUMPS SHALL HAVE FINGER DRAINS PER DETAILS IN PLANS.

## ELECTRICAL NOTES

- SEE ELECTRICAL DRAWINGS FOR SITE LIGHTING AND LUMINAIRE DESCRIPTION.
- SEE ELECTRICAL SHEETS FOR ALL DEDICATED EXTERIOR BUILDING AND SIGN LIGHTING SCHEDULES. ELECTRICAL CONTRACTOR SHALL BALANCE LOADS WHERE REQUIRED.
- WHEN INSTALLING VERTICAL SWEEPS FOR UTILITY CONDUITS, CONTRACTOR SHALL USE SCHEDULE 80 DUCTS OF THE SIZE SHOWN ON THE PLANS.

CONTRACTOR TO COORDINATE ALL WORK, PERMITS AND FEES WITH VILLAGE OF BTHEL UTILITIES DEPARTMENT TRAVIS DOTSON @ 513-734-2243 EXT. 10.

## TELEPHONE NOTES

- CONTRACTOR TO COORDINATE ALL WORK, PERMITS AND FEES WITH SPECTRUM @ 844-521-5419.
- CONTRACTOR SHALL COORDINATE THE NUMBER OF LINES REQUIRED WITH THE CONSTRUCTION/PROJECT MANAGER.

































## NATURAL GAS NOTES

CONTRACTOR TO COORDINATE ALL WORK, PERMITS AND FEES WITH VILLAGE OF BETHEL UTILITIES DEPARTMENT, TONY GISKA @ 513-979-5419.

## CABLE NOTES

- INSTALL 4" CABLE TVSS CONDUIT PER VILLAGE, STATE OR NEC CODE, WHICHEVER IS MORE STRINGENT (FOR FUTURE USE). SEE ELECTRICAL SHEETS FOR DETAILS. TERMINATE CABLE CONDUIT AT RIGHT-OF-WAY. PROVIDE END CAP AND NOTE LOCATION ON AS-BUILT DRAWINGS.

## EXISTING GENERAL LEGEND

	EXISTING IRON PIN FOUND AS NOTED
	EXISTING IRON PIPE FOUND AS NOTED
	EXISTING CONCRETE MONUMENT FOUND AS NOTED
	5/8" x 30" REBAR WITH CAP "GPD" SET
	EXISTING POWER & TELEPHONE POLE
	EXISTING ELECTRIC TELEPHONE
	EXISTING TRANSFORMER
	EXISTING ELECTRIC PULLBOX
	EXISTING CATCH BASIN
	EXISTING SANITARY MANHOLE
	EXISTING FIRE HYDRANT
	EXISTING WATER METER
	EXISTING WATER VALVE
	EXISTING DRILLED WATER WELL
	EXISTING TELEPHONE PEDESTAL
	EXISTING POST OR BOLLARD
	EXISTING SIGN
	EXISTING GUY WIRE
	EXISTING MAIL BOX
	EXISTING ROCK/BOULDER
	EXISTING CONCRETE PAD/AREA/SIDEWALK
	EXISTING CURB
	EXISTING PROPERTY LINE
	EXISTING RIGHT OF WAY LINE
	EXISTING OVERHEAD UTILITY LINES
	EXISTING UNDERGROUND GAS LINES
	EXISTING UNDERGROUND STORM LINES
	EXISTING UNDERGROUND SANITARY LINES
	EXISTING UNDERGROUND WATER LINES
	EXISTING UNDERGROUND ELECTRIC LINES
	EXISTING UNDERGROUND TELEPHONE LINES
	

## GENERAL NOTES

- ALL WORK SPECIFIED AS A DEPARTMENT OF TRANSPORTATION ITEM SHALL BE GOVERNED BY THE OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS AS WELL AS THE CURRENT EDITION OF THE LOCAL JURISDICTION STORM WATER MANAGEMENT MANUAL. IT IS THE CONTRACTOR'S RESPONSIBILITY TO POSSESS AND TO BE FAMILIAR WITH APPLICABLE SECTIONS.
- THESE CONTRACT DRAWINGS SHALL BE MADE AVAILABLE ON SITE AT ALL TIMES AND PRESENTED UPON REQUEST. IF UNFORESEEN STORM WATER POLLUTION IS ENCOUNTERED, ADDITIONAL STORM WATER POLLUTION PREVENTION (SWPP) MEASURES SHALL BE IMPLEMENTED TO MANAGE THE CURRENT SITE CONDITIONS WHICH MAY BE REQUESTED BY THE OWNER, COUNTY ENGINEER, PROJECT ENGINEER OR SOIL AND WATER CONSERVATION SERVICE REPRESENTATIVE AT ANYTIME. SUCH REQUESTS AND CHANGE IN SITE CONDITIONS SHALL BE IMPLEMENTED IMMEDIATELY AT CONTRACTOR'S EXPENSE.
- ALL STORM WATER POLLUTION PREVENTION PRACTICES SHALL BE INSTALLED BEFORE ANY OTHER EARTH MOVING OCCURS.
- SEDIMENT BARRIERS SHALL BE INSTALLED DOWNSLOPE OF DISTURBED AREAS. SEDIMENT BARRIERS SHALL BE INSTALLED ALONG LEVEL CONTOURS, MAXIMUM CONTRIBUTING DRAINAGE AREA TO SEDIMENT BARRIERS SHALL BE PER THE CURRENT STATE'S EPA OR THE LOCAL AUTHORITY REQUIREMENTS. COMPOSITE FILTER SOCKS USED IN LIEU OF SILT FENCE SHALL BE A MINIMUM OF 12 INCHES IN DIAMETER.
- SILT BARRIERS SHALL BE INSTALLED AROUND ALL EXISTING AND NEW STORM INLETS, CATCH BASINS AND YARD DRAINS. INSTALL ROCK CHECK DAMS FOR HEADWALL INLETS FOR STORM WATER POLLUTION PREVENTION.
- STORM WATER POLLUTION PREVENTION MEASURES SHALL BE INSTALLED AROUND ALL DIRT OR TOPSOIL STOCKPILES AND OTHER TEMPORARILY DISTURBED AREAS AS MAY BE SHOWN ON THESE PLANS AND/OR AS DIRECTED BY THE ENGINEER OR THE LOCAL AUTHORITY HAVING JURISDICTION.
- SILT BARRIERS, CONSTRUCTION ENTRANCES, AND SILT PERIMETER CONTROLS SHALL REMAIN IN PLACE UNTIL A GOOD STAND OF GRASS HAS BEEN OBTAINED AND/OR PAVING OPERATIONS ARE COMPLETE. CONTRACTOR SHALL KEEP SILT FROM ENTERING ANY STORM DRAINAGE SYSTEM. ONCE SITE HAS BEEN COMPLETELY STABILIZED, ANY SILT IN PIPES AND DRAINAGE SWALES SHALL BE REMOVED WITHIN 10 DAYS.
- ALL EXISTING WATER COURSES WITHIN THE PROJECT LIMITS SHALL BE TEMPORARILY PROTECTED DURING LAND CLEARING AND GRADING OPERATIONS. SOILS WITHIN 50 FEET OF SAID WATER COURSES SHALL BE STABILIZED WITHIN 2 DAYS OF THE INITIAL CLEARING / GRADING OPERATION.
- CONSTRUCTION ENTRANCE SHALL BE UTILIZED. IF CONDITIONS ARE SUCH THAT MUD IS COLLECTING ON VEHICLE TIRES, THE TIRES MUST BE CLEANED BEFORE THE VEHICLES ENTER THE PUBLIC ROADWAY. THE SITE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING OR FLOW OF MUD ONTO THE PUBLIC RIGHT-OF-WAY. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO THE ROADWAY MUST BE REMOVED PROMPTLY.
- IF FOR ANY REASON, THE PROJECT IS SUSPENDED, THE CONTRACTOR SHALL ENSURE THAT ALL INSTALLED EROSION MEASURES ARE FUNCTIONING AND PROPERLY MAINTAINED DURING THIS PERIOD, AND THAT ALL BARE SOILS ARE SEEDED AND MULCHED WITH TEMPORARY SEED MIXTURE.
- CONCRETE WASHOUT FACILITY (IF APPLICABLE) SHALL BE CONSTRUCTED IN ACCORDANCE WITH PLAN DETAILS AND LOCAL GOVERNING AUTHORITY REGULATIONS AND INSTRUCTIONS.
- IMPLEMENTATION OF EROSION AND SEDIMENT CONTROLS SHALL CONFORM TO STATE OF OHIO CONSTRUCTION GENERAL PERMIT OHC000005 AND CLERMONT COUNTY CODIFIED ORDINANCES. IF A CONFLICT EXISTS BETWEEN THE TWO REGARDING EROSION AND SEDIMENT CONTROL IMPLEMENTATION, THE MORE RESTRICTIVE SHALL APPLY.
- DISTURBED AREAS WITHIN 50' OF A STREAM SHALL HAVE PERMANENT STABILIZATION APPLIED WITHIN 2 DAYS OF FINAL GRADE.
- DISTURBED AREAS WHICH WILL REMAIN DORMANT FOR OVER 1 YEAR OR ARE AT FINAL GRADE SHALL HAVE PERMANENT STABILIZATION APPLIED WITHIN 7 DAYS OF LAST EARTHWORK DISTURBANCE.

## INSPECTION NOTES

- CONTRACTOR SHALL INSPECT ALL SWPP MEASURES DAILY AND LOGGED BY THE CONTRACTOR FOR INSPECTION. LOGGING SHALL BE WEEKLY AND AFTER EVERY 1/2" RAINFALL EVENT. REPAIR AS NECESSARY TO PREVENT EROSION. SILTATION SHALL BE REMOVED FROM AREAS WHERE FAILURES HAVE OCCURRED AND CORRECTIVE ACTION TAKEN WITHIN 24 HOURS TO MAINTAIN ALL SWPP.
- CONTRACTORS INSPECTOR SHALL BE A QUALIFIED INDIVIDUAL. ONLY A QUALIFIED INSPECTION PERSONNEL IS TO PERFORM THE INSPECTIONS. SITE INSPECTIONS SHALL BE DONE WEEKLY AND WITHIN 24 HRS AFTER EVERY RAINFALL EVENT EXCEEDING 1/2" OF RAINFALL. ALL NECESSARY REPAIRS SHOULD BE IMPLEMENTED IMMEDIATELY AFTER SUCH INSPECTIONS.
- CONTRACTOR'S INSPECTOR SHALL BE RESPONSIBLE FOR PREPARING AND SIGNING WEEKLY AND ALL INTERMEDIATE EROSION CONTROL INSPECTION REPORTS AFTER EVERY INSPECTION, WHICH INCLUDE BUT NOT LIMITED TO (DISTURBED AREAS, MATERIAL STORAGE AREAS, EROSION AND SEDIMENT CONTROLS; DISCHARGE LOCATIONS AND VEHICLE ENTRANCE/EXIT LOCATIONS). SUCH REPORTS SHALL BE MADE AVAILABLE TO OWNER, ENGINEER AND CITY / STATE OFFICIALS UPON THEIR REQUEST.
- REPORTS SHALL BE KEPT FOR 3 YEARS AFTER TERMINATION OF THE CONSTRUCTION ACTIVITIES.
- CONTRACTOR MAY SUBMIT A WAIVER REQUEST TO THE LOCAL AND STATE GOVERNING AUTHORITIES FOR A REDUCTION TO MONTHLY INSPECTIONS IF THE SITE WILL BE STABILIZED AND DORMANT FOR A LONG PERIOD, AND/OR THE RUNOFF IS UNLIKELY DUE TO WEATHER CONDITIONS FOR AN EXTENDED PERIOD OF TIME (FROZEN GROUND).
- FOR BMPS THAT REQUIRE REPAIR OR MAINTENANCE - NON SEDIMENT POND BMPS ARE TO BE REPAIRED WITHIN 3 DAYS OF INSPECTION AND SEDIMENT PONDS ARE TO BE REPAIRED OR CLEANED OUT WITHIN 10 DAYS OF INSPECTION.
- FOR BMPS THAT DO NOT MEET THE INTENDED FUNCTION, A NEW BMP SHALL BE INSTALLED WITHIN 10 DAYS OF THE INSPECTION.
- FOR MISSING BMPS REQUIRED, THE MISSING BMPS SHALL BE INSTALLED WITHIN 10 DAYS OF THE INSPECTION.

## SPILLS AND CONTAMINATION

- CONSTRUCTION PERSONNEL, INCLUDING SUBCONTRACTORS WHO MAY USE OR HANDLE HAZARDOUS OR TOXIC MATERIALS, SHALL BE MADE AWARE OF THE FOLLOWING GENERAL GUIDELINES REGARDING DISPOSAL AND HANDLING OF HAZARDOUS AND CONSTRUCTION WASTES:
  - PREVENT SPILLS
  - USE PRODUCTS UP
  - FOLLOW LABEL DIRECTIONS FOR DISPOSAL
  - REMOVE LIDS FROM EMPTY BOTTLES AND CANS WHEN DISPOSING IN TRASH
  - RECYCLE WASTES WHENEVER POSSIBLE
  - DONT POUR INTO WATERWAYS, STORM DRAINS OR ONTO THE GROUND
  - DONT POUR DOWN THE SINK, DOOR DRAIN OR SEPTIC TANKS
  - DONT BURY CHEMICALS OR CONTAINERS
  - DONT BURN CHEMICALS OR CONTAINERS
  - DONT MIX CHEMICALS TOGETHER
- ANY DISCHARGE OF PETROLEUM OR PETROLEUM PRODUCTS OF LESS THAN 25 GALLONS ONTO A PVIOUS SURFACE SHALL BE LEGALLY REMOVED AND PROPERLY TREATED OR PROPERLY DISPOSED OF, OR OTHERWISE REMEDIATED, SO THAT NO CONTAMINATION FROM THE DISCHARGE REMAINS ON-SITE. SPILLS OF 25 GALLONS OR MORE OF PETROLEUM PRODUCTS SHALL BE REPORTED TO THE OHIO EPA, THE LOCAL FIRE DEPARTMENT, AND THE LOCAL EMERGENCY PLANNING COMMITTEE WITHIN 30 MINUTES OF THE DISCOVERY OF THE RELEASE. ALL SPILLS WHICH CONTACT WATERS OF THE STATE MUST BE REPORTED TO THE CURRENT STATE'S EPA.
- SPILL REPORTING REQUIREMENTS: SPILLS ON PAVEMENT SHALL BE ABSORBED WITH SAWDUST OR KITTY LITTER AND DISPOSED OF WITH THE TRASH AT A LICENSED SANITARY LAND FILL. HAZARDOUS OR INDUSTRIAL WASTES SUCH AS MOST SOLVENTS, GASOLINE, OIL-BASED PAINTS, AND CEMENT CURING COMPOUNDS REQUIRE SPECIAL HANDLING. SPILLS SHALL BE REPORTED TO THE OHIO EPA.
- CONTAINERS SHALL BE PROVIDED FOR THE PROPER COLLECTION OF ALL WASTE MATERIAL INCLUDING CONSTRUCTION DEBRIS, TRASH, PETROLEUM PRODUCTS AND ANY HAZARDOUS MATERIALS USED ON-SITE. CONTAINERS SHALL BE COVERED AND NOT LEAKING. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THAT MATERIAL. CONSTRUCTION DEMOLITION AND DEBRIS (CD&D) WASTE MUST BE DISPOSED OF AT THE OHIO EPA APPROVED CD&D LAND FILL.
- PROCESS WASTE WATER/LEACHATE MANAGEMENT : EPA'S CONSTRUCTION GENERAL PERMIT ONLY ALLOWS THE DISCHARGE OF STORM WATER AND DOES NOT INCLUDE OTHER WASTE STREAMS/DISCHARGES SUCH AS VEHICLE AND/OR EQUIPMENT WASHING, ON-SITE SEPTIC LEACHATE CONCRETE WASH OUTS, WHICH ARE CONSIDERED PROCESS WASTEWATERS. ALL PROCESS WASTEWATERS MUST BE COLLECTED AND PROPERLY DISPOSED AT AN APPROVED DISPOSAL FACILITY. IN THE EVENT, LEACHATE OR SEPTAGE IS DISCHARGED, IT MUST BE ISOLATED FOR COLLECTION AND PROPER DISPOSAL AND CORRECTIVE ACTIONS TAKEN TO ELIMINATE THE SOURCE OF WASTE WATER.
- WASTES GENERATED BY CONSTRUCTION ACTIVITIES (I.E. CONSTRUCTION MATERIALS SUCH AS PAINTS, SOLVENTS, FUELS, CONCRETE, WOOD, ETC) MUST BE DISPOSED OF IN ACCORDANCE WITH LOCAL REGULATIONS. HAZARDOUS AND TOXIC SUBSTANCES ARE USED ON VIRTUALLY ALL CONSTRUCTION SITES. GOOD MANAGEMENT OF THESE SUBSTANCES IS ALWAYS NEEDED.
- NO CONSTRUCTION RELATED WASTE MATERIALS ARE TO BE BURIED OR BURNED ON-SITE.
- HANDLING CONSTRUCTION CHEMICALS: MIXING, PUMPING, TRANSFERRING OR OTHER HANDLING OF CONSTRUCTION CHEMICALS SUCH AS FERTILIZER, LIME, ASPHALT, CONCRETE DRYING COMPOUNDS, AND ALL OTHER POTENTIALLY HAZARDOUS MATERIALS SHALL BE PERFORMED IN AN AREA AWAY FROM ANY WATERCOURSE, DITCH OR STORM DRAIN.
- EQUIPMENT FUELING AND MAINTENANCE, OIL CHANGING, ETC., SHALL BE PERFORMED AWAY FROM WATERCOURSES, DITCHES OR STORM DRAINS. IN AN AREA DESIGNATED FOR THAT PURPOSE, THE DESIGNATED AREA SHALL BE EQUIPPED FOR RECYCLING OIL AND CATCHING SPILLS. SECONDARY CONTAINMENT SHALL BE PROVIDED FOR ALL FUEL OIL STORAGE TANKS, THESE AREAS MUST BE INSPECTED EVERY SEVEN DAYS AND WITHIN 24 HRS. OF A 0.5 INCH OR GREATER RAIN EVENT TO ENSURE THERE ARE NO EXPOSED MATERIALS WHICH WOULD CONTAMINATE STORM WATER. SITE OPERATORS MUST BE AWARE THAT SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) REQUIREMENTS MAY APPLY. AN SPCC PLAN IS REQUIRED FOR SITES WITH ONE SINGLE ABOVE GROUND TANK OF 660 GALLONS OR MORE, ACCUMULATIVE ABOVE GROUND STORAGE OF 1330 GALLONS OR MORE, OR 42,000 GALLONS OF UNDERGROUND STORAGE. CONTAMINATED SOILS MUST BE PROPERLY DISPOSED OF IN ACCORDANCE WITH LOCAL GOVERNING AUTHORITY REGULATIONS. SPCC PLAN AND APPROVALS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- CONTAMINATED SOILS: IF SUBSTANCES SUCH AS OIL, DIESEL FUEL, HYDRAULIC FLUID, ANTIFREEZE, ETC. ARE SPILLED, LEAKED, OR RELEASED ONTO THE SOIL, THE SOIL SHOULD BE DUG UP AND DISPOSED OF AT LICENSED SANITARY LAND FILL OR OTHER APPROVED PETROLEUM CONTAMINATED SOIL REMEDIATION FACILITY (NOT A CONSTRUCTION / DEMOLITION DEBRIS LAND FILL). NOTE THOSE STORM WATER RUNOFFS ASSOCIATED WITH CONTAMINATED SOILS ARE NOT BE AUTHORIZED UNDER CURRENT REGULATIONS OF CONSTRUCTION ACTIVITIES.
- CONTRACTOR SHALL TAKE PREVENTIVE MEASURES FOR WATER DISCHARGES FROM CONTAMINATED SOILS BY ANY MEANS POSSIBLE, INCLUDING THE FOLLOWING:
  - THE USE OF BERMS, TRENCHES, AND PITS TO COLLECT CONTAMINATED RUNOFF AND PREVENT DISCHARGES
  - PUMPING RUNOFF INTO A SANITARY SEWER (WITH PRIOR WRITTEN APPROVAL OF THE SANITARY SEWER SERVICE OPERATOR) OR INTO A CONTAINER FOR TRANSPORT TO AN APPROPRIATE TREATMENT/DISPOSAL FACILITY.
  - COVERING AREAS OF CONTAMINATION WITH TARPS OR OTHER METHODS THAT PREVENT STORMWATER FROM COMING INTO CONTACT WITH CONTAMINATED MATERIALS.

## TEMPORARY SEEDING

- STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SUCH AS DIVERSIONS AND SEDIMENT TRAPS SHALL BE INSTALLED AND STABILIZED WITH TEMPORARY SEEDING PRIOR TO GRADING THE REST OF THE CONSTRUCTION SITE.
- TEMPORARY SEEDING / STABILIZATION SHALL BE APPLIED WITHIN THE FOLLOWING TIME FRAMES FOR VARIOUS AREAS OF THE SITE:
  - ANY DISTURBED AREA WITHIN 50 FEET OF A WATERCOURSE AND NOT AT FINAL GRADE SHALL BE SEEDED AND MULCHED WITHIN 2 DAYS OF THE MOST RECENT DISTURBANCE, IF THAT AREA WILL REMAIN IDLE FOR MORE THAN 14 DAYS.
  - ALL CONSTRUCTION ACTIVITIES IN ANY DISTURBED AREA, INCLUDING SOIL STOCKPILES THAT WILL BE IDLE FOR MORE THAN 14 DAYS BUT LESS THAN ONE YEAR, AND NOT WITHIN 50 FEET OF A WATERCOURSE SHALL BE SEEDED AND MULCHED WITHIN 7 DAYS OF THE MOST RECENT DISTURBANCE IN THE AREA.
  - DISTURBED AREAS THAT WILL BE IDLE OVER THE WINTER SHALL BE SEEDED AND MULCHED PRIOR TO NOVEMBER 1.
- THE SEED BED SHOULD BE PULVERIZED AND LOOSE TO ENSURE THE SUCCESS OF ESTABLISHING VEGETATION. TEMPORARY SEEDING SHOULD NOT BE POSTPONED IF IDEAL SEED BED PREPARATION IS NOT POSSIBLE.
- TEMPORARY VEGETATION SEEDING RATES SHALL ESTABLISH ADEQUATE STANDS OF VEGETATION, WHICH MAY REQUIRE USE OF SOIL AMENDMENTS. BASE RATES FOR LIME AND FERTILIZER SHALL BE USED.
- ALL SEED MIXES AND SEEDING RATES USED SHALL BE APPROVED BY THE LOCAL GOVERNING AUTHORITY AND THE OWNER.
- SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SPREADER, DRILL, CULTIPACKER, SEEDER, OR HYDROSEEDER. WHEN FEASIBLE, SEED THAT HAS BEEN BROADCAST SHALL BE COVERED BY RAKING OR DRAGGING AND THEN LIGHTLY TAMPED INTO PLACE USING A ROLLER OR CULTIPACKER. IF HYDROSEEDING IS USED, THE SEED AND FERTILIZER WILL BE MIXED ON-SITE AND THE SEEDING SHALL BE DONE IMMEDIATELY AND WITHOUT INTERRUPTION.
- APPLICATIONS OF TEMPORARY SEEDING SHALL INCLUDE MULCH, WHICH SHALL BE APPLIED DURING OR IMMEDIATELY AFTER SEEDING. SEEDINGS MADE DURING OPTIMUM SEEDING DATES ON FAVORABLE, VERY FLAT SOIL CONDITIONS MAY NOT NEED MULCH TO ACHIEVE ADEQUATE STABILIZATION. IF MULCH IS USED, FOLLOW THE REQUIREMENTS AND INSTRUCTIONS IN THE MULCH APPLICATION.

## MULCH

- MULCH AND OTHER APPROPRIATE VEGETATIVE PRACTICES SHALL BE APPLIED TO DISTURBED AREAS WITHIN 7 DAYS OF GRADING IF THE AREA IS TO REMAIN DORMANT (UNDISTURBED) FOR MORE THAN 21 DAYS OR ON AREAS AND PORTIONS OF THE SITE WHICH CAN BE BROUGHT TO FINAL GRADE.
  - MULCH SHALL CONSIST OF ONE OF THE FOLLOWING:
    - STRAW SHALL BE UNROTTED SMALL GRAIN STRAW APPLIED AT THE RATE OF 2 TONS/AC. OR 90 LB./1,000 SQ. FT. (TWO TO THREE BALES) THE STRAW MULCH SHALL BE SPREAD UNIFORMLY BY HAND OR MECHANICALLY SO THE SOIL SURFACE IS COVERED. FOR UNIFORM DISTRIBUTION OF HAND-SPREAD MULCH, DIVIDE AREA INTO APPROXIMATELY 1,000 SQ. FT. SECTIONS AND PLACE TWO 45-LB BALES OF STRAW IN EACH SECTION.
    - WOOD CELLULOSE FIBER SHOULD BE USED AT 2,000 LB/AC. OR 48 LB/1,000 SQ. FT.
    - ACCEPTABLE MULCHES INCLUDE MULCH MATTINGS AND ROLLED EROSION CONTROL PRODUCTS APPLIED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS OR WOOD MULCH/CHIPS APPLIED AT 10-20 TONS/AC.
  - MULCH SHALL BE ANCHORED IMMEDIATELY TO MINIMIZE LOSS BY WIND OR RUNOFF. THE FOLLOWING ARE ACCEPTABLE METHODS FOR ANCHORING MULCH.
    - USE A DISK, CRIMPER, OR SIMILAR TYPE TOOL SET STRAIGHT TO PUNCH OR ANCHOR THE MULCH MATERIAL INTO THE SOIL. STRAW MECHANICALLY ANCHORED SHALL NOT BE FINELY CHOPPED BUT BE LEFT GENERALLY LONGER THAN 6 INCHES.
    - USE MULCH NETTINGS ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS, FOLLOWING ALL PLACEMENT AND ANCHORING REQUIREMENTS. USE IN AREAS OF WATER CONCENTRATION AND STEEP SLOPES TO HOLD MULCH IN PLACE.
    - FOR STRAW MULCH, SYNTHETIC BINDERS SUCH AS ACRYLIC DLR (AGRI-TAC), DCA-70, PETROSET, TERRA TACK OR EQUAL MAY BE USED AT RATES RECOMMENDED BY THE MANUFACTURER. ALL APPLICATIONS OF SYNTHETIC BINDERS MUST BE CONDUCTED IN SUCH A MANNER WHERE THERE IS NO CONTACT WITH WATERS OF THE STATE.
    - WOOD CELLULOSE FIBER MAY BE USED FOR ANCHORING STRAW. THE FIBER BINDER SHALL BE APPLIED AT A NET DRY WEIGHT OF 750 LB/AC. THE WOOD CELLULOSE FIBER SHALL BE MIXED WITH WATER AND THE MIXTURE SHALL CONTAIN A MAXIMUM OF 50 LB/100 GAL. OF WOOD CELLULOSE FIBER.

## DUST CONTROL NOTES

- DUST CONTROL SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION, IF POSSIBLE GRADING SHALL BE DONE BY PHASING IN ORDER TO MINIMIZE THE AMOUNT OF LAND DISTURBANCE AT ONE TIME. IF PHASING IS NOT AN OPTION, DUST SHALL BE CONTROLLED WITH WATER DURING EARTHWORK OPERATIONS. AFTER EARTHWORK OPERATIONS, THE EXPOSED SOILS SHALL BE COVERED WITH STRAW OR MULCH UNTIL SEEDED.
- DUST CONTROL OR DUST SUPPRESSANTS MAY BE USED TO PREVENT NUISANCE CONDITIONS WHEN APPROVED BY THE LOCAL AUTHORITY HAVING JURISDICTION. WHEN USED, SUPPRESSANTS SHALL BE APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND IN A MANNER, WHICH PREVENTS A DISCHARGE TO WATERS OF THE STATE. SUFFICIENT DISTANCE MUST BE PROVIDED BETWEEN APPLICATIONS AND NEARBY BRIDGES, CATCH BASINS, AND OTHER WATERWAYS. APPLICATION (EXCLUDING WATER) MAY NOT OCCUR WHEN RAIN IS IMMINENT AS NOTED IN THE SHORT TERM FORECAST. OIL MAY NOT BE APPLIED FOR DUST CONTROL.
  - SUGGESTED METHODS OF CONSTRUCTION DUST CONTROL MAY INCLUDE THE FOLLOWING:
    - CONSTRUCTION SEQUENCING AND DISTURBING ONLY SMALL AREAS AT A TIME CAN GREATLY REDUCE PROBLEMATIC DUST FROM THE SITE. IF LAND MUST BE DISTURBED, ADDITIONAL TEMPORARY STABILIZATION MEASURES SHOULD BE CONSIDERED PRIOR TO DISTURBANCES.
    - APPLY TEMPORARY OR PERMANENT SEEDING AND MULCH TO AREAS THAT WILL REMAIN IDLE FOR OVER 14 DAYS. SAVING EXISTING TREES AND LARGE SHRUBS WILL ALSO REDUCE SOIL AND AIR MOVEMENT ACROSS DISTURBED AREAS.
    - SPRAY DISTURBED SITE WITH WATER UNTIL THE SURFACE IS WET BEFORE AND DURING GRADING AND REPEAT AS NEEDED, ESPECIALLY ON HAUL ROADS AND OTHER HEAVY TRAFFIC ROUTES. WATERING SHALL BE DONE AT A RATE THAT PREVENTS DUST BUT DOES NOT CAUSE SOIL EROSION. WETTING AGENTS MAY BE UTILIZED ACCORDING TO MANUFACTURERS INSTRUCTIONS.
    - GRADED ROADWAYS AND OTHER SUITABLE AREAS MAY BE STABILIZED USING CRUSHED STONE OR COARSE GRAVEL AS SOON AS PRACTICABLE AFTER REACHING AN INTERIM OR FINAL GRADE. CRUSHED STONE OR COARSE GRAVEL CAN BE USED AS A PERMANENT COVER TO PROVIDE CONTROL OF SOIL EMISSIONS.
    - EXISTING WINDBREAK VEGETATION SHALL BE MARKED AND PRESERVED TO THE EXTENT POSSIBLE. SNOW FENCING OR OTHER SUITABLE BARRIER MAY BE PLACED PERPENDICULAR TO PREVAILING AIR CURRENTS AT INTERVALS OF ABOUT 15 TIMES THE BARRIER HEIGHTS TO CONTROL AIR CURRENTS AND BLOWING SOIL.
    - WHEN TEMPORARY DUST CONTROL MEASURES ARE USED; REPETITIVE TREATMENT SHOULD BE APPLIED AS NEED TO ACCOMPLISH SATISFACTORY CONTROL.
    - PAVED AREAS THAT HAVE ACCUMULATED SEDIMENT FROM CONSTRUCTION SHOULD BE CLEANED DAILY, OR AS NEEDED, UTILIZING A STREET SWEEPER OR BUCKET-TYPE ENDOLOADER OR SCRAPER.

## DEWATERING

DEWATERING REFERS TO THE ACT OF REMOVING AND DISCHARGING WATER FROM EXCAVATED AREAS ON CONSTRUCTION SITES; UTILITY LINE CONSTRUCTION OR FROM SEDIMENT TRAPS OR BASINS ON CONSTRUCTION SITES. GIVEN THE UNIQUE CONDITIONS AT ANY PARTICULAR CONSTRUCTION SITE, ANY OR ALL OF THE PRACTICES MAY APPLY. IN ALL CASES, EVERY EFFORT SHALL BE MADE TO ELIMINATE SEDIMENT POLLUTION ASSOCIATED WITH DEWATERING.

### PRACTICES FOR DEWATERING EXCAVATED AREAS

- PUMPING OF WATER TO AN EXISTING SEDIMENT BASIN OR TRAP IN WHICH THE ENTIRE VOLUME OF WATER FROM THE AREA TO BE DEWATERED CAN BE CONTAINED WITHOUT DISCHARGE TO RECEIVING WATERS.
- PUMPING OF WATER TO AN EXISTING SEDIMENT BASIN OR TRAP SUCH THAT THE ENTIRE VOLUME OF WATER FROM THE AREA TO BE DEWATERED CAN BE MANAGED WITHOUT EXCEEDING THE DESIGN OUTFLOW FROM THE SEDIMENT CONTROL STRUCTURE.
- USE OF A STRAW BALE/SILT FENCE PIT OR TRAP AS DESCRIBED HEREIN AND APPROVED BY THE LOCAL GOVERNING AUTHORITY.
- PUMPING WATER THROUGH A GEOTEXTILE BAG MADE SPECIFICALLY FOR THIS PURPOSE.
- A WELL-VEGETATIVE FILTER STRIP, CAPABLE OF WITHSTANDING THE VELOCITY OF DISCHARGED WATER WITHOUT ERODING, INCLUDING THE INSTALLATION OF ENERGY DISSIPATION (HAYBALES, RIPRAP OR SHEET OF PLYWOOD) AT THE PUMP DISCHARGE.
- USE A SUMP PIT TO REDUCE THE PUMPING OF MUD.

DEWATERING OF SEDIMENT TRAPS AND BASINS. IN ALL CASES, WATER REMOVED FROM TRAPS AND BASINS SHALL BE DISCHARGED SO THAT IT PASSES THROUGH A SEDIMENT CONTROL DEVICE APPROVED BY THE LOCAL GOVERNING AUTHORITY PRIOR TO ENTERING RECEIVING WATERS. PRACTICES FOR DEWATERING OF TRAPS AND BASINS MAY INCLUDE SOME OR ALL OF THE FOLLOWING AS MAY BE APPROVED AND APPLICABLE. IN ALL CASES, THE DEWATERING OPERATIONS UTILIZED MUST BE CONTINUOUSLY MONITORED BY THE CONTRACTOR.

### USE OF A STRAW BALE/SILT FENCE PIT OR TRAP

- AN EXCAVATED BASIN (APPLICABLE TO "STRAW BALE/SILT FENCE PIT") MAY BE LINED WITH FILTER FABRIC TO HELP REDUCE SCOUR AND TO PREVENT EROSION OF SOIL FROM WITHIN THE STRUCTURE. IT MAY ALSO BE HELPFUL TO DIRECT THE DISCHARGE ONTO A HAY OR STRAW BALE OR RIPRAP.
- MEASURES SHALL CONSIST OF STRAW BALES, SILT FENCE AND A STONE OUTLET CONSISTING OF A COMBINATION OF 4-8 INCH RIPRAP AND 1/4 TO 2 INCH AGGREGATE AND A WET STORAGE PIT ORIENTED AS SHOWN IN DRAWING.
- THE EXCAVATED AREA SHOULD BE A MINIMUM OF 3 FEET BELOW THE BASE OF THE PERIMETER MEASURES (STRAW BALES OR SILT FENCE).
- ONCE THE WATER LEVEL NEARS THE CREST OF THE STONE WEIR (EMERGENCY OVERFLOW), THE PUMP MUST BE STOPPED WHILE THE STRUCTURE DRAINS DOWN TO THE ELEVATION OF THE WET STORAGE.
- THE WET STORAGE PIT MAY BE DEWATERED ONLY AFTER A MINIMUM OF 6 HOURS OF SEDIMENT SETTLING TIME. THIS EFFLUENT SHOULD BE PUMPED ACROSS A WELL-VEGETATED AREA OR THROUGH A SILT FENCE PRIOR TO ENTERING A WATERCOURSE.
- ONCE THE DEVICE HAS BEEN REMOVED, GROUND CONTOURS SHALL BE RETURNED TO ORIGINAL CONDITION.

### PUMPING WATER THROUGH A GEOTEXTILE BAG MADE SPECIFICALLY FOR THIS PURPOSE.

- THE BAG SHALL BE INSTALLED ON A VERY SLIGHT SLOPE SO INCOMING WATER FLOWS DOWNHILL THROUGH THE BAG WITHOUT CREATING MORE EROSION.
- THE INLET OPENING OF THE DEWATERING DEVICE SHALL HAVE A FILL SPOUT LARGE ENOUGH TO ACCOMMODATE THE DISCHARGE HOSE AND SHALL USE TWO STAINLESS STEEL STRAPS TO SECURE THE HOSE AND PREVENT PUMPED WATER FROM ESCAPING WITHOUT BEING FILTERED.
- THE BAG SHOULD BE PLACED ON AN AGGREGATE OR HAY BALE BED TO MAXIMIZE WATER FLOW THROUGH THE ENTIRE SURFACE AREA OF THE BAG.
- THE FILTER BAG IS FULL WHEN IT NO LONGER CAN EFFICIENTLY FILTER SEDIMENT OR PASS WATER AT A REASONABLE RATE.
- FLOW RATES VARY DEPENDING ON THE SIZE OF THE DEWATERING DEVICE, AMOUNT OF SEDIMENT DISCHARGED INTO THE DEWATERING DEVICE, THE TYPE OF GROUND, ROCK, OR OTHER SUBSTANCE UNDER THE BAG AND THE DEGREE OF THE SLOPE ON WHICH THE BAG LIES. THE FILTER BAG SHOULD BE SIZED TO ACCOMMODATE THE ANTICIPATED FLOW RATES FROM THE TYPE OF PUMP USED. IN ALL CASES FOLLOW THE MANUFACTURERS RECOMMENDATIONS FOR PUMPING FLOW RATES.
- THE FILTER BAG CAN BE LEFT IN PLACE AFTER CUTTING THE TOP OFF AND SEEDING AND MULCHING THE ACCUMULATED SEDIMENT OR REMOVED AND DISPOSED OF OFFSITE IN AN APPROVED LANDFILL.

A WELL-VEGETATIVE FILTER STRIP, CAPABLE OF WITHSTANDING THE VELOCITY OF DISCHARGED WATER WITHOUT ERODING, INCLUDING THE INSTALLATION OF ENERGY DISSIPATION (HAYBALES, RIPRAP OR SHEET OF PLYWOOD) AT THE PUMP DISCHARGE. SUCH OTHER METHODS AS MAY BE APPROVED BY THE LOCAL GOVERNING AUTHORITY.

REGARDLESS OF THE TYPE OF TREATMENT, ALWAYS USE A FLOATING SUCTION HOSE TO PUMP THE CLEANER WATER FROM THE TOP OF THE POND, AS THE CLEANER WATER IS PUMPED, THE SUCTION HOSE WILL LOWER AND EVENTUALLY ENCOUNTER SEDIMENT-LADEN WATER. AT THIS POINT CEASE PUMPING OPERATIONS AND REMOVE THE REMAINDER OF THE TRAPPED SEDIMENT WITH MACHINERY. EVEN WHEN PUMPING FROM THE TOP OF THE WATER COLUMN, PROVISIONS MUST STILL BE MADE TO FILTER WATER AS REQUIRED IN THIS SECTION PRIOR TO DISCHARGING TO A STREAM. DURING THE DEWATERING, PERSONNEL SHOULD BE ASSIGNED TO MONITOR PUMPING OPERATIONS AT ALL TIMES TO ENSURE THAT SEDIMENT POLLUTION IS ABATED. PUMPING SEDIMENT-LADEN WATER INTO THE WATERS OF THE STATE WITHOUT FILTRATION IS PROHIBITED.

THE DEWATERINGS DEVICE MUST BE SIZED (AND OPERATED) TO ALLOW PUMPED WATER TO FLOW THROUGH THE FILTERING APPARATUS WITHOUT EXCEEDING THE CAPACITY OF THE STRUCTURE.



Copyright: Glaus, Pyle, Schomer, Burns & DeHaven, Inc. 2021

NOT FOR CONSTRUCTION

DATE	REMARKS

CONTRACT DATE:  
BUILDING TYPE: END 20  
PLAN VERSION: JUNE 2021  
BRAND DESIGNER:  
SITE NUMBER:  
STORE NUMBER:  
PA/PM: AB  
DRAWN BY.: KK  
JOB NO.: 2021188.12

## TACO BELL

West Plane Street  
Bethel, OH 45013




END 20

## SWPP NOTES


# C-010

PLOT DATE:



**NOT FOR CONSTRUCTION**



**C3 SILT BAG INLET PROTECTION**  
N.T.S.





**C4 CURB INLET PROTECTION**  
N.T.S.



**MAINTENANCE:**  
SILT FENCE SHOULD BE INSPECTED REGULARLY AND FREQUENTLY AS WELL AS AFTER EACH RAINFALL EVENT TO INSURE THAT THEY ARE INTACT AND THERE ARE NO GAPS AT THE FENCE-GROUND INTERFACE OR TEARS ALONG THE LENGTH OF THE FENCE. IF GAPS OR TEARS ARE FOUND, THEY SHOULD BE REPAIRED OR THE FABRIC REPLACED IMMEDIATELY. ACCUMULATED SEDIMENTS SHOULD BE REMOVED FROM THE FENCE BASE WHEN THE SEDIMENT REACHES ONE-THIRD TO ONE-HALF THE HEIGHT OF THE FENCE. SEDIMENT REMOVAL SHOULD OCCUR MORE FREQUENTLY IF ACCUMULATED SEDIMENT IS CREATING NOTICEABLE STRAIN ON THE FABRIC AND THERE IS THE POSSIBILITY OF THE FENCE FAILING FROM A SUDDEN STORM EVENT. WHEN THE SILT FENCE IS REMOVED, THE ACCUMULATED SEDIMENT SHOULD BE REMOVED.

**C5 SILT FENCE**  
N.T.S.

**NOTES:**  
1) SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS.  
2) ALL SILT FENCE SHALL BE PLACED AS CLOSE TO THE CONTOUR AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS WHICH MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH.  
3) TO PREVENT WATER PONDED BY THE SILT FENCE FROM FLOWING AROUND THE ENDS, EACH END SHALL BE CONSTRUCTED UPSLOPE SO THAT THE ENDS ARE AT A HIGHER ELEVATION.  
4) WHERE POSSIBLE, SILT FENCE SHALL BE PLACED ON THE FLATTEST AREA AVAILABLE.  
5) WHERE POSSIBLE, VEGETATION SHALL BE PRESERVED FOR 5 FT. (OR AS MUCH AS POSSIBLE) UPSLOPE FROM THE SILT FENCE. IF VEGETATION IS REMOVED, IT SHALL BE REESTABLISHED WITHIN 7 DAYS FROM THE INSTALLATION OF THE SILT FENCE.  
6) THE HEIGHT OF THE SILT FENCE SHALL BE A MINIMUM OF 16 IN. ABOVE THE ORIGINAL GROUND SURFACE.  
7) THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND SECURELY SEALED.  
8) POSTS SHALL BE A MINIMUM OF 5 FEET LONG, 2 INCHES IN DIAMETER AND SPACED A MAXIMUM OF 10 FEET APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND. WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE SUPPORT FENCE, POST SPACING SHALL NOT EXCEED 6 FEET.  
9) THE SILT FENCE SHALL BE PLACED IN A TRENCH CUT A MINIMUM OF 6 INCHES DEEP. THE TRENCH SHALL BE CUT WITH A TRENCHER, CABLE LAYING MACHINE, OR OTHER SUITABLE DEVICE WHICH WILL ENSURE AN ADEQUATELY UNIFORM TRENCH DEPTH.  
10) THE SILT FENCE SHALL BE PLACED WITH THE STAKES ON THE DOWNSLOPE SIDE OF THE GEOTEXTILE AND SO THAT 8 IN. OF CLOTH ARE BELOW THE GROUND SURFACE. EXCESS MATERIAL SHALL LAY ON THE BOTTOM OF THE 6 IN. DEEP TRENCH. THE TRENCH SHALL BE BACKFILLED AND COMPACTED.  
11) WHEN EXTRA STRENGTH FILTER FABRIC AND CLOSER POST SPACING ARE USED, THE WIRE MESH SUPPORT FENCE MAY BE ELIMINATED. IN SUCH A CASE, THE FILTER FABRIC IS STAPLED OR WIRED DIRECTLY TO THE POSTS.  
12) THE STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE FENCE, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE. FILTER FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.  
13) SEAMS BETWEEN SECTION OF SILT FENCE SHALL BE OVERLAPPED WITH THE END STAKES OF EACH SECTION WRAPPED TOGETHER BEFORE DRIVING INTO THE GROUND.  
14) SILT FENCE SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVERTOPS THE SILT FENCE, FLOWS UNDER OR AROUND THE ENDS, OR IN ANY OTHER WAY BECOMES A CONCENTRATED FLOW, ONE OF THE FOLLOWING SHALL BE PERFORMED, AS APPROPRIATE: A) THE LAYOUT OF THE SILT FENCE SHALL BE CHANGED, B) ACCUMULATED SEDIMENT SHALL BE REMOVED, OR C) OTHER PRACTICES SHALL BE INSTALLED.



**CONTRACT DATE:**  
**BUILDING TYPE:** END 20  
**PLAN VERSION:** JUNE 2021  
**BRAND DESIGNER:**  
**SITE NUMBER:**  
**STORE NUMBER:**  
**PA/PM:** AB  
**DRAWN BY.:** KK  
**JOB NO.:** 2021188.12

**TACO BELL**  
West Plane Street  
Bethel, OH 45013

**TACO BELL**

**END 20**


**SWPP DETAILS**

**C-011**

**PLANT DATE:**

**CONSTRUCTION ENTRANCE NOTES**

- STONE SIZE - NO. 2 STONE SHALL BE USED, OR RECYCLED CONCRETE EQUIVALENT.
- THE CONSTRUCTION ENTRANCE SHALL COINCIDE WITH THE PROPOSED DRIVE AS SHOWN ON THE PLAN.
- PAVEMENT THICKNESS - STONE LAYER SHALL BE 6" THICK FOR STANDARD DUTY ACTIVITY AND 10" THICK FOR HEAVY DUTY ACTIVITY.
- DRIVEWAY WIDTH - THE ENTRANCE SHALL BE AT LEAST 20' WIDE. CONTRACTOR SHALL ENSURE ALL VEHICLES UTILIZE THE CONSTRUCTION ENTRANCE UNTIL PAVEMENT IS IN PLACE.
- BEDDING-A GEOTEXTILE SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL BE COMPOSED OF STRONG ROT-PROOF POLYMERIC FIBERS AND MEET THE SPECIFICATIONS SHOWN BELOW.
- CULVERT-A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE OR TO PREVENT RUNOFF FROM BEING DIRECTED OUT ONTO PAVED SURFACES.
- WATER BAR - A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF NEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.
- MAINTENANCE - TOP DRESSING OF ADDITIONAL STONE SHALL BE APPLIED AS CONDITIONS DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING.
- CONSTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND PREVENT OFF SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION SHALL BE RESTRICTED FROM MUDDY AREAS.
- THE ENTRANCE SHALL REMAIN IN PLACE UNTIL THE DISTURBED AREA IS STABILIZED OR REPLACED WITH A PERMANENT ROADWAY OR ENTRANCE.



**A1**

**COMPOST SOCK FABRIC MINIMUM SPECIFICATIONS**

MATERIAL TYPE	3 mil HDPE	5 mil HDPE	5 mil HDPE	MULTI-FILAMENT POLYPROPYLENE (MFPF)	HEAVY DUTY MULTI-FILAMENT POLYPROPYLENE (MFPP)
MATERIAL CHARACTERISTICS	PHOTO-DEGRADABLE	PHOTO-DEGRADABLE	BIO-DEGRADABLE	PHOTO-DEGRADABLE	PHOTO-DEGRADABLE
SOCK DIAMETERS	12" 18"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"	12" 18" 24" 32"
MESH OPENING	3/8"	3/8"	3/8"	3/8"	1/8"
TENSILE STRENGTH		26 PSI	26 PSI	44 PSI	202 PSI
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	% AT 1000 HR.	23% AT 1000 HR.		100% AT 1000 HR.	100% AT 1000 HR.
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YEAR	2 YEARS


**TWO-PLY SYSTEMS**

INNER CONTAINMENT NETTING	HDPE BIAXIAL NET CONTINUOUSLY WOUND FUSION-WELDED JUNCTURES
OUTER FILTRATION MESH	3/4" X 3/4" MAX. APERTURE SIZE COMPOSITE POLYPROPYLENE FABRIC (WOVEN LAYER & NON-WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH) 3/16" MAX. APERTURE SIZE

**SOCK FABRICS COMPOSED OF BURLAP MAY BE USED ON PROJECTS LASTING 6 MONTHS OR LESS**


**COMPOST SHALL MEET THE FOLLOWING STANDARDS:**

ORGANIC MATTER CONTENT	80% - 100% (DRY WEIGHT BASIS)
ORGANIC PORTION	FIBROUS AND ELONGATED
pH	5.5 - 8.0
MOISTURE CONTENT	35% - 55%
PARTICLE SIZE	98% PASS THROUGH 1" SCREEN
SOLUBLE SALT CONCENTRATION	5.0 cS MAXIMUM



- COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK ALIGNMENT.
- TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.
- ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
- SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH 1/2 INCH STORM RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
- BIODEGRADABLE FILTER SOCK SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

**A2 COMPOST FILTER SOCK**  
N.T.S.




- NOTES:**
- CONTAINMENT MUST BE STRUCTURALLY SOUND AND LEAK FREE AND CONTAIN ALL LIQUID WASTES.
  - CONTAINMENT DEVICES MUST BE OF SUFFICIENT QUANTITY OR VOLUME TO COMPLETELY CONTAIN THE LIQUID WASTES GENERATED.
  - WASHOUT MUST BE CLEANED OR NEW FACILITIES CONSTRUCTED AND READY TO USE ONCE WASHOUT IS 75% FULL.
  - WASHOUT AREA(S) SHALL BE INSTALLED IN A LOCATION EASILY ACCESSIBLE BY CONCRETE TRUCKS.
  - ONE OR MORE AREAS MAY BE INSTALLED ON THE CONSTRUCTION SITE AND MAY BE RELOCATED AS CONSTRUCTION PROGRESSES.
  - AT LEAST WEEKLY REMOVE ACCUMULATION OF SAND AND AGGREGATE AND DISPOSE OF PROPERLY.

**A3 CONCRETE WASHOUT AREA**  
N.T.S.

- NOTES:**
- INLET PROTECTION SHALL BE CONSTRUCTED EITHER BEFORE UPSLOPE LAND DISTURBANCE BEGINS OR BEFORE THE STORM DRAIN BECOMES OPERATIONAL.
  - SILT FENCE SHALL BE GEOTEXTILE FABRIC, PER STATE'S DEPARTMENT OF TRANSPORTATION STANDARDS, AND SHOULD BE CUT FROM A CONTINUOUS ROLL TO AVOID JOINTS.
  - STAKES SHALL BE 1" X 2" WOOD (PREFERRED) OR EQUIVALENT METAL WITH A MINIMUM LENGTH OF 3 FEET. STAKES SHALL BE SPACED AROUND THE PERIMETER OF THE INLET A MAXIMUM OF 3 FEET APART AND SECURELY DRIVEN INTO THE GROUND (MINIMUM OF 8 INCHES). THE TOP OF THE FRAME SHALL BE AT LEAST 6 IN. BELOW ADJACENT ROADS IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC.
  - WIRE MESH SHALL BE OF SUFFICIENT STRENGTH TO SUPPORT FABRIC WITH WATER FULLY IMPOUNDED AGAINST IT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY TO THE FRAME.
  - THE SILT FENCE SHALL BE STAPLED WITH HEAVY DUTY WIRE STAPLES AT LEAST 1/2 INCH LONG, TO THE WOODEN STAKES, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE HEIGHT OF THE FILTER BARRIER SHALL BE A MINIMUM OF 15 INCHES AND SHALL NOT EXCEED 18 INCHES (PLATE 1.08B).
  - THE GEOTEXTILE SHALL OVERLAP ACROSS ONE SIDE OF THE INLET SO THE ENDS OF THE CLOTH ARE NOT FASTENED TO THE SAME POST.
  - A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 4 INCHES DEEP AROUND THE OUTSIDE PERIMETER OF THE STAKES.
  - BACKFILL SHALL BE PLACED AROUND THE INLET IN COMPACTED 6 IN. LAYERS UNTIL THE EARTH IS EVEN WITH NOTCH ELEVATION ON ENDS AND TOP ELEVATION ON SIDES.
  - A COMPACTED EARTH DIKE OR A CHECK DAM SHALL BE CONSTRUCTED IN THE DITCH LINE BELOW THE INLET IF THE INLET IS NOT IN A DEPRESSION AND IF RUNOFF BYPASSING THE INLET WILL NOT FLOW TO A SETTLING POND. THE TOP OF EARTH DIKES SHALL BE AT LEAST 6 IN. HIGHER THAN THE TOP OF THE FRAME.

**A4 SILT BARRIER**  
N.T.S.



**CONSTRUCTION SEQUENCE**

1. DURING PRECONSTRUCTION MEETING ALL EROSION & SEDIMENT CONTROL FACILITIES & PROCEDURES SHALL BE DISCUSSED. A GENERAL CONSTRUCTION SEQUENCE FOLLOWS AND MAY NEED TO BE UPDATED BY THE CONTRACTOR TO SUIT THE SPECIFICS OF THE SITE AND INTENDED CONTRACTOR SPECIFIC SEQUENCING.
- 1.1. INSTALL CONSTRUCTION ENTRANCE AS DETAILED ON PLANS. TEMPORARY CONSTRUCTION FENCING SHALL BE INSTALLED AROUND PERIMETER OF CONSTRUCTION SITE. WHERE THERE IS EXISTING FENCE ALONG THE PERIMETER OF THE SITE, IT CAN BE UTILIZED. FENCING SHALL BE USED TO RESTRICT OUTSIDE TRAFFIC TO SITE.
- 1.2. DELIVER CONSTRUCTION TRAILER TO SITE AND INSTALL TEMPORARY POWER AND TELEPHONE, IF REQUIRED. TEMPORARY UTILITY SERVICES ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- 1.3. STAKE AND/OR FLAG LIMITS OF CLEARING.
- 1.4. CLEAR & GRUB, AS NECESSARY, FOR INSTALLATION OF PERIMETER CONTROLS. INSTALL SILT PERIMETER CONTROLS AS SHOWN ON PLANS. SILT PERIMETER CONTROLS SHALL BE INSTALLED LEVEL, ALONG THE CONTOURS, WITH ENDS TURNED UPSLOPE TO PREVENT CONCENTRATED FLOW AT THE SILT PERIMETER CONTROLS.
- 1.5. INSTALL TEMPORARY SILT INLET PROTECTION ON ALL EXISTING CATCH BASINS AND INLETS, AS DESIGNATED IN THE PLANS. REMOVAL OF SILT INLET PROTECTION FROM DESIGNATED INLETS CAN ONLY OCCUR WHEN A STRUCTURE IS REMOVED, AND AS REQUIRED BY THE PROGRESSION OF THE DEMOLITION AND CONSTRUCTION.
- 1.6. CLEAR & GRUB THE REMAINING SITE AS NECESSARY. TOPSOIL SHALL BE STRIPPED AND STOCKPILED ON SITE FOR REUSE, OR REMOVED TO AN APPROVED OFFSITE SPOIL AREA. UTILIZE DUST CONTROL MEASURES AS REQUIRED TO MINIMIZE AIR-BORNE POLLUTION BY METHODS APPROVED BY THE AUTHORIZING EPA OFFICE.
- 1.7. BEGIN FILLING & GRADING AS REQUIRED TO REACH SUBGRADE.
- 1.8. INSTALL POST CONSTRUCTION STORMWATER MANAGEMENT FACILITIES INCLUDING DETENTION BASIN AND OUTLET CONTROL STRUCTURE.
- 1.9. ONCE PAVEMENT GRADES HAVE BEEN ESTABLISHED, AS DESIGNATED ON THE PLANS, THE CONTRACTOR SHALL UTILIZE THESE AREAS FOR STRUCTURE CONSTRUCTION.
- 1.10. CONSTRUCT UNDERGROUND UTILITY WORK INCLUDING STORM DRAINAGE FACILITIES. UPON INSTALLATION OF STORM DRAINAGE CATCH BASINS, YARD DRAINS AND INLETS, INSTALL REQUIRED INLET PROTECTION.
- 1.11. DO NOT REPLACE ANY TOPSOIL, SEED OR INSTALL FINAL PAVEMENT PRIOR TO COMPLETION OF BUILDING SHELL. SHOULD SITEWORK BE COMPLETED PRIOR TO THIS DATE, MULCH DISTURBED AREAS TO BE PLANTED AND INSTALL STONE SUBBASE IN DISTURBED AREAS TO BE PAVED.
- 1.12. FOLLOWING COMPLETION OF BUILDING SHELL AND PAVEMENT INSTALLATION, BEGIN LANDSCAPE INSTALLATION.
- 1.13. COMPLETE SITEWORK, PAVEMENT MARKINGS AND FINAL CLEAN-UP. RESEED ANY AREAS THAT MAY REQUIRE ATTENTION IMMEDIATELY. NOTE THAT LAWN AREAS WILL NOT BE DEEMED STABLE UNTIL A MINIMUM 80% VEGETATIVE DENSITY HAS BEEN ACHIEVED.
- 1.14. MAINTAIN EROSION & SEDIMENTATION CONTROL MEASURES UNTIL THE SITE HAS BEEN COMPLETELY STABILIZED. ALL AREAS OF VEGETATIVE SURFACE, WHETHER PERMANENT OR TEMPORARY, SHALL BE CONSIDERED TO BE IN PLACE AND FUNCTIONAL WHEN THE REQUIRED UNIFORM RATE OF COVERAGE (80%) IS OBTAINED.
- 1.15. REMOVE SEDIMENT CONTROLS.

**NOT FOR CONSTRUCTION**

**PROJECT DESCRIPTION**

THE EXISTING PROJECT SITE IS CURRENTLY A RESIDENTIAL HOME THAT WILL BE DEMOLISHED TO MAKE WAY FOR THE PROPOSED DEVELOPMENT. A TACO BELL RESTAURANT. THE SITE CURRENTLY DRAINS INTO AN EXISTING CREEK LOCATED ON THE NORTH END OF THE SITE THESE DRAINAGE PATTERNS WERE FOLLOWED IN THE POST-DEVELOPED CONDITIONS.

THE PROPOSED PROJECT SITE IS APPROXIMATELY 22.6% IMPERVIOUS SURFACE, PROPOSED CONSTRUCTION WILL CONSIST OF A NEW TACO BELL RESTAURANT, PARKING LOT AND DRIVES, SITE LIGHTING AND OTHER ASSOCIATED SITE AMENITIES.

**PROJECT COMPLETION STATISTICS**

PARCEL SIZE:	1.90 ACRES
TOTAL DISTURBED AREA:	1.06 ACRES
EXISTING LAND USE FOR THE SITE IS A RESIDENTIAL HOUSE	
ESTIMATED PRE-CONSTRUCTION IMPERVIOUS AREA:	0.07 ACRES
ESTIMATED PRE-CONSTRUCTION IMPERVIOUS PERCENT:	3.68%
PRE-CONSTRUCTION RUN-OFF COEFFICIENT:	0.37
PROPOSED LAND USE WILL BE A TACO BELL.	
ESTIMATED POST-CONSTRUCTION IMPERVIOUS AREA:	0.43 ACRES
ESTIMATED POST-CONSTRUCTION IMPERVIOUS PERCENT:	22.6%
POST-CONSTRUCTION RUN-OFF COEFFICIENT:	0.47

**PROJECT LOCATION:**

LATITUDE	38.9656°	LONGITUDE	-84.0923°
----------	----------	-----------	-----------

**EXISTING SITE SOIL TYPES:**

- HF2: HICKORY LOAM, 18 TO 35 PERCENT SLOPES.
  - JUR1B2: JONESBORO-ROSSMOYNE SILT LOAMS, 2 TO 6 PERCENT SLOPES.
  - WS1A1: WESTBORO-SCHAFFER SILT LOAMS, 0 TO 2 PERCENT SLOPES.
- REFERENCE: USDA NATIONAL RESOURCES CONSERVATION SERVICE WEB SOIL SURVEY.

**WETLAND INFORMATION:**

THERE APPEARS TO BE NO WETLANDS WITHIN THE PROJECT LIMITS.

**FIRST AND SUBSEQUENT RECEIVING STREAM:**

INITIAL RECEIVING WATER IS TOWN RUN AND THE SUBSEQUENT RECEIVING WATER IS POPLAR CREEK.

**OWNER CONTACT:**

AMPLER DEVELOPMENT, LLC.  
 2601 NORTHWEST EXPRESSWAY, SUITE 100W  
 OKLAHOMA CITY, OK 73112  
 DAN PEYTON  
 (512)-468-7088

**ANTICIPATED TIMING:**

CONSTRUCTION BEGIN:	TBD
CONSTRUCTION COMPLETE:	TBD
CONTRACTOR:	T.B.D.
CONTACT:	_____
PHONE NUMBER:	_____

CONTRACTOR SHALL MAINTAIN A CONSTRUCTION LOG DOCUMENTING ALL GRADING AND STABILIZATION ACTIVITIES.

DATE	REMARKS

CONTRACT DATE: \_\_\_\_\_  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER: \_\_\_\_\_  
 SITE NUMBER: \_\_\_\_\_  
 STORE NUMBER: \_\_\_\_\_  
 PA/PM: AB  
 DRAWN BY: KK  
 JOB NO.: 2021188.12

**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013




END 20

SWPP PLAN

**C-012**

PLOT DATE: \_\_\_\_\_



**LEGEND**  
 (SEE SHEET C-001 FOR GENERAL LEGEND)

- PROPOSED SILT BARRIER REFER TO SWPP DETAILS
- PROPOSED SILT FENCE REFER TO SWPP DETAILS
- PROPOSED CONSTRUCTION ENTRANCE REFER TO SWPP DETAILS
- LIMITS OF DISTURBANCE = 0.97 AC.

**SWPP KEYNOTES**

- LIMITS OF DISTURBANCE
- TEMPORARY SEEDING
- PERMANENT SEEDING
- CONCRETE WASHOUT AREA
- SILT FENCE
- CONSTRUCTION ENTRANCE
- INLET PROTECTION

**CONCRETE WASHOUT**  
 CONTRACTOR SHALL PLACE CONCRETE WASHOUT ON SITE AS NEEDED. CONCRETE WASHOUT FACILITIES SHALL BE LOCATED A MINIMUM OF 50' FROM STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES AND WATERCOURSES.

**BENCHMARKS:**  
 STATE PLANE GRID NORTH, NAD 83 (2011), GEOID 18, OHIO SOUTH ZONE. TIED BY GPS TO THE O.D.O.T. VRS.

ELEVATIONS ARE NAVD 88.

BENCHMARK #1 - X-CUT ON HYDRANT BONNET BOLT  
 N 355397, E 1516029  
 ELEVATION=878.94

BENCHMARK #2 - X-CUT ON HYDRANT BONNET BOLT  
 N 355629, E 1515405  
 ELEVATION=877.49



UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.

EASEMENT FOR HIGHWAY PURPOSE VOL. 10, PG. 31

36' WIDE PROPOSED ACCESS EASEMENT

CHANNEL EASEMENT VOL. 10 PG. 35


CINCINNATI AND SUBURBAN BELL TELEPHONE COMPANY MISC. VOL. 23, PG. 56

C21552RT Low Wire = 896.56

DOLLAR GENERAL SITE BY OTHERS

UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.

PAUL W. MAYES & VICTORIA L. PATTERSON  
 INSTR. No. 20170000518  
 P.N. 360327.076



**PLAN KEYNOTES** (#)

1. EXISTING PAVEMENT TO BE REMOVED. SEE LEGEND FOR TYPE.
2. EXISTING STAIRS TO BE REMOVED.
3. EXISTING BUILDING AND BELOW GRADE BASEMENT FOUNDATION AND SLAB TO BE REMOVED. CONTRACTOR SHALL REMOVE FOUNDATIONS AND SLABS AS FOUND IN THE FIELD AND BACKFILL AREAS AS RECOMMENDED AND OBSERVED BY THE ON SITE GEOTECHNICAL ENGINEER.
4. EXISTING POST TO BE REMOVED.
5. EXISTING LANDSCAPING (INCLUDING BUSHES, TREES, ROCKS, ETC.) TO BE REMOVED.
6. EXISTING MAILBOX TO BE REMOVED.
7. EXISTING UTILITIES TO BE REMOVED.
8. CONTRACTOR TO REMOVE EXISTING LANDSCAPING AS NEEDED FOR PROPOSED IMPROVEMENTS.
9. EXISTING CURB TO BE REMOVED.
10. EXISTING CONCRETE SIDEWALK TO BE REMOVED.
11. EXISTING CURB AND GUTTER TO BE REMOVED.
12. EXISTING WATER SERVICE TO BE REMOVED AND ABANDONED AT THE RIGHT-OF-WAY.
13. EXISTING GAS SERVICE TO BE REMOVED AND ABANDONED AT THE RIGHT-OF-WAY.

**NOT FOR CONSTRUCTION**

**DEMOLITION NOTE:**

ALL EXISTING SITE AND SURROUNDING FEATURES SUCH AS UTILITIES, PAVEMENT, CURB, LANDSCAPING, ETC. SHALL REMAIN AND BE PROTECTED THROUGHOUT CONSTRUCTION UNLESS NOTED OTHERWISE, OR ARE REQUIRED TO BE MODIFIED OR REMOVED FOR THE INSTALLATION OF PROPOSED IMPROVEMENTS. ALL DISTURBED FEATURES SHALL BE RESTORED OR RELOCATED AS REQUIRED TO THE SATISFACTION OF THE OWNER. CONTRACTOR SHALL REPAIR/REPLACE ANY SURROUNDING FEATURES DAMAGED AS A RESULT OF CONSTRUCTION ACTIVITIES AT NO ADDITIONAL COST AND TO THE SATISFACTION OF THE OWNER.

**LEGEND**

(SEE SHEET C-001 FOR GENERAL LEGEND)

- EXISTING ASPHALT TO BE REMOVED
- EXISTING GRAVEL TO BE REMOVED
- EXISTING CONCRETE TO BE REMOVED
- EXISTING BUILDING/STRUCTURE TO BE REMOVED
- DENOTES LIMITS OF SAWCUT
- DEMOLITION KEYNOTE
- LIMITS OF DISTURBANCE = 1.06 AC.

DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12

**TACO BELL**

West Plane Street  
 Bethel, OH 45013



END 20

**DEMOLITION PLAN**


**C-101**

PLOT DATE:

**BENCHMARKS:**  
 STATE PLANE GRID NORTH, NAD 83 (2011),  
 GEOID 18, OHIO SOUTH ZONE,  
 TIED BY GPS TO THE O.D.O.T. VRS.  
  
 ELEVATIONS ARE NAVD 88.  
  
 BENCHMARK #1 - X-CUT ON HYDRANT BONNET BOLT  
 N 355397, E 1516029  
 ELEVATION=878.94  
  
 BENCHMARK #2 - X-CUT ON HYDRANT BONNET BOLT  
 N 355629, E 1515405  
 ELEVATION=877.49



UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.



EASEMENT FOR HIGHWAY PURPOSES VOL. 10, PG. 34

WEST PLANE STREET



CHANNEL EASEMENT VOL. 10 PG. 35

DOLLAR GENERAL SITE BY OTHERS

CINCINNATI AND SUBURBAN BELL TELEPHONE COMPANY MISC. VOL. 25, PG. 56

ALFWAR O.R. P.

PAUL W. MAYES & VICTORIA L. PATTERSON  
 INSTR. No. 20170000518  
 P.N. 360327.076



ALFWARESS PROPERTIES, LLC  
 O.R. 2901, PG. 760  
 P.N. 360327.031

- PLAN KEYNOTES** (#)
- PROPOSED P.C.C. CURB, SEE SHEET C-501.
  - PROPOSED CURB AT DRIVE THRU, SEE SHEET C-501.
  - PROPOSED P.C.C. CURBED WALK, SEE SHEET C-501.
  - PROPOSED LIGHT POLE SEE ELECTRICAL PLANS FOR SPECIFICATIONS AND DETAILS.
  - PROPOSED 5" P.C.C. PAVEMENT W/ W.W.F. 6" x 6"-W2.9 (CONTROL JTS. 12-0" O.C.) OVER 5" CRUSHED AGGREGATE OR GRAVEL BASE. APPLY LIQUID ASPHALT AT ALL JOINTS BETWEEN CONCRETE AND ASPHALT.
  - PROPOSED DETERRENT BOLLARD IN CURB, SEE SHEET C-501.
  - PROPOSED DETERRENT BOLLARD, SEE SHEET C-501.
  - PROPOSED ADA PARKING SIGN IN BOLLARD, SEE SHEET C-501.
  - PROPOSED LANDSCAPING AREA. SOD ALL DISTURBED AREAS EXCEPT WHERE PLANTING BEDS ARE INDICATED. SEE SHEET L-101.
  - PROPOSED 'STOP' AND 'DO NOT ENTER' SIGN PER ODOT STANDARDS AND SHEET C-501.
  - PROPOSED 'DO NOT ENTER' SIGN PER ODOT STANDARDS AND SHEET C-501.
  - PROPOSED PAINTED TRANSVERSE STRIPING, SEE SHEET C-501.
  - PROPOSED PAINTED 4" WIDE SOLID STRIPE - WHITE ON ASPHALT, YELLOW ON CONCRETE.
  - PROPOSED DIRECTIONAL PAVEMENT MARKINGS - WHITE ON ASPHALT, YELLOW ON CONCRETE. BLUE FOR ADA - SEE SHEET C-501. CONTRACTOR TO OBTAIN STENCILS FROM PAVEMENT MARKINGS VENDOR FOR TEXT PAVEMENT MARKINGS.
  - PROPOSED PAINTED 18" WIDE WHITE SOLID STRIPE STOP BAR.
  - PROPOSED PAINTED INTERNATIONAL ADA SYMBOL PER ADA SPECIFICATIONS AND SHEET C-501.
  - PROPOSED ADA ACCESSIBLE RAMP PER ADA SPECIFICATIONS AND SHEET C-502.
  - PROPOSED FROST SLAB AT DOOR. SEE STRUCTURAL PLANS FOR DETAIL.
  - PROPOSED ELECTRICAL TRANSFORMER WITH PIT VAULT PER ELECTRICAL COMPANY SPECIFICATIONS. G.C. TO VERIFY EXACT LOCATION AND SIZE WITH UTILITY ENGINEER.
  - PROPOSED ELECTRIC METER PER ELECTRIC COMPANY SPECIFICATIONS. SEE ARCHITECTURAL DRAWINGS FOR EXACT LOCATION.
  - PROPOSED MENU BOARD, SPEAKER POST, AND CANOPY PER SIGN SUPPLIER SPECIFICATIONS AND SHEET C-502. SIGN SUPPLIER TO PROVIDE A TEMPLATE FOR G.C. G.C. TO COORDINATE A MEETING WITH THE CONSTRUCTION/PROJECT MANAGER AND OPERATIONS TO VERIFY LOCATION AND PLACEMENT OF MENU BOARD, SPEAKER POST, AND CANOPY PRIOR TO ANY CONSTRUCTION. SIGN SUPPLIER SHALL PROVIDE G.C. WITH FOUNDATION DETAILS. G.C. RESPONSIBLE FOR SIGN FOUNDATIONS/ELECTRICAL.
  - PROPOSED EVOLUTION PORTAL CLEARANCE BAR "ORDER HERE", SEE SHEET C-502.
  - PROPOSED WOODEN DUMPSTER ENCLOSURE ON 7" P.C.C. PAD OVER 5" CRUSHED AGGREGATE OR GRAVEL BASE, SEE ARCHITECTURAL PLANS. APPLY LIQUID ASPHALT AT ALL JOINTS BETWEEN CONCRETE AND ASPHALT.
  - PROPOSED MONUMENT SIGN PER SIGN SUPPLIER SPECIFICATIONS. SIGN SUPPLIER SHALL DESIGN AND INSTALL FOUNDATION.
  - PROPOSED 1,000 GALLON EXTERIOR GREASE INTERCEPTOR, SEE SHEET C-131 FOR INFORMATION.
  - PROPOSED SENSOR LOOP. SEE ELECTRICAL DRAWINGS FOR DETAILS.
  - PROPOSED "MOBILE PICK UP" PARKING SIGNS IN BOLLARD. CONTRACTOR TO INSTALL SIGN POST AND BOLLARD PER THE ADA PARKING SIGN DETAIL. SIGN TO BE BY SIGN VENDOR.
  - PROPOSED WATER STRUCTURE, SEE SHEET C-131.
  - PROPOSED SANITARY MANHOLE, SEE SHEET C-131.
  - PROPOSED STORM STRUCTURES, SEE SHEET C-131 FOR DESIGN INFORMATION.
  - PROPOSED 4" WIDE X 32' LONG ROCK CHANNEL PROTECTION, SEE SHEET C-503.
  - PROPOSED LANDSCAPE RESTORATION FROM REMOVAL OF THE EXISTING DRIVEWAY WITHIN RIGHT OF WAY.
  - PROPOSED CURB AND GUTTER PER THE VILLAGE OF BETHEL SPECIFICATIONS.
  - PROPOSED CURB TAPER FROM 6" TO 0" SEE SHEET C-502.
  - PROPOSED PORTABLE CONCRETE BARRIER PER ODOT STANDARD DRAWING PCB-1.
  - PROPOSED CONCRETE COLLAR ON CATCH BASIN SEE SHEET C-503.
  - PROPOSED CONCRETE WALK SEE SHEET C-502.
  - PROPOSED 3' CURB TAPER FROM 6" TO 0". SEE SHEET C-502.

**LEGEND**  
 (SEE SHEET C-001 FOR GENERAL LEGEND)

	PROPOSED STANDARD DUTY ASPHALT SEE SHEET C-501 FOR DETAIL.
	PROPOSED HEAVY DUTY ASPHALT SEE SHEET C-501 FOR DETAIL.
	PROPOSED ASPHALT PAVEMENT REPLACEMENT FOR SANITARY TRENCH PER VILLAGE OF BETHEL SPECIFICATIONS.
	PROPOSED CONCRETE
	CONSTRUCTION KEYNOTE
	PROPOSED PARKING SPACE NUMBER

**BUILDING SETBACKS**

	REQUIRED	PROVIDED
FRONT: W PLANE ST	25'	53.2'
REAR: NORTH	0'	308.5'
SIDE: WEST	0'	41.9'
SIDE: EAST	0'	82.0'

**PARKING SETBACKS**

	REQUIRED	PROVIDED
FRONT: W PLANE ST	0'	24.5'
REAR: NORTH	0'	244.1'
SIDE: WEST	0'	26.8'
SIDE: EAST	0'	8.0'

**LAND USE DATA**

	% OF SITE AREA	AREA PROVIDED
BUILDING	2.1%	0.04 AC.
PAVEMENT/IMPERVIOUS	20.0%	0.38 AC.
LANDSCAPING	77.9%	1.48 AC.
<b>TOTAL</b>	<b>100%</b>	<b>1.90 AC.</b>

CURRENT ZONING: B2 (GENERAL BUSINESS)

**BENCHMARKS:**  
 STATE PLANE GRID NORTH, NAD 83 (2011),  
 GEOID 18, OHIO SOUTH ZONE.  
 TIED BY GPS TO THE O.D.O.T. VRS.

ELEVATIONS ARE NAVD 88.

BENCHMARK #1 - X-CUT ON HYDRANT BONNET BOLT  
 N 355397, E 1516029  
 ELEVATION=878.94

BENCHMARK #2 - X-CUT ON HYDRANT BONNET BOLT  
 N 355629, E 1515405  
 ELEVATION=877.49



UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.



**NOT FOR CONSTRUCTION**

DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12

**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013





END 20

SITE PLAN


**C-111**

PLOT DATE:






- LEGEND**
- 000 — PROPOSED CONTOUR
  - XXX.XX± EXISTING SPOT ELEVATION MATCH EXISTING GRADE
  - XXX.XX PROPOSED ELEVATION @ FINISHED GROUND ELEVATION BOTTOM OF 6" CURB
  - T=XXX.XX  
B=XXX.XX TOP OF CURB ELEVATION  
BOTTOM OF CURB/FINISHED PAVEMENT ELEVATION
  - 0.0% PROPOSED DRAINAGE SLOPE & DIRECTION
  - ADA LIMITS OF ADA ROUTING
  - PROPOSED NORTH AMERICAN GREEN ROLLMAX VMAX SC250 PERMANENT TURF REINFORCEMENT MAT OR APPROVED EQUAL
  - FLOOD ROUTE



A1 ENLARGEMENT 1  
1" = 10'



A2 ENLARGEMENT 2  
1" = 10'

**NOT FOR CONSTRUCTION**

DATE	REMARKS

CONTRACT DATE:  
BUILDING TYPE: END 20  
PLAN VERSION: JUNE 2021  
BRAND DESIGNER:  
SITE NUMBER:  
STORE NUMBER:  
PA/PM: AB  
DRAWN BY.: KK  
JOB NO.: 2021188.12

**TACO BELL**  
West Plane Street  
Bethel, OH 45013



END 20

GRADING PLAN


C-121

PLOT DATE:

**BENCHMARKS:**  
STATE PLANE GRID NORTH, NAD 83 (2011),  
GEOD 18, OHIO SOUTH ZONE,  
TIED BY GPS TO THE O.D.O.T. VRS.  
  
ELEVATIONS ARE NAVD 88.  
  
BENCHMARK #1 - X-CUT ON HYDRANT BONNET BOLT  
N 355397, E 1516029  
ELEVATION=878.94  
  
BENCHMARK #2 - X-CUT ON HYDRANT BONNET BOLT  
N 355629, E 1515405  
ELEVATION=877.49



UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.



PLAN KEYNOTES (###)

- STORM**
- PROPOSED 11 LF OF 6" PVC DOWNSPOUT COLLECTOR LINE @ 1.00%
  - PROPOSED 29 LF OF 6" PVC DOWNSPOUT COLLECTOR LINE @ 3.82%
  - 8" INV. AT BUILDING = 873.50
  - PROPOSED 104 L.F. OF 6" PVC STORM SEWER @ 1.00%
  - PROPOSED 58 L.F. OF 12" RCP STORM SEWER @ 0.66%
  - PROPOSED 100 L.F. OF 12" RCP STORM SEWER @ 0.57%
  - PROPOSED 113 L.F. OF 12" RCP STORM SEWER @ 0.36%
  - PROPOSED 14 L.F. OF 12" RCP STORM SEWER @ 0.29%
  - PROPOSED 85 L.F. OF 12" HDPE STORM SEWER @ 1.18%
  - PROPOSED STORM CLEANOUT, SEE SHEET C-503, RIM = 875.47, 6" INV. = 873.39
  - PROPOSED WYE CONNECTION, SEE SHEET C-502, 6" INV. = 873.08
  - PROPOSED WYE CONNECTION, SEE SHEET C-502, 6" INV. = 872.80
  - PROPOSED STORM CLEANOUT, SEE SHEET C-503, RIM = 875.97, 6" INV. = 873.47
  - PROPOSED 4" WIDE X 37" LONG ROCK CHANNEL PROTECTION, SEE SHEET C-503.
- SANITARY**
- PROPOSED 85 L.F. OF 8" PVC SANITARY SEWER @ 0.44%
  - PROPOSED 97 L.F. OF 8" PVC SANITARY SEWER @ 0.44%
  - PROPOSED SANITARY CONNECTION, PROP. 8" INV.=869.68, PROP 6" INV. = 869.76.
  - PROPOSED 180 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 58 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 4 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 3 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 3 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 8 L.F. OF 6" PVC SANITARY SEWER @ 1.00%
  - PROPOSED 10 L.F. OF 6" PVC SANITARY SEWER @ 2.85%
  - PROPOSED 3 L.F. OF 6" PVC SANITARY SEWER @ 2.85%
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.49, 6" INV. = 871.56
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.95, 6" INV. = 872.14
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.95, 6" INV. = 872.18
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.88, 6" INV. = 872.41
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.98, 6" INV. = 872.40
  - PROPOSED 6" INV. AT BUILDING = 872.49
  - PROPOSED SANITARY WYE CONNECTION, SEE SHEET C-503, 6" INV.=872.12
  - PROPOSED 3" SANITARY VENT PIPE, SEE MECHANICAL PLANS.
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.95, 6" INV. = 872.21
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 875.95, 6" INV. = 872.20
  - PROPOSED SANITARY CLEANOUT SEE SHEET C-503, RIM = 876.75, 6" INV. = 870.63

- WATER**
- PROPOSED WATER CONNECTION, COORDINATE WITH PLUMBING PLANS.
  - PROPOSED WATER METER IN BELOW GRADE VAULT PER UTILITY COMPANY STANDARDS AND SPECIFICATIONS.
  - PROPOSED 120 L.F., 1.5" COPPER TYPE 'K' WATER SERVICE LINE.
  - PROPOSED WATER SERVICE TAP PER UTILITY COMPANY STANDARDS AND SPECIFICATIONS.
  - PROPOSED 75 L.F.± WATER SERVICE TO BE BORED UNDER EXISTING ROAD BY AND TAPPED INTO EXISTING WATER SERVICE BY UTILITY COMPANY. CONTRACTOR TO COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION TO TIE INTO.
- ELECTRIC AND COMMUNICATIONS**
- PROPOSED ELECTRIC METER PER ELECTRIC COMPANY SPECIFICATIONS. SEE BUILDING DRAWINGS FOR EXACT LOCATION. ELECTRIC SERVICE LINE TO BE COORDINATED WITH THE ELECTRIC COMPANY.
  - PROPOSED ELECTRIC AND TELECOMMUNICATIONS SERVICE CONNECTION TO BE COORDINATED WITH THE UTILITY COMPANIES.
  - PROPOSED LIGHT POLE, SEE STRUCTURAL PLANS FOR FOUNDATION DETAIL AND ELECTRICAL DRAWINGS FOR SPECIFICATIONS.
  - PROPOSED ELECTRICAL TRANSFORMER PER ELECTRICAL COMPANY SPECIFICATIONS. G.C. TO VERIFY EXACT LOCATION AND SIZE WITH UTILITY ENGINEER.
- GAS**
- PROPOSED GAS METER PER GAS COMPANY SPECIFICATIONS. SEE BUILDING DRAWINGS FOR EXACT LOCATION. GAS SERVICE LINE TO BE COORDINATED WITH THE GAS COMPANY.
  - PROPOSED 145 L.F.± GAS SERVICE CONNECTION TO BE COORDINATED WITH THE GAS COMPANY.
  - PROPOSED GAS VALVE TO BE INSTALLED PER GAS COMPANY. CONTRACTOR TO COORDINATE EXACT LOCATION WITH UTILITY COMPANY.
  - PROPOSED 85 L.F.± GAS SERVICE TO BE BORED UNDER EXISTING ROAD BY AND TAPPED INTO EXISTING GAS SERVICE BY UTILITY COMPANY. CONTRACTOR TO COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION TO TIE INTO.
- UTILITY CROSSINGS**
- GENERAL CROSSING NOTES: CONTRACTOR SHALL COORDINATE ALL CROSSINGS WITH THE UTILITY COMPANY. PRESSURIZED AND SECONDARY UTILITIES SHALL DEFLECT TO MAINTAIN 18" CLEAR AT SANITARY OR STORM SEWER CROSSINGS.
- SEE UTILITY CROSSING GENERAL NOTE.
  - PROPOSED UTILITY CROSSING: 12" STORM INV=872.29; 6" SANITARY INV=871.35 PIPE TO CONCRETE ENCASED SEE SHEET C-501 FOR DETAIL
  - PROPOSED UTILITY CROSSING: 6" STORM INV=873.38; 6" SANITARY INV=872.54 PIPE TO CONCRETE ENCASED SEE SHEET C-501 FOR DETAIL

**LEGEND**  
 (SEE SHEET C-001 FOR GENERAL LEGEND)


- ST - PROPOSED STORM SEWER
- SAN - PROPOSED SANITARY SEWER
- W - PROPOSED WATER SERVICE
- GAS - PROPOSED GAS SERVICE
- E&T - PROPOSED UNDERGROUND ELECTRIC AND TELEPHONE SERVICE
- D.S. - PROPOSED DOWNSPOUT
- XX## - APPURTENANCES
- # - UTILITY CONSTRUCTION KEYNOTE

**EXISTING STRUCTURES**

STRUCT. ID	STRUCTURE DETAILS
EX 1	EXISTING CURB INLET RIM = 873.87 15" HDPE (NE) = 870.85
EX 67	EXISTING STORM SEWER MANHOLE RIM = 877.27 18" RCP (E & W) = 869.67 12" RCP (S) = 869.67
EX 83	EXISTING STORM SEWER MANHOLE RIM = 876.60 18" VCP (NW) = 866.50 18" VCP (E) = 866.80
EX 300	EXISTING CATCH BASIN RIM = 873.96 18" VCP (NE & SE) = 865.16
EX 302	EXISTING STORM SEWER MANHOLE RIM = 875.38 18" RCP (N & SW) = 863.98
EX 60	EXISTING SANITARY SEWER MANHOLE TO BE MODIFIED RIM = 876.93 8" VCP (E) = 868.73 8" VCP (S) = 868.78 8" VCP (N) = 868.63 6" CMP (SW) = 872.28 PROP. 8" PVC (W) = 868.73

**PROPOSED STRUCTURES**

STRUCT. ID	STRUCTURE DETAILS
CB 1	PROPOSED ODOT 2-2A CATCH BASIN PER ODOT STD DWG CB-1.2 * FINGER DRAINS (N) RIM = 874.50 12" RCP INV. (W)=871.18 12" RCP INV. (E)=871.18 6" PVC INV. (S) = 872.35 SUMP DEPTH = 2.0'
CB 2	PROPOSED ODOT 2-2A CATCH BASIN PER ODOT STD DWG CB-1.2 * FINGER DRAINS (N) RIM = 874.40 12" RCP INV. (NW)=871.59 12" RCP INV. (SW)=871.59 SUMP DEPTH = 2.0'
CB 3	PROPOSED ODOT 2-2A CATCH BASIN PER ODOT STD DWG CB-1.2 * FINGER DRAINS (N,S) RIM = 874.87 12" RCP INV. (SW)=872.16 12" RCP INV. (NE)=872.16 SUMP DEPTH = 2.0'
CB 4	PROPOSED ODOT 2-2A CATCH BASIN PER ODOT STD DWG CB-1.2 * FINGER DRAINS (W,S) RIM = 874.61 12" RCP INV. (E)=872.61 SUMP DEPTH = 2.0'
CS 1	PROPOSED OUTLET CONTROL STRUCTURE ODOT CATCH BASIN 2-2B (SEE DETAIL ON SHEET C-504) RIM=873.75 INV. 1" ORIFICE = 871.00 INV. 12" (N) = 871.00
HW-1	PROP HEADWALL SEE SHEET C-503 12" RCP INV (W)=871.14
HW-2	PROP HEADWALL SEE SHEET C-503 12" HDPE INV (S)=870.00
GI 1	PROPOSED 1,000 GALLON EXTERIOR GREASE INTERCEPTOR SEE SHEET C-505 RIM=875.95 INV. 6" PVC (NW)=872.38 INV. 6" PVC (SE)=870.88
MH 1	PROPOSED SANITARY MANHOLE (SEE SHEET C-505) RIM= 877.70 INV. 8" PVC (W,E) = 869.10
MH 2	PROPOSED SANITARY MANHOLE (SEE SHEET C-505) RIM=877.90 INV. 8" PVC (W,E) = 869.70



**BENCHMARKS:**  
 STATE PLANE GRID NORTH, NAD 83 (2011), GEOID 18, OHIO SOUTH ZONE, TIED BY GPS TO THE O.D.O.T. VRS.  
 ELEVATIONS ARE NAVD 88.  
 BENCHMARK #1 - X-CUT ON HYDRANT BONNET BOLT  
 N 355397, E 1516029  
 ELEVATION=878.94  
 BENCHMARK #2 - X-CUT ON HYDRANT BONNET BOLT  
 N 355629, E 1515405  
 ELEVATION=877.49

UTILITIES SHOWN ON SURVEY WERE LOCATED BASED ON FIELD MARKING PROVIDED BY OUPS REQUEST #B129202186 AND #B129202188.



**NOT FOR CONSTRUCTION**

DATE	REMARKS


CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12

**TACO BELL**


West Plane Street  
 Bethel, OH 45013

END 20







**C1** PORTAL PLACEMENT DETAIL  
 N.T.S.




**C3** FOUNDATION CONDUIT DETAIL  
 N.T.S.




**C4** CURB TAPER  
 N.T.S.




**B2** ENLARGED MENU BOARD DETAIL @ STRAIGHT CURB  
 N.T.S.




**B4** FLUSH CURB  
 N.T.S.



**A2** ADA ACCESSIBLE RAMP  
 N.T.S.



**A1** BUTT JOINT  
 N.T.S.



**A4** CONCRETE WALK  
 N.T.S.

**NOT FOR CONSTRUCTION**

DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12


**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013



END 20


DETAILS

**C-502**  
 PLOT DATE:




- NOTES:  
 PROPOSED WATER SERVICE BELOW PROPOSED SEWER LINE WITH 18" MINIMUM SEPARATION. GRANULAR MATERIAL TO BE COMPACTED TO 75% OF RELATIVE DENSITY.
- GUIDELINES:
1. IF SELECT GRANULAR BACKFILL EXISTS, REMOVE WITHIN WIDTH OF PROPOSED SEWER TRENCH AND REPLACE WITH SELECT EXCAVATED MATERIAL AND COMPACT.
  2. OMIT SELECT GRANULAR CRADLE AND GRANULAR BACKFILL TO ONE (1) FOOT OVER TOP OF PIPE AND USE SELECT EXCAVATED MATERIAL AND COMPACT FOR 10 FEET ON EITHER SIDE OF WATER MAIN
  3. A. CONSTRUCT 10 FEET OF PROPOSED SEWER OF WATER MAIN MATERIAL AND PRESSURE TEST, OR, B. USE 10 FEET OF CASING FOR PROPOSED SEWER AND SEAL ENDS OF CASING.
  4. POINT LOADS SHALL NOT BE ALLOWED BETWEEN SEWER OR SEWER CASING AND WATER MAIN.
  5. PROVIDE ADEQUATE SUPPORT FOR EXISTING WATER MAIN TO PREVENT DAMAGE DUE TO SETTLEMENT OF SEWER TRENCH.

**C1 WATER & SEWER TRENCH SEPARATOR**  
N.T.S.




**B1 HEADWALL**  
N.T.S.

- KEYED NOTES
- 1 EXCAVATE WIDTH OF TRENCH AS NEEDED
  - 2 PLACE SUITABLE SOIL OR GRANULAR BACKFILL IN 6" MAX. LIFTS. SUITABLE SOIL SHALL BE COMPACTED TO 90% MIN. (98% MIN. UNDER PAVEMENT) DRY DENSITY, PER ASTM D698. GRANULAR BACKFILL SHALL BE COMPACTED TO 75% (80% UNDER PAVEMENT) RELATIVE DENSITY, PER ASTM 4353. GRANULAR BACKFILL REQUIRED UNDER PAVEMENT.
  - 3 PROPOSED STORM OR SANITARY SEWER
  - 4 TOPSOIL, SEED, AND MULCHING OR PAVEMENT AS DETAILED ELSEWHERE.
  - 5 NO. 57 OR NO. 67 AGGREGATE PLACED A MINIMUM OF 12" ABOVE THE TOP OF THE PIPE
  - 6 NO. 57 OR NO. 67 AGGREGATE PLACED A MINIMUM OF 6" BELOW THE BOTTOM OF THE PIPE




**B2 SEWER TRENCH**  
N.T.S.



- NOTES:
1. SUBGRADE FOR THE FILTER OR BEDDING AND RIPRAP SHALL BE PREPARED TO THE REQUIRED LINES AND GRADES AS SHOWN ON THE PLAN. THE SUBGRADE SHALL BE CLEARED OF ALL TREES, STUMPS, ROOTS, SOD, LOOSE ROCK, OR OTHER MATERIAL.
  2. RIPRAP SHALL CONFORM TO THE GRADING LIMITS AS SHOWN ON THE PLAN.
  3. GEOTEXTILE SHALL BE SECURELY ANCHORED ACCORDING TO MANUFACTURERS' RECOMMENDATIONS.
  4. GEOTEXTILE SHALL BE LAID WITH THE LONG DIMENSION PARALLEL TO THE DIRECTION OF FLOW AND SHALL BE LAID LOOSELY BUT WITHOUT WRINKLES AND CREASES. WHERE JOINTS ARE NECESSARY, STRIPS SHALL BE PLACED TO PROVIDE A 12-IN. MINIMUM OVERLAP, WITH THE UPSTREAM STRIP OVERLAPPING THE DOWNSTREAM STRIP.
  5. RIPRAP MAY BE PLACED BY EQUIPMENT BUT SHALL BE PLACED IN A MANNER TO PREVENT SLIPPAGE OR DAMAGE TO THE GEOTEXTILE.
  6. RIPRAP SHALL BE PLACED BY A METHOD THAT DOES NOT CAUSE SEGREGATION OF SIZES. EXTENSIVE PUSHING WITH A DOZER CAUSES SEGREGATION AND SHALL BE AVOIDED BY DELIVERING RIPRAP NEAR ITS FINAL LOCATION WITHIN THE CHANNEL.
  7. CONSTRUCTION SHALL BE SEQUENCED SO THAT OUTLET PROTECTION IS PLACED AND FUNCTIONAL WHEN THE STORM DRAIN, CULVERT, OR OPEN CHANNEL ABOVE IT BECOMES OPERATIONAL.
  8. ALL DISTURBED AREAS WILL BE VEGETATED AS SOON AS PRACTICAL.


**C3 ROCK CHANNEL PROTECTION**  
N.T.S.

- KEYED NOTES
- 1 6" DIA. CLEAN-OUT PIPE
  - 2 CAP AND SEAL CONDUIT
  - 3 THREADED CLEAN-OUT CAP
  - 4 45° BEND
  - 5 WYE
  - 6 SEWER




**B3 STORM CLEAN OUT (LAWN AREA)**  
N.T.S.


- KEYED NOTES
- 1 CONCRETE, MATCH PAVEMENT SPEC.
  - 2 6" (MIN.) AGGREGATE BASE
  - 3 6" DIA. CLEAN-OUT PIPE
  - 4 CAP AND SEAL CONDUIT
  - 5 THREADED CLEAN-OUT CAP
  - 6 CAST-IRON MONUMENT BOX, EJIW 1565 OR APPROVED EQUAL.
  - 7 45° BEND
  - 8 WYE
  - 9 SEWER




**A3 STORM CLEAN OUT (PAVEMENT AREA)**  
N.T.S.




**C3 CONCRETE COLLAR**  
N.T.S.



**B4 FINGER DRAIN DETAIL**  
N.T.S.



**A1 CONCRETE ENCASEMENT MONOLITHIC CRADLING OF UPPER PIPE FOR CROSSINGS WITH LESS THAN 18" MINIMUM CLEARANCE**  
N.T.S.



**A4 WYE CONNECTION**  
N.T.S.

**NOT FOR CONSTRUCTION**

DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12

**TACO BELL**

West Plane Street  
 Bethel, OH 45013




END 20

DETAILS

**C-503**


PLOT DATE:

**NOT FOR CONSTRUCTION**




- NOTES:
- SEE PLAN FOR LENGTH AND WIDTH.
  - GRADING PLAN CONTOURS DO NOT REFLECT 12" DEPRESSION AS SHOWN ON THIS DETAIL. CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING SUBSOIL ELEVATIONS IN ROCK CHANNEL PROTECTION AREAS AS REQUIRED TO MEET DETAIL SPECIFICATIONS.
  - CONTRACTOR SHALL SHAPE ROCK CHANNEL PROTECTION AT DETENTION OUTLET PER PLAN. ROCK SHALL BE INCLUDED ON SIDE SLOPES AS SHOWN.

**ROCK CHANNEL PROTECTION DETAIL**  
N.T.S.




**EMERGENCY SPILLWAY DETAIL**  
N.T.S.



**WATER QUALITY DRAINAGE ASSEMBLY DETAIL**  
N.T.S.

- KEYED NOTES**
- E.J.I.W. 6610 BEEHIVE DITCH GRATE INSET INTO STRUCTURE (OR APPROVED EQUAL)
  - BOTTOM SLAB MAY BE PRECAST SEPARATELY (6 INCH THICK MIN.) IF CAST-IN-PLACE, CONCRETE SHALL BE AT LEAST 8 INCH THICK.
  - 4 INCH PVC THREADED CAP SEALED WATER TIGHT WITH 1.0" ORIFICE DRILLED INTO BOTTOM OF CAP. 1.0 INCH ORIFICE INV. = 871.00
  - WATER QUALITY DRAINAGE ASSEMBLY, SEE DETAIL.
  - PERFORATED ASSEMBLY SHALL BE COMPLETELY COVERED WITH WASHED #57 CRUSHED LIMESTONE. (9" MIN. ALL SIDES)
  - WASHED 1'S & 2'S LIMESTONE ENVELOPE AROUND #57 STONE (15" MIN. ALL SIDES)
  - WATER TIGHT FLEXIBLE CONNECTOR (OR APPROVED EQUAL)
  - PVC PIPE SHALL EXTEND 6 INCH INSIDE OF STRUCTURE TO ALLOW FOR CAPPING.

- CONTROL STRUCTURE NOTES:**
- THE CONTROL STRUCTURE SHALL CONFORM TO OHIO DOT CATCH BASIN 2-2B, MODIFIED PER THIS DETAIL.
  - PRECAST WALLS SHALL BE REINFORCED SUFFICIENTLY TO PERMIT SHIPPING AND HANDLING WITHOUT DAMAGE.
  - CAST-IN-PLACE CONCRETE SHALL BE MIN. 4,000 PSI @ 28 DAY. ALL PRECAST CONCRETE SHALL MEET STATE REQUIREMENTS WITH 6% +/- 2% AIR VOID CONTENT IN THE CURED CONCRETE.
  - PRIOR TO THE START OF THIS PROJECT, THE CONTRACTOR SHALL SUBMIT CONTROL STRUCTURE SHOP DRAWING TO DESIGN ENGINEER FOR APPROVAL AND THEN CONTRACTOR SHALL SUBMIT APPROVED SHOP DRAWING TO COUNTY ENGINEER.



**A1 EXTENDED DRY DETENTION BASIN DETAIL**  
N.T.S.

DATE	REMARKS





CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: KK  
 JOB NO.: 2021188.12

**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013






END 20  
 DETAILS

**C-504**  
 PLOT DATE:



**NOT FOR CONSTRUCTION**



DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY: KK  
 JOB NO.: 2021188.12

**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013



END 20

DETAILS

**C-505**  
 PLOT DATE:

**LANDSCAPE NOTES & PLANTING SPECIFICATIONS**

**SCOPE OF WORK**

- THIS WORK SHALL CONSIST OF PERFORMING CLEARING AND GRUBBING, SOIL PREPARATION, FINISH GRADING, PLANTING AND DRAINAGE, INCLUDING ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, AND ANY OTHER APPURTENANCES NECESSARY FOR THE COMPLETION OF THIS PROJECT.
- QUANTITY TAKEOFF IS SUPPLIED FOR CONTRACTOR'S ASSISTANCE ONLY. CONTRACTOR IS RESPONSIBLE FOR SUPPLYING ALL PLANT MATERIALS AS PER PLAN.
- NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR WITHIN EASEMENT OR RIGHT-OF-WAY LIMITS.

**PRESERVATION/PROTECTION (IF APPLICABLE)**

- CONTRACTOR SHALL MAINTAIN AND PRESERVE TREES AND SHRUBS NOT BEING REMOVED, INCLUDING THEIR ROOTS. TREE PROTECTION FENCING SHALL BE USED AT THE DRIP LINE OF ALL TREES AND SHRUBS WITHIN 50 FEET OF CONSTRUCTION EXCEPT AS SHOWN ON PLAN. FENCING SHALL REMAIN IN PLACE UNTIL FINAL PLANT INSPECTION FOLLOWING CONSTRUCTION. MATERIALS SHALL NOT BE STOCKPILED WITHIN THIS DEFINED AREA AND VEHICLES AND OTHER EQUIPMENT SHALL BE OPERATED TO AVOID SOIL COMPACTION.
- FEEDER ROOTS SHOULD NOT BE CUT IN AN AREA EQUAL TO TWICE THE TREE CIRCUMFERENCE (MEASURED 6" ABOVE THE GROUND LINE IN INCHES) EXPRESSED IN FEET. (EXAMPLE: A CIRCUMFERENCE OF 10" WOULD HAVE A 'NO CUT' ZONE OF 20 FEET IN ALL DIRECTIONS FROM THE TREE). THIS SHOULD APPLY TO UTILITY SERVICES, IF FEASIBLE. THE ONLY EXCEPTION TO THIS REQUIREMENT WILL BE THOSE SPECIFICALLY ALLOWED BY THE LANDSCAPE ARCHITECT, SPECIFICATIONS OR AS INDICATION ON THE PLANS.
- TREE TRUNKS AND EXPOSED ROOTS DAMAGED DURING EQUIPMENT OPERATIONS SHALL BE TREATED IN ACCORDANCE WITH THE ARBOR CULTURAL STANDARDS OF THE CITY.

**PLANT MATERIALS**

- GENERAL - ALL MATERIALS SHALL BE OF ITS KIND AVAILABLE AND SHALL HAVE BEEN GROWN IN A CLIMATE SIMILAR TO THAT ON SITE.
- PLANTS - ALL PLANTS SHALL BE HEALTHY, OF NORMAL GROWTH, WELL ROOTED, FREE FROM DISEASE AND INSECTS. QUALITY AND SIZE OF PLANT MATERIAL SHALL CONFORM TO ANSI Z60.1 "AMERICAN STANDARDS FOR NURSERY STOCK".
- VARIETIES AND SIZES OF PLANTS SHALL BE AS SHOWN ON DRAWINGS.
- PLANTS SHALL BE IN A HEALTHY, VIGOROUS CONDITION, FREE OF DEAD OR BROKEN BRANCHES, SCARS THAT ARE NOT COMPLETELY HEALED, FROST CRACKS, DISFIGURING KNOTS, BROKEN OR ABRADED BARK, REDUNDANT LEADERS OR BRANCHES, OR ABERRATIONS OF ANY KIND. PLANTS SHALL NOT HAVE MULTIPLE LEADERS, UNLESS THIS IS THE NATURAL FORM.
- BALLED AND BURLAPPED (B&B) PLANTS SHALL BE DUG WITH A FIRM ROOT BALL OF NATURAL EARTH, OF A SIZE IN PROPORTION TO THE PLANT'S SIZE, AS MEASURED BY CALIPER, HEIGHT, OR SPREAD. BALLED AND BURLAPPED PLANTS SHALL BE HANDLED ONLY BY THE ROOT BALL, NOT BY THE TRUNK OR BRANCHES, AS THIS MAY BREAK OR LOOSEN THE ROOT BALL AND DAMAGE THE ROOT SYSTEM. CONTAINER PLANTS SHALL HAVE BEEN ESTABLISHED FOR A MINIMUM OF ONE FULL GROWING SEASON IN THEIR CONTAINERS BEFORE INSTALLATION. CONTAINER PLANTS SHALL BE HANDLED ONLY BY THE CONTAINER, NOT BY THE STEMS OR BRANCHES, AS THIS MAY PULL THE PLANT OUT OF THE CONTAINER AND BREAK OR LOOSEN THE ROOT BALL AND DAMAGE THE ROOT SYSTEM.
- PLANTS SHALL BE PROTECTED FROM DRYING OUT DURING SHIPPING WITH TARPULLINS OR OTHER COVERINGS. PLANTS SHALL BE PROTECTED FROM DRYING OUT AFTER DELIVERY BY PLANTING IMMEDIATELY; IF THIS IS NOT POSSIBLE, THE ROOT BALL SHALL BE COVERED WITH PEAT MOSS OR EARTH, AND WATERED FREQUENTLY TO KEEP IT MOIST UNTIL PLANTING.
- DO NOT HANDLE, MOVE, BIND, TIE OR OTHERWISE TREAT PLANTS SO AS TO DAMAGE THE ROOT BALL, ROOTS, TRUNK, OR BRANCHES IN ANY WAY.

**TOPSOIL**

- TOPSOIL HAS BEEN (OR WILL BE) STOCKPILED FOR REUSE IN LANDSCAPE WORK, IF QUANTITY OF STOCKPILED TOPSOIL IS INSUFFICIENT, PROVIDE ADDITIONAL TOPSOIL AS REQUIRED TO COMPLETE LANDSCAPE WORK. IMPORTED TOPSOIL SHALL CONSIST OF LOOSE, FRIABLE, LOAMY TOPSOIL WITHOUT ADMIXTURE OF SUBSOIL OR REFUSE. ACCEPTABLE TOPSOIL SHALL CONTAIN NOT LESS THAN 3 PERCENT NOR MORE THAN 20 PERCENT ORGANIC MATTER.
- PLANTING BACKFILL FOR PARKING LOT ISLANDS SHALL CONSIST OF A HOMOGENEOUS MIXTURE OF 3 PARTS TOPSOIL TO ONE PART SPHAGNUM PEAT INSTALLED OVER A 6" THICKNESS OF NO. 57 AGGREGATE.

**SOIL CONDITIONING**

- OBTAIN LABORATORY ANALYSIS OF STOCKPILED AND IMPORTED TOPSOIL COMPLETE WITH RECOMMENDATIONS FOR SOIL AMENDMENT.
- BEFORE MIXING, CLEAN TOPSOIL OF ROOTS, PLANTS, SOD, STONES, CLAY LUMPS, AND OTHER EXTRANEIOUS MATERIALS HARMFUL OR TOXIC TO PLANT GROWTH.
- MIX SPECIFIED SOIL AMENDMENTS AND FERTILIZERS WITH TOPSOIL AT RATES SPECIFIED BY THE LAB REPORT. DELAY MIXING OF FERTILIZER IF PLANTING WILL NOT FOLLOW PLACING OF PLANTING SOIL WITHIN A FEW DAYS.
- FOR PLANTING BEDS AND LAWNS, MIX PLANTING SOIL EITHER PRIOR TO PLANTING OR APPLY ON SURFACE OF TOPSOIL AND MIX THOROUGHLY BEFORE PLANTING. MIX LIME WITH DRY SOIL PRIOR TO MIXING OF FERTILIZER.
- PREVENT LIME FROM CONTACTING ROOTS OF ACID-LOVING PLANTS.
- APPLY PHOSPHORIC ACID FERTILIZER (OTHER THAN THAT CONSTITUTING A PORTION OF COMPLETE FERTILIZERS) DIRECTLY TO SUBGRADE BEFORE APPLYING PLANTING SOIL AND TILLING.

**PLANTING SOIL**

- PLANTING SOIL MIX SHALL BE CLEAR OF ALL STONES AND DEBRIS 1" OR LARGER, AND CONSIST OF THE FOLLOWING: 25% ORGANIC COMPOST, 75% ACCEPTABLE TOPSOIL.

**OTHER MATERIALS**

- BED EDGING - EDGING SHALL BE 4" STEEL EDGING WITH THREE (3) METAL ANCHOR STAKES PER 20 FOOT SECTION. ALL MASS PLANTING BEDS SHALL HAVE EDGING PLACED BETWEEN MULCH AREA AND ANY ADJACENT TURF AREA.
- MULCH: ORGANIC MULCH FREE FROM DELETERIOUS MATERIALS AND SUITABLE FOR TOP DRESSING OF TREES, SHRUBS, OR PLANTS AND CONSISTING OF THE FOLLOWING:
  - RIVER ROCK MULCH AREA: AGGREGATE MULCH, 3/4"-2" IN SIZE, WASHED AND ROUNDED, SHALL BE INSTALLED WITHIN THE RIVER ROCK MULCH AREA PER THE PLAN. RIVER ROCK MULCH SHALL BE INSTALLED AT 3" INCHES DEPTH.
  - NON-DRYED, DOUBLE SHREDDED HARDWOOD SHALL BE INSTALLED IN ALL OTHER LANDSCAPE BEDS OUTSIDE OF THE RIVER ROCK MULCH AREA AT A DEPTH OF 3 INCHES.

**GENERAL WORK PROCEDURES**

- LANDSCAPE WORK SHALL BE ACCORDING TO THE WORKMANLIKE STANDARDS ESTABLISHED FOR LANDSCAPE CONSTRUCTION AND PLANTING IN THE OHIO STANDARDIZED LANDSCAPE SPECIFICATIONS (ASLA) AND ANY LOCAL LANDSCAPE ORDINANCES.
- CONTRACTOR SHALL OBTAIN A COPY OF LOCAL ORDINANCES REGARDING ACCEPTABLE PLANT AND PLANTING DETAILS AND ABIDE BY THOSE ORDINANCES AND DETAILS.
- ENGINEER RESERVES THE RIGHT TO REJECT ALL PLANT MATERIAL DEEMED NOT ACCEPTABLE.
- ANY PROPOSED PLANT SUBSTITUTIONS SHALL BE EQUIVALENT IN FORM, HABIT, STRUCTURE, BRANCHING AND LEAF TYPE AND MUST BE ISSUED TO THE LANDSCAPE ARCHITECT FOR APPROVAL, IN WRITING, PRIOR TO INSTALLATION.

**WEEDING**

- BEFORE AND DURING PRELIMINARY GRADING AND FINISH GRADING, ALL WEEDS AND GRASSES SHALL BE DUG OUT BY THE ROOTS AND DISPOSED OF AT THE CONTRACTOR'S EXPENSE.

**PLANTING**

- POSITION TREES AND SHRUBS AT THEIR INTENDED LOCATIONS AS PER THE PLANS AND SECURE THE APPROVAL OF THE OWNER BEFORE EXCAVATING PITS, MAKING NECESSARY ADJUSTMENTS AS DIRECTED.
- PLANTING PITS SHALL BE AS PER DETAILS.
- PREPARED SOIL SHALL BE TAMPED FIRMLY AT BOTTOM OF PIT, FILL WITH PLANTING SOIL AROUND BALL OF PLANT. COMPLETE BACKFILLING AND WATER THOROUGHLY.
- EACH TREE AND SHRUB SHALL RECEIVE THE LANDSCAPER'S BIONUTRITION (3-0-3) GRANULAR WITH MYCORRHIZAL TECHNOLOGY FERTILIZER OR APPROVED OTHER, APPLY FERTILIZER PER MANUFACTURER'S SPECIFICATIONS.
- WATER IMMEDIATELY AFTER PLANTING. WATER SHALL BE APPLIED TO EACH TREE AND SHRUB IN SUCH MANNER AS NOT TO DISTURB BACKFILL AND TO THE EXTENT THAT ALL MATERIALS IN THE PLANTING HOLE ARE THOROUGHLY SATURATED.
- INSTALL BED EDGING AND MULCH PER MATERIALS SPECIFICATION AND DETAILS.
- REMOVE ALL SALES TAGS, STRINGS, STRAPS, WIRE, ROPE OR OTHER MATERIALS THAT MAY INHIBIT PLANT GROWTH BOTH ABOVE AND BELOW THE SURFACE OF THE SOIL.
- REMOVE ANY BROKEN, SUCKERING, DISEASED, CRISSCROSSED OR AESTHETICALLY DISPLEASING BRANCHES BACK TO LIVE LEADER OR SIDE LATERAL WITH A FLUSH CUT.

**FINISH GRADING**

- ALL AREAS WILL BE GRADED BY THE CONTRACTOR TO SUBSTANTIALLY PLUS/MINUS 0.1 FOOT OF FINISH GRADE.
- ALL LAWN AND PLANTING AREAS SHALL BE GRADED TO A SMOOTH, EVEN, UNIFORM PLANE WITH NO ABRUPT CHANGE OF SURFACE. SOIL AREAS ADJACENT TO THE BUILDINGS SHALL SLOPE AWAY FROM THE BUILDINGS.
- ALL PLANTING AREAS SHALL BE GRADED AND MAINTAINED TO ALLOW FREE FLOW OF SURFACE WATER.
- PARKING LOT ISLAND SHALL BE BACKFILLED AS PART OF THIS CONTRACT.

**GROUND COVER**

- SPACING AND VARIETY OF GROUND COVER SHALL BE AS SHOWN ON DRAWINGS.
- MULCH GROUND COVER WITH 2" THICKNESS OF SPHAGNUM PEAT.
- IMMEDIATELY AFTER PLANTING GROUND COVER, CONTRACTOR SHALL THOROUGHLY WATER GROUND COVER.
- ALL GROUND COVER AREAS SHALL BE TREATED WITH A PRE-EMERGENT BEFORE FINAL LANDSCAPE INSPECTION. GROUND COVER AREAS SHALL BE WEDED PRIOR TO APPLYING PRE-EMERGENT. PRE-EMERGENT TO BE APPLIED AS PER MANUFACTURER'S RECOMMENDATION.

**GUARANTEE**

- CONTRACTOR SHALL GUARANTEE ALL PLANTS FOR A PERIOD OF ONE (1) YEAR FROM DATE OF PROJECT ACCEPTANCE BY THE OWNER.

**CLEANUP**

- UPON THE COMPLETION OF ALL PLANTING WORK AND BEFORE FINAL ACCEPTANCE, THE CONTRACTOR SHALL REMOVE ALL MATERIAL, EQUIPMENT, AND DEBRIS RESULTING FROM HIS WORK. AN 'ACCEPTABLE CONDITION' SHALL BE AS DEFINED AND APPROVED BY THE OWNER'S AUTHORIZED REPRESENTATIVE.

**IRRIGATION**

- CONTRACTOR SHALL PROVIDE & INSTALL AN IRRIGATION SYSTEM TO PROVIDE 100% COVERAGE OF THE SITE.
- IRRIGATED AREAS WITHIN 5 FEET OF BUILDING WALLS SHALL BE IRRIGATED BY DRIP IRRIGATION OR SIMILAR. CONTRACTOR SHALL ENSURE BUILDING WALLS AND WINDOWS WILL NOT BE DAMAGED OR STAINED BY IMPROPER IRRIGATION INSTALLATION OR POOR SELECTION OF FIXTURES.
- SYSTEM SHALL INCLUDE ALL SPRINKLER FIXTURES, DRIP TUBING, PIPING, VALVES, WIRING AND CONTROLS TO PROVIDE A COMPLETE FUNCTIONAL SYSTEM THAT SHALL COMPLY WITH CITY CODE.
- IRRIGATION CONTRACTOR SHALL PROVIDE A METHOD FOR WINTERIZATION. WINTERIZATION SHALL BE PERFORMED BY CONTRACTOR UPON COMPLETION IF SYSTEM IS INSTALLED BETWEEN NOVEMBER 1 AND MARCH 31.
- PRIOR TO UPDATING THE IRRIGATION SYSTEM, A CERTIFIED IRRIGATION DESIGNER SHALL PROVIDE SHOP DRAWINGS TO ENGINEER FOR APPROVAL.
- UPON APPROVAL OF SHOP DRAWINGS, THE UPDATED IRRIGATION SYSTEM SHALL BE APPROVED BY OWNER FOR FINAL ACCEPTANCE.

**MAINTENANCE**

(MAINTENANCE PERIOD TO COMMENCE AFTER FINAL INSPECTION.)

- MAINTENANCE PERIOD FOR THIS CONTRACT SHALL BE 90 CALENDAR DAYS COMMENCING AFTER FINAL INSPECTION OF CONSTRUCTION.
- MAINTAIN TREES, SHRUBS AND OTHER PLANTS BY PRUNING, CULTIVATING AND WEEDING AS REQUIRED FOR HEALTHY GROWTH. RESTORE PLANTING SAUCERS, RESET TREES AND SHRUBS TO PROPER GRADES OR VERTICAL POSITION AS REQUIRED.
- MAINTAIN LAWNS BY WATERING, MOWING, TRIMMING, AND OTHER OPERATIONS SUCH AS ROLLING, REGRADING AND REPLANTING AS REQUIRED TO ESTABLISH A SMOOTH, ACCEPTABLE LAWN, FREE OF ERODED OR BARE AREAS.
- MAINTAIN THE LANDSCAPING BY KEEPING ALL PLANTS DISEASE-FREE AND PLANTING BEDS GROOMED, EXCEPT IN NATURALLY OCCURRING VEGETATION AREAS.
- REPLACE ANY REQUIRED PLANTING(S), WHICH SEVERELY DECLINE OR DIE AFTER THE DATE OF PLANTING. SUCH REPLACEMENT SHALL OCCUR DURING THE NEXT APPROPRIATE PLANTING SEASON.

**SODDING**

- SOD SHALL BE FIRST GRADE CERTIFIED BLENDS OF THE FOLLOWING SPECIES PER HARDINESS ZONE CONTAINING NOT MORE THAN 30 PERCENT OF OTHER GRASSES AND CLOVERS, AND FREE FROM ALL NOXIOUS WEEDS.
  - ZONES 3, 4 & 5: APPROVED BLUE GRASS BLEND
  - ZONE 6: APPROVED FESCUE BLEND
  - ZONES 7 & 8: APPROVED BERMUDA BLEND
  - ZONES 9 & 10: APPROVED ST AUGUSTINE FLORATAM BLEND
- SOD SHALL BE RECENTLY MOWED TO A HEIGHT OF NOT LESS THAN 3 INCHES. IT SHALL BE CUT INTO STRIPS OF NOT LESS THAN 3 FEET AND NOT OVER 6 FT. WITH A UNIFORM WIDTH OF NOT OVER 24 INCHES.
- SOD SHALL BE CUT TO A DEPTH EQUAL TO THE GROWTH OF THE FIBROUS ROOTS BUT IN NO CASE LESS THAN 1 INCH.
- SOD SHALL BE DELIVERED TO THE JOB WITHIN 24 HOURS AFTER BEING CUT AND SHALL BE INSTALLED WITHIN 48 HOURS AFTER BEING CUT.
- BEFORE SOD IS PLACED, THE SOD BED WILL HAVE BEEN EXCAVATED TO SUCH A DEPTH THAT WHEN THE SOD IS IN PLACE THE TOP OF THE SOD WILL BE FLUSH WITH THE SURROUNDING GRADE.
- NO SOD SHALL BE PLACED WHEN THE TEMPERATURE IS BELOW 32 DEGREES F. NO FROZEN SOD SHALL BE PLACED NOR SHALL ANY SOD BE PLACED ON FROZEN SOIL. WHEN SOD IS PLACED BETWEEN THE DATES OF JUNE 1ST AND OCTOBER 15TH, IT SHALL BE COVERED IMMEDIATELY WITH A STRAW MULCH 1 INCH THICK (LOOSE MEASUREMENT).
- AFTER LAYING, THE SOD SHALL BE WATERED THOROUGHLY AND TAMPED WITH APPROVED SOD TAMPERS SUFFICIENTLY TO BRING THE SOD INTO CLOSE CONTACT WITH THE SOD BED AND INSURE TIGHT JOINTS BETWEEN THE SECTIONS OR STRIPS.
- THE CONTRACTOR SHALL KEEP ALL SODDED AREAS INCLUDING SUBGRADE, THOROUGHLY MOIST FOR 30 DAYS AFTER SODDING.
- THE CONTRACTOR SHALL REPAIR ANY AREAS DAMAGED FOLLOWING INSTALLATION AS DIRECTED BY THE ENGINEER. SOD SHALL BE IN PLACE AT LEAST 30 DAYS BEFORE FINAL ACCEPTANCE.

**SEEDING**

- GRASS SEED SHALL BE FRESH, CLEAN, DRY, NEW-CROP SEED COMPLYING WITH THE ASSOCIATION OF OFFICIAL SEED ANALYSTS' "RULES FOR TESTING SEEDS" FOR PURITY AND GERMINATION TOLERANCES.
- ALL AREAS TO BE SEEDED SHALL RECEIVE NO LESS THAN FIVE POUNDS OF SEED PER ONE THOUSAND SQUARE FEET. APPLY SEED AND PROTECT WITH STRAW MULCH AS REQUIRED FOR NEW LAWNS. GRASS SEED MIX SHALL CONSIST OF THE FOLLOWING:

PROPORTION	NAME	MIN. % GERM.	MIN. % PURE SEED	MAX. % WEED SEED
30%	KENTUCKY BLUEGRASS (POA PRATENSIS)	80	85	0.50
30%	CREEPING RED FESCUE (FESTUCA RUBRA)	85	98	0.50
20%	PERENNIAL RYE GRASS (LOLIUM PERENNE)	90	98	0.50
20%	ANNUAL RYEGRASS (LOLIUM MULTIFLORUM)	85	92	1.00

**DETENTION BASIN SEEDING**

- GRASS SEED SHALL BE FRESH, CLEAN, DRY, NEW-CROP SEED COMPLYING WITH THE ASSOCIATION OF OFFICIAL SEED ANALYSTS' "RULES FOR TESTING SEEDS" FOR PURITY AND GERMINATION TOLERANCES.
- ALL AREAS TO BE SEEDED SHALL RECEIVE NO LESS THAN FIVE POUNDS OF SEED PER ONE THOUSAND SQUARE FEET. APPLY SEED AND PROTECT WITH STRAW MULCH AS REQUIRED FOR NEW LAWNS. GRASS SEED MIX SHALL CONSIST OF THE FOLLOWING:

PROPORTION	NAME	MIN. % GERM.	MIN. % PURE SEED	MAX. % WEED SEED
30%	KENTUCKY BLUEGRASS (POA PRATENSIS)	80	85	0.50
40%	KENTUCKY 31 FESCUE (FESTUCA ARUNDINACEA VAR. KY 31)	85	98	0.50
30%	PERENNIAL RYE GRASS (LOLIUM PERENNE)	90	98	0.50

**PLANTING SCHEDULE**

- ALL PLANTING IS RECOMMENDED TO BE DONE WITHIN THE FOLLOWING DATES. WHEN PLANTING OUTSIDE THESE DATES, WRITTEN DOCUMENTATION SHALL BE PROVIDED THAT SURVIVAL OR REPLACEMENT WILL BE ENSURED. NO PLANTING SHALL BE DONE IN FROZEN SOIL.

NORMAL PLANTING SEASONS	SPRING	FALL
ALL TREES AND SHRUBS	MARCH 15-MAY 15	OCTOBER 1-DECEMBER 1
EVERGREENS	APRIL 1-MAY 15	OCTOBER 1-NOVEMBER 15
GROUNDCOVERS	APRIL 1-JUNE 1	WHEN SOD IS WORKABLE
SEED AND MULCH	APRIL 1-MAY 15	OCTOBER 1-NOVEMBER 15



Copyright: Glaus, Pyle, Schomer, Burns & DeHaven, Inc. 2021

**NOT FOR  
CONSTRUCTION**

DATE	REMARKS

CONTRACT DATE:  
BUILDING TYPE: END 20  
PLAN VERSION: JUNE 2021  
BRAND DESIGNER:  
SITE NUMBER:  
STORE NUMBER:  
PA/PM: AB  
DRAWN BY.: JRA  
JOB NO.: 2021188.12



END 20

**LANDSCAPE  
NOTES**







**L-001**

PLOT DATE:





**NOT FOR CONSTRUCTION**



DATE	REMARKS

CONTRACT DATE:  
 BUILDING TYPE: END 20  
 PLAN VERSION: JUNE 2021  
 BRAND DESIGNER:  
 SITE NUMBER:  
 STORE NUMBER:  
 PA/PM: AB  
 DRAWN BY.: JRA  
 JOB NO.: 2021188.12

**TACO BELL**  
 West Plane Street  
 Bethel, OH 45013



END 20

LANDSCAPE DETAILS

**L-501**

PLOT DATE: