EQUIPMENT SCHEDULE

ITEM#	QTY	DESCRIPTION	MANUFACTURER	MODELNO.
01.11	1	CUP DISPENSER, GOURMET EZ FIT PORTION	SAN JAMAR	SJ-C2010C-BK
01.12A	3	LICORICE XPRESS STAND NAPKIN DISPENSER	TORK	POL-6332000-BK
01.23	1	BK BEVERAGE COUNTER, 9'-8"	H&K	52375-1
01E.03	1	DISPENSER, KETCHUP COUNTERTOP (BK)	SERVER	SER-ECD07500
02A.03	4	TWO TIER UNDER COUNTER SHELVING	INTERMETRO	1848NK3
02C.01	1	BK STRAW HOLDER	H&K	52201
02C.02	1	BK LID ORGANIZER S-M-L	H&K	52200
02C.03	1	BK UNIVERSAL CONDIMENT DISPENSER	H&K	52014
04.03	1	BK 24 IN POS DT TABLE W/O CASH DRAWER	H&K	52169
04.90	1	POS DRIVE THRU TABLE 24"	H&K	52896
05.04	1	WORK STATION, DRIVE THRU 48"	INTERMETRO	BKROC2448DT
05A.02	1	30" X 24" CASHIER CABINET	H&K	52241
06.00	1	CART, BEVERAGE STATION DRIVE THRU 1-2-3	INTERMETRO	INM-BKBC1430
10.01	1	12 V SODA SYSTEM W/ICE	LANCER CORP.	LAN-85-4562-H123
11.01	1	SODA SYSTEM, DROP IN 8V W/ICE	LANCER CORP.	85-2378T-124
11.02	3	CARBONATOR	LANCER CORP.	85-1923-00
11.05	1	STAND 25X25 FOR 8-V MACHINE	LANCER CORP.	LAN-840058-BK (LAN-84-1005)
14.08	1	BASE CABINET, 3-BRL	BY OWNER	-
14.17	1	FROZEN COKE MACHINE	BY OWNER	-
15.10	1	SHAKE & SOFT SERVE (3PH)	BY OWNER	-
15.15	1	S/S CABINET BRUSHES	H&K	8047
16.08	1	ICE BIN, 900 LB CAPACITY	HOSHIZAKI	B-900SF
16.18	1	ICE MACHINE CHASE	H&K	BZM342
16.63	1	CUBER, 1130 LB CAPACITY REMOTE AIR COOLED 1PH	HOSHIZAKI	KM-1301SRJ
16.73	1	ICE MACHINE 1425LB	MANITOWOC	IY-F1400C
17.00	1	COFFEE/TEA BREWER	BUNN	ITCB
17B.00	4	TEA DISPENSER	BUNN	TDO-N-3.5
21.04A	1	FRONT PREP TABLE "A" (60") 8-PAN	H&K	52616-11A
21.85	1	BK MIDDLE PREP TABLE (BUN RACK)	H&K	52332-10
21.87	1	BK MOBILE TOASTER TABLE 20IN	H&K	52290-10
21.89	1	BK REAR PREP TABLE (REFRIG UNDERCOUNTER) 5 PANS	H&K	52419-10
21.94B	2	SHELF EXTENSION FOR 2 AMA-OC24	H&K	54017
21C.32	1	BK EXPEDITER STATION	H&K	52622
21C.45	1	BK BEVERAGE REFRIGERATOR-SLIME LINE	H&K	52614-2
23.14	1	7'-7" BROILER/OVEN HOOD ROC STORES	H&K	52415-1
24.00	1	BROILER	DUKE	FBB-NO-120

EQUIPMENT SCHEDULE

ITEM#	QTY	DESCRIPTION	MANUFACTURER	MODELNO.
25.00	1	FREEZER, REACH-IN LH	TRUE	T23F-2-MC
26.14	1	BK MEAT FREEZER 50"	H&K	52471-1
30.16	1	UNIVERSAL FRY DUMP STATION S/SNEXT GENERATION	H&K	52382-6E
31.03	1	4 VAT FRYER	FRYMASTER	4FQG30U
32.06	1	BK FRY FREEZER W/FRY BASKET HOLDER	H&K	52474-2
32C.03	1	UNDERCOUNTER REFRIG	SILVER KING	SK-RS/SUS10
33.17	1	6'-4" FRYER ROC WALL HUNG HOOD	H&K	52440-1
36.02	1	COMBI OVEN STEAMER ELECTRIC	BLODGETT	BLCT-6E
38.08	1	36X30IN MOBILE WORK TABLE	H&K	52209
38.38	1	WORK TABLE 20IN X 30IN X 34IN W BACK SPLASH AND SHELF	H&K	52928
40.00	1	WALK-IN COOLER/FREEZER	KOLPAK	CUSTOM
41.02	1	18Wx54L WIRE SHELF 4 TIER	INTERMETRO	INM-1854NK3
41.03	1	24Wx36L WIRE SHELF 4 TIER	INTERMETRO	INM-2436NK3
41.04	3	24Wx42L WIRE SHELF 4 TIER	INTERMETRO	INM-2442NK3
41.05	1	24Wx48L WIRE SHELF 4 TIER	INTERMETRO	INM-2448NK3
41.39	1	BOWTIE DUNNAGE RACK 22x30	INTERMETRO	HP2230PDMB
41.40	8	BOWTIE DUNNAGE RACK 22x36	INTERMETRO	HP2236PDMB
42.01	2	18Wx48L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-1848NC
42.02	2	18Wx54L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-1854NC
42.04	2	24Wx42L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2442NK3
42.05	3	24Wx48L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2448NK3
42.06	1	24Wx54L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2454NC
42.14	1	24Wx60L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2460NK3
43.00	1	SHELVING SMART WALL	INTERMETRO	BKSWP8446
43.03	1	SHELVING SMART WALL	INTERMETRO	BKSWP8446DBL
50.02	2	MICROWAVE OVEN	AMANA	AOC24
51.13	2	PHU - 3X4	DUKE	HS2-342086T2R
51B.13	1	PHU - 2X4	DUKE	HS2-24208T1R
52.00	1	EGG COOKER	ROUND UP	ES-1200
53.13	1	REFRIG. UNDERCOUNTER	TURBO AIR	MUR-28-N
55.03	2	VERTICAL CONTACT TOASTER	ANTUNES	BKT-2V
60.06	1	BK 3-COMPARTMENT SINK 105"	H&K	52019-1
61.04	1	BK 1-COMPARTMENT SINK W/LH DRN BOARD, 46"	H&K	52015X
62.13	3	PEDESTAL HAND SINK	ADVANCE TABCO	7-PS-96
73.01	1	WATER FILTER	SELECTO	SEL-80-6202

BUILDING LAYOUT DRAWN FROM ARCHITECTURAL

DATE OF DRAWING: 12.20.21

GENERAL CONTRACTOR NOTES

1. ALL EQUIPMENT SHALL BEAR THE N. S. F. SEAL.
2. ALL PORTIONS OF WORK SHALL BE DONE IN ACCORDANCE WITH N. S. F. STANDARDS, APPLICABLE LOCAL, STATE AND NATIONAL CODES, ORDINANCES AND STANDARDS.
3. NOTIFY H&K's PROJECT MANAGER IMMEDIATELY IF COMPLIANCE WITH A LOCAL, STATE OR NATIONAL CODE IS IN CONFLICT WITH THESE DRAWINGS.
4. NOTIFY H&K's PROJECT MANAGER IMMEDIATELY IF THESE DRAWINGS DIFFER FROM THE ARCHITECTURAL BUILDING DRAWINGS.
5. G. C. TO VERIFY THE REQUIREMENTS FOR ITEMS NOT PROVIDED BY H&K.
6. ITEMS MAY BE LISTED IN THE EQUIPMENT SCHEDULE BUT NOT SHOWN ON THE DRAWING.
7. H&K's DRAWINGS INCLUDE ONLY THOSE REQUIREMENTS FOR SPECIFIC KITCHEN EQUIPMENT PROVIDED BY H&K. REFER TO THE ARCHITECTURAL BUILDING DRAWINGS FOR LOCATIONS OF OTHER REQUIREMENTS. H&K's ASSUMES NO RESPONSIBILITY FOR EQUIPMENT SUPPLIED BY OTHERS OR EXISTING. (VERIFY BY RESPECTIVE TRADES).
8. G. C. TO SET REMOTE CONDENSING UNIT(S) ON THE BUILDING ROOF. REFER TO MASTER DRAWINGS FOR DETAILS.
9. G. C. TO PROVIDE AND INSTALL EQUIPMENT STANDS AND PITCH PANS FOR BUILDING ROOF MOUNTED CONDENSING UNIT(S).
10. G. C. SHALL PROVIDE FOR ACCESS FOR THE EQUIPMENT TRUCK TO WITHIN 10' (3m) OF THE BUILDING DOOR(S) PRIOR TO THE ARRIVAL OF THE EQUIPMENT TRUCK AT THE RESTAURANT.
11. "BY OWNER" SUPPLIED EQUIPMENT WILL BE LISTED IN THE EQUIPMENT SCHEDULE ON SHEET 1.
12. UTILITY AMOUNTS ARE ACTUAL MAXIMUM OPERATING AMOUNTS FOR EQUIPMENT. ALLOW FOR OVERAGE WHEN SIZING PANEL BOX.
13. ALL DIMENSIONS ARE FROM FINISHED WALLS, COLUMN CENTERLINES AND FINISHED FLOOR. DIMENSIONS ABOVE FINISHED FLOOR TO CENTERLINE OF ROUGH-IN.
14. ALL UTILITY MATERIALS NECESSARY TO PERFORM COMPLETE CONNECTION OF EQUIPMENT WILL BE DONE BY ELECTRICAL, PLUMBING OR MECHANICAL CONTRACTOR.
15. ALL DRAWINGS PREPARED BY H&K ARE THE PROPERTY OF H&K. REPRODUCTION, DISTRIBUTION OR ALTERATION WITHOUT WRITTEN AUTHORIZATION FROM H&K IS PROHIBITED.

DISCLAIMER

IMPORTANT NOTICE: TO ALL CONTRACTORS AND TRADES

THESE DRAWINGS HAVE BEEN PREPARED BY H&K INTERNATIONAL AT THE REQUEST OF THE OWNER. THE INFORMATION PROVIDED MAY BE TIME SENSITIVE AND IS SUBJECT TO CHANGE AS REVISIONS TO THE EQUIPMENT LISTING MAY HAVE OCCURRED AFTER THE RELEASE OF THIS DRAWING.

PLEASE VERIFY WITH THE OWNER THAT THE DRAWING PROVIDED REFLECTS THE MOST CURRENT INFORMATION AVAILABLE. ALSO REQUEST A LIST OF ALL OWNER SUPPLIED EQUIPMENT AND EQUIPMENT SUPPLIED BY 'OTHERS' WITH DETAILS AND SPECIFICATIONS THAT APPLY TO THIS EQUIPMENT.

H&K INTERNATIONAL DOES NOT ASSUME RESPONSIBILITY FOR EQUIPMENT SUPPLIED BY OTHER PARTIES.

H&K INTERNATIONAL 103014

SYMBOL LEGEND

- RECEPTACLES
- JUNCTION BOX
- EXHAUST DUCT ABOVE HOOD
- GAS LINE
- WATER LINE
- DRAIN LINE
- FLOOR SINK
- FLOOR DRAIN
- EXISTING FULL WALL
- EXISTING LOW WALL
- NEW FULL WALL
- NEW LOW WALL
- OPTIONAL EQUIPMENT
- NEW EQUIPMENT ON EQUIPMENT PLAN
- RELOCATED EQUIPMENT ON EQUIPMENT PLAN
- EXISTING EQUIPMENT
- EQUIPMENT ON ROUGH-IN PLAN
- EXISTING TRUSSES
- SERVICE AREA
- NEW MENU BOARD VALANCE

H & K DALLAS INC.
2200 SKYLINE DR
MESQUITE, TEXAS 75149
(214) 818-3500

REVISION	DATE	BY
REMOVED ITEM 52976 (REFRIGERATED CHICKEN BATTER STATION)	12APR22	EN
UPDATED AS PER NEW X-BASE -	24MAR22	EN
UPDATED AS PER NEW MARKUPS -	16FEB22	EN

DATE: 20DEC21
DRAWN: EN
CHECKED: INT
SCALE: SEE PLAN

TITLE: KITCHEN_LAYOUT - SEWELL, NJ

THESE DRAWINGS SPECIFICATIONS ARE THE PROPERTY OF H&K AND SHALL NOT BE REPRODUCED OR COPIED WITHOUT H&K's WRITTEN PERMISSION.

CUSTOMER: BURGER-KING CORPORATION

STORE NO: 00824

SHEET: 2 OF 4

SHEET NO: K-2C

DRAWING FILE NAME: BK00824 K-C 04.12.22