Interior Building Finishes

Item	Description	Finish	Supplier FCC	Supplier Others	Installer FCC	Installer Others	BK Codes	Notes
B3D	Tile at Back of Drink Station	Manufacturer: Eurowest; Item: TCG2424027SQ; Color: Simply Gray Honed (rectified); Size: 24"x24"; Grout: CBP, Fusion Pro Single Comp., #335 Winter Gray 1/16"		X		X	CT-25G, GR-15G	Install: Horizontal stacked bond to floor - no base tile. Eurowest Contact: BK@eurowest.com Rep: Joy Klein, ph. 813.334.3302 *Additional supplier(s) available per BKC Finish Schedule*. Grout Note: Prolite® Premium Large Format Tile Mortar, Rapid Set
B4A	Back of House	Manufacturer: Marlite; Series: FRP Symmetrix, A916 G312R; Panel Color: White/Black Core, No Top Coat (Grey Score Line); Trim: FRPMOLD BK Nickel Anodized; Edge Trim: A570, 8' lengths; O/S Trim: A560, 8' lengths; I/S Trim: A551, 8' lengths; Panel Sizes: 4'x8' or 4' x 10'; Sealant: Gray Sealant 509, WM46651		X		X	FRP-1G, TR-3G	Marlite Cust. Serv.: 330.343.6621 Rep: Anita Craig, acraig@marlite.com. **Option:** White Subway Tile, See B9A
B5A	Wainscot (Lower Wall Surface)	Supplier/Item: Marlite, Allure Panel; Color: Nevamar, WF001-T Macchiato; Panel Size: 4' x 4'; Trim: Match to Marlite Macchiato	X			X	WP-2G	Install: Wood grain runs vertically. *Panel Qty (4' x 4'): 40 Panels; Divider Trim AP-30N (9'): 207 LF; Edge Trim AP-28N (9'): 36 LF; I/C AP-32N (9'): 54 LF; O/C AP-34N (9'): 36 LF*
		Adhesive: By Others		X		X		
B6A	Chair Rail	Style: FDBC084; Material: Solid Surface, Corian, Deep Nocturne; Size: 1" x 2"	X			X	SS-8G	Qty. (12'): 108 LF
B7A	Main Wall Finish	Manufacturer: Paint, PPG; Primer: 6-4900XI Speedhide Zero VOC Int. Latex Satin; Paint: 6-4310XI Speedhide Zero VOC Int Latex Eggshell; Color: Ashen, PPG1023-3		X		X	P-15G	PPG Contact: Daniel Huber, 713.702.3636, daniel.huber@ppg.com *Additional supplier(s) available per BKC Finish Schedule*
B8A	Accent Brick Finish	Manufacturer: Pine Hall Brick; Series: Thin Clad Veneer; Color: Old Irvington; Size: 7 5/8" x 3 5/8" x 1/2"; Grout: Lehigh Hanson, B-12C/B-12, Gingerbread, Ohio River Masonry Sand		X		X	BR-2G, EGR-1G	Install: Horizontal, 50% offset, include base tile to match floor. Pine Hall Contact: Preston Steele E-mail: psteele@pinehallbrick.com *Additional supplier(s) available*. Grout Contact: Carl Applebaum, 502-523-2666, carl.applebaum@lehighhanson.com
B8B	Wall Tile Corner Trim	Manufacturer: Schluter Systems; Finish: Satin Nickel Anodized Alum.; Style: QUADEC Q100AT 3/8"		X		X	TR-1	Contact: 786-858-0010 Rep: Rosanna Ruiz
B9A	Menuboard & Service Area Back Wall	Manufacturer: Eurowest; Item: 1318glosswht1; Color: White, Glossy; Size: 3" x 12"; Grout: CBP, Fusion Pro Single Comp., #543 Driftwood, 1/8"Th		X		X	CT-31G, GR-18G	Install: Horizontal, 50% offset. Eurowest Contact: BK@eurowest.com Rep: Joy Klein, ph. 813.334.3302 *Additional supplier(s) available*
B10A	Window Sills	Material: Solid Surface Corian, Deep Nocturne; Thickness: 1/2"	X			X	SS-8G	Qty. (12'): 72 LF
B11A	Interior Doors and Frames	Finish: Laminate, Nevamar WK0017T Venerable Old Oak (grain); Frames: Clear Anodized Aluminum; Finish: Paint, PPG; Primer: 90-712 Pitt Tech; Paint: 6-1510XI, Speedhide Int/Ext WB Alkyd Semi Gloss; Color: Ashen, PPG1023-3		X		X	PL-9G, P-4G	Install: Wood Grain Runs Vertically. Nevamar Contact: 877.726.6526 Rep: John Trulock. PPG Contact: Daniel Huber, 713.702.3636, daniel.huber@ppg.com *Additional supplier(s) available per BKC Finish Schedule*
B11B	Kitchen Door & Frame (Kitchen Side Only)	Not Applicable						
B12A	Open Truss Ceiling & BKoT Upper Wall Finish	Manufacturer: PPG; Primer: 17-921 Seal Grip; Paint: PPG 6-417 Speedhide Zero VOC Int. Latex Eggshell; Color: Cabin Fever, PPG 1021-7		X		X	P-6G	PPG Contact: Daniel Huber, 713.702.3636, daniel.huber@ppg.com *Additional supplier(s) available per BKC Finish Schedule*
B12B	Acoustical Ceiling Tile	Item: Armstrong, Cortega PN91311, #770; Size: 2' x 2' x 5/8"; Tile Color: Custom Color, Sepia; Edge: Flat In-Lay 15/16; Grid: Prelude 15/16", Exposed Tee; Grid Color: Custom Color, Sepia		X		X	ACT-1G	**Option to B12A Open Truss**. Contact: 252-214-4426 Rep: Cheryl Smith
B12C	Kitchen Acoustical Ceiling Tile	Item: Armstrong, Kitchen Zone #BP672; Size: 2' x 4' x 1/2"; Tile Color: White; Grid: Prelude 15/16" Exposed Tee; Grid Color: White		X		X	ACT-2G	Contact: 252-214-4426 Rep: Cheryl Smith *Additional supplier(s) available per BKC Finish Schedule*
B12D	Acoustical Ceiling Tile (Play Area, if applicable)	Not Applicable						
B12E	Drywall Ceiling	Finish: Paint, PPG; Primer: 6-4900XI Speedhide Zero VOC Int Latex Satin; Paint: 6-4310XI Speedhide Zero VOC Int. Latex Eggshell; Color: White on White 30GY 88/014		X		X	P-5G	Refer to RCP for GC installed recessed light locations. PPG Contact: Daniel Huber, 713.702.3636, daniel.huber@ppg.com *Additional supplier(s) available per BKC Finish Schedule*
B13A	Soffits	Finish: Paint, PPG; Primer: 6-4900XI Speedhide Zero VOC Int Latex Satin; Paint: 6-4310XI Speedhide Zero VOC Int. Latex Eggshell; Color: White on White 30GY 88/014		X		X	P-5G	Refer to RCP for GC installed recessed light locations. PPG Contact: Daniel Huber, 713.702.3636, daniel.huber@ppg.com *Additional supplier(s) available per BKC Finish Schedule*
B13B	Drywall Transition Reveal Trim	Manufacturer: Trim-Tex Drywall Products; Item: Silver Architectural Reveal Bead, AS5110S; Size: 1/2" x 1/2" x 10' lengths		X		X	TR-01G	If 6" x 6" perimeter soffit is omitted from BKoT bldg, this trim must be used between P-15G main wall finish and P-6G Upper Wall Finish

IMPORTANT

WRITTEN DIMENSIONS HAVE PRECEDENCE OVER SCALE IN ALL CASES.

DO NOT SCALE OFF PLANS. CONTACT FCC COMMERCIAL FURNITURE'S REPRESENTATIVE TO VERIFY ANY QUESTIONABLE DIMENSIONS AT TELEPHONE # 800.322.7328

THE GENERAL CONTRACTOR MUST VERIFY ALL BUILDING DIMENSIONS, EQUIPMENT, FURNITURE PLACEMENT, UTILITY LOCATIONS, AND CONDITIONS AT THE JOB SITE.

THE GENERAL CONTRACTOR MUST NOTIFY FCC COMMERCIAL FURNITURE INC OF ALL DISCREPANCIES AND/OR REQUIRED ADJUSTMENTS PRIOR TO STARTING WORK.

FCC COMMERCIAL FURNITURE HAS PREPARED THESE DOCUMENTS AS ACCURATELY AS POSSIBLE WITH THE ARCHITECTURAL INFORMATION PROVIDED. DUE TO LACK OF ACCURATE AND AND COMPLETE DIMENSIONED ARCHITECTURAL PLANS, OWNER UNDERSTANDS THAT ADJUSTMENTS TO THE FINAL LOCATIONS OF EQUIPMENT AND/OR FURNITURE PLACEMENT MAY BE REQUIRED AT THE OWNER'S EXPENSE DUE TO DISCREPANCIES BASED ON ACTUAL JOB SITE DIMENSIONS AND CONDITIONS.

REFER TO ARCHITECTURAL OR ENGINEER DRAWINGS FOR COMPLETE AND ACCURATE DIMENSIONS OF BUILDING STRUCTURE.

THESE CONTRACT DOCUMENTS AND THE INFORMATION THEY CONTAIN ARE THE PROPERTY OF FCC COMMERCIAL FURNITURE INC., ROSEBURG, OREGON, 97470.

ALL PREPARED CONTRACT DOCUMENTS MAY NOT BE COPIED, REPRODUCED, USED OR IMPLEMENTED IN ANY WAY, IN PART OR IN WHOLE, WITHOUT THE EXPRESS WRITTEN CONSENT OF FCC COMMERCIAL FURNITURE INC.

ANY UNAUTHORIZED USE OF THESE PLANS WILL RESULT IN PAYMENT DUE FOR SERVICES RENDERED BY FCC COMMERCIAL FURNITURE INC.

ANY DEVIATIONS FROM THESE DRAWINGS FOR ANY REASON SHALL NOT BE DONE WITHOUT CONSENT OF FCC COMMERCIAL FURNITURE INC, IN ADVANCE, IN WRITING. FCC COMMERCIAL FURNITURE IS NOT RESPONSIBLE FOR DEVIATIONS, CHANGES, ADDITIONS, OR DELETIONS NOT REVIEWED AND APPROVED IN ADVANCE BY FCC COMMERCIAL FURNITURE INC.

THESE DOCUMENTS REFLECT SPECIFIC SEATING AND DECOR EQUIPMENT ORDERED OF DATE SHOWN BELOW.

CLIENT:

BURGER KING

Burger King
322 Pottstown Ave.
Pennsburg, PA 18073
Decor: Garden Grill
Building Type: ROC-2502T

CUSTOMER
Ampler Development

SHEET TITLE:
SPECIFICATIONS

WORK ORDER NUMBER:

FINALS BY:

DRAWN BY:
Joe Logsdon

SCALE:
NTS

ORIGINAL DATE:
December 7, 2021

PLOT DATE:
March 14, 2022

PROJECT #:
22834-001

SHEET #:
D8.3