

EQUIPMENT SCHEDULES								
ITEM#	QTY	DESCRIPTION	MANUFACTURER	MODELNO.				
24.00	1	BROILER	DUKE	FBB-NO-120				
26.14	2	BK MEAT FREEZER 50"	H&K	52471-1				
30.17	1	UNIVERSAL FRY DUMP STATION S/SNEXT GENERATION	H&K	52399-6E				
31.03	1	4 VAT FRYER	FRYMASTER	4FQG30U				
32.06	1	BK FRY FREEZER W/FRY BASKET HOLDER	H&K	52474-2				
32C.03	1	UNDERCOUNTER REFRIG	SILVER KING	SK-RS/SUS10				
33.22	1	9'-0" FRYER/OVEN HOOD FREE STANDING	H&K	52571-1				
36.02	1	COMBI OVEN STEAMER ELECTRIC	BLODGETT	BLCT-6E				
38.08	1	36X30IN MOBILE WORK TABLE	H&K	52209				
38.38	1	WORK TABLE 20IN X 30IN X 34IN W BACK SPLASH AND SHELF	H&K	52928				
40.00	1	WALK-IN COOLER/FREEZER	KOLPAK	CUSTOM				
41.01	1	18Wx48L WIRE SHELF 4 TIER	INTERMETRO	INM-1848NK3				
41.03	1	24Wx36L WIRE SHELF 4 TIER	INTERMETRO	INM-2436NK3				
41.04	1	24Wx42L WIRE SHELF 4 TIER	INTERMETRO	INM-2442NK3				
41.05	2	24Wx48L WIRE SHELF 4 TIER	INTERMETRO	INM-2448NK3				
41.36	1	24Wx30L WIRE SHELF 4 TIER	INTERMETRO	INM-2430NK3				
41.39	1	BOWTIE DUNNAGE RACK 22x30	INTERMETRO	HP2230PDMB				
41.40	8	BOWTIE DUNNAGE RACK 22x36	INTERMETRO	HP2236PDMB				
42.01	4	18Wx48L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-1848NC				
42.04	2	24Wx42L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2442NC				
42.05	4	24Wx48L WIRE SHELF 4 TIER DRY STORAGE	INTERMETRO	INM-2448NC				
43.00	1	SHELVING SMART WALL	INTERMETRO	BKSWP8446				
43.03	1	SHELVING SMART WALL	INTERMETRO	BKSWP8446DBL				
50.02	2	MICROWAVE OVEN	AMANA	AOC24				
51.13	2	PHU - 3X4	DUKE	HS2-342086T2R				
51B.13	1	PHU - 2X4	DUKE	HS2-242084T1R				
52.00	1	EGG COOKER	ROUND UP	ES-1200				
53.13	1	REFRIG. UNDERCOUNTER	TURBO AIR	MUR-28-N				
54.01	1	REFRIGERATED CHICKEN BATTER STATION	H&K	52976				
55.03	2	VERTICAL CONTACT TOASTER	ANTUNES	BKT-2V				
60.06	1	BK 3-COMPARTMENT SINK 105"	H&K	52019-1				
61.15	1	BK 1-COMPARTMENT SINK W/LH DRN BOARD, 46"	H&K	52015X-1				
62.13	3	PEDESTAL HAND SINK	ADVANCE TABCO	7-PS-96				
73.01	1	WATER FILTER	SELECTO	SEL-80-6202				



ВУ	JAR	dΟ	NЭ
REVISION	UPDATED AS PER NEW MARKUPS -	UPDATED AS PER NEW MARKUPS -	UPDATED AS PER NEW MARKUPS -
DATE	16FEB22	15FEB22	10FEB22
DATE: 11JAN22	DRAWN: OP	CHECKED: JAR	SCALE: SEE PLAN
TITLE:	KITCHEN_LAYOUT	PENNSBURG, PA	THESE DRAWINGS SPECIFICATIONS ARE THE PROPERTY OF H&K AND SHALL NOT BE REPRODUCED OR CODIED WITHOUT H&K'S WRITTEN PERMISSION
1			

DISCLAIMER

BUILDING LAYOUT DRAWN

FROM ARCHITECTURAL

DATE OF DRAWING: 01.11.22

GENERAL CONTRACTOR NOTES

ALL PORTIONS OF WORK SHALL BE DONE IN ACCORDANCE WITH N. S. F. STANDARDS, APPLICABLE LOCAL, STATE AND NATIONAL CODES, ORDINANCES AND STANDARDS.

NOTIFY H&K's PROJECT MANAGER IMMEDIATELY IF COMPLIANCE WITH A LOCAL,

NOTIFY H&K's PROJECT MANAGER IMMEDIATELY IF THESE DRAWINGS DIFFER FROM

STATE OR NATIONAL CODE IS IN CONFLICT WITH THESE DRAWINGS.

G. C. TO VERIFY THE REQUIREMENTS FOR ITEMS NOT PROVIDED BY H&K.

ITEMS MAY BE LISTED IN THE EQUIPMENT SCHEDULE BUT NOT SHOWN ON THE

H&K's DRAWINGS INCLUDE ONLY THOSE REQUIREMENTS FOR SPECIFIC KITCHEN EQUIPMENT PROVIDED BY H&K. REFER TO THE ARCHITECTURAL BUILDING

G. C. TO SET REMOTE CONDENSING UNIT(S) ON THE BUILDING ROOF. REFER TO

10' (3m) OF THE BUILDING DOOR(S) PRIOR TO THE ARRIVAL OF THE EQUIPMENT

11 "BY OWNER" SUPPLIED EQUIPMENT WILL BE LISTED IN THE EQUIPMENT SCHEDULE

12 UTILITY AMOUNTS ARE ACTUAL MAXIMUM OPERATING AMOUNTS FOR EQUIPMENT.

14 ALL UTILITY MATERIALS NECESSARY TO PERFORM COMPLETE CONNECTION OF

15 ALL DRAWINGS PREPARED BY H&K ARE THE PROPERTY OF H&K. REPRODUCTION,

DISTRIBUTION OR ALTERATION WITHOUT WRITTEN AUTHORIZATION FROM H&K IS

13 ALL DIMENSIONS ARE FROM FINISHED WALLS, COLUMN CENTERLINES AND FINISHED FLOOR. DIMENSIONS ABOVE FINISHED FLOOR TO CENTERLINE OF ROUGH-IN.

EQUIPMENT WILL BE DONE BY ELECTRICAL, PLUMBING OR MECHANICAL CONTRACTOR.

DRAWINGS FOR LOCATIONS OF OTHER REQUIREMENTS. H&K's ASSUMES NO RESPONSIBILITY FOR EQUIPMENT SUPPLIED BY OTHERS OR EXISTING.

9 G. C. TO PROVIDE AND INSTALL EQUIPMENT STANDS AND PITCH PANS FOR

10 G. C. SHALL PROVIDE FOR ACCESS FOR THE EQUIPMENT TRUCK TO WITHIN

ALL EQUIPMENT SHALL BEAR THE N. S. F. SEAL.

THE ARCHITECTURAL BUILDING DRAWINGS.

(VERIFY BY RESPECTIVE TRADES).

MASTER DRAWINGS FOR DETAILS.

TRUCK AT THE RESTAURANT.

ON SHEET 1.

PROHIBITED.

BUILDING ROOF MOUNTED CONDENSING UNIT(S).

ALLOW FOR OVERAGE WHEN SIZING PANEL BOX.

THESE DRAWINGS HAVE BEEN PREPARED BY H&K INTERNATIONAL AT THE REQUEST OF THE OWNER. THE INFORMATION PROVIDED MAY BE TIME SENSITIVE AND IS SUBJECT TO CHANGE AS REVISIONS TO THE EQUIPMENT LISTING MAY HAVE OCCURRED AFTER THE RELEASE OF THIS DRAWING.

IMPORTANT NOTICE: TO ALL CONTRACTORS AND TRADES

PLEASE VERIFY WITH THE OWNER THAT THE DRAWING PROVIDED REFLECTS THE MOST CURRENT INFORMATION AVAILABLE. ALSO REQUEST A LIST OF ALL OWNER SUPPLIED EQUIPMENT AND EQUIPMENT SUPPLIED BY 'OTHERS' WITH DETAILS AND SPECIFICATIONS THAT APPLY TO THIS EQUIPMENT.

H&K INTERNATIONAL DOES NOT ASSUME RESPONSIBILITY FOR EQUIPMENT SUPPLIED BY OTHER PARTIES.

H&K INTERNATIONAL 103014

SYMBO	OL LEGEND	
\rightarrow	RECEPTACLES	EXISTING FULL WALL
J	JUNCTION BOX	 EXISTING LOW WALL
	EXHAUST DUCT ABOVE HOOD	NEW FULL WALL
_	GAS LINE	NEW LOW WALL
<u> </u>	WATER LINE	 OPTIONAL EQUIPMENT
+	DRAIN LINE	 NEW EQUIPMENT ON EQUIPMENT PLAN
	FLOOR SINK	RELOCATED EQUIPMENT
	FLOOR DRAIN	ON EQUIPMENT PLAN
		 EXISTING EQUIPMENT
		 EQUIPMENT ON ROUGH-IN PLAN
		 EXISTING TRUSSES
		 SERVICE AREA
		 NEW MENU BOARD VALANCE

Y-KING ATION

及及

100 J

SUR ORI

SHEET NO:

.. 0

00825